CAASL Doc No: SLCAIS 031

Democratic Socialist Republic of Sri Lanka



Civil Aviation Authority of Sri Lanka

Implementing Standards

(Issued under Section 120, Civil Aviation Act No. 14 of 2010)

Title: Compliance to Annex 4 – Aeronautical Charts

IS Reference Code: IS-04-All Date of Issue: 28th October 2024

Pursuant to Section 120 of the Civil Aviation Act No.14 of 2010 which is hereinafter referred to as the CA Act, Director General of Civil Aviation which is hereinafter referred to as the DGCA shall have the power to issue, whenever he considers it necessary or appropriate to do so, such Implementing Standards for the purpose of giving effect to any of the provisions in the CA Act, Regulations or Rules made thereunder including the Articles of the Convention on International Civil Aviation which are specified in the Schedule to the CA Act.

Accordingly, I, being the DGCA do hereby issue the Implementing Standard on Requirements for Aeronautical Charts as mentioned in the Attachment hereto (Ref: Attachment No. IS-04-All-Att), elaborating the requirements to be satisfied for the effective implementation of the International Standards and Recommended Practices on "Aeronautical Charts" contained in ICAO Annex 4.

This Implementing Standard shall be applicable to Airport & Aviation Services (SL) (Pvt) Ltd, the statutory service provider who is responsible for the provision of Aeronautical Information Services/Aeronautical Charts for Air Navigation. This Implementing Standard shall come in to force with effect from 28th November 2024 and remain in force unless revised / revoked.

This Implementing Standard will replace the previous 3rd edition of SLCAIS 031 - Rev 00 issued on 16th December 2022.

Attention is also drawn to Section 103 of the CA Act, which states inter alia that failure to comply with any Implementing Standard is an offence. Further, if any standard stipulated in this Implementing Standard is not complied with or violated, an appropriate enforcement action will be taken as per the Aviation Enforcement Policy & Procedures Manual, SLCAP 0005 by the DGCA under section 102 of the CA Act No. 14 of 2010.

AVM Sagara Kotakadeniya (*Retd*) Director General of Civil Aviation and Chief Executive Officer

Civil Aviation Authority of Sri Lanka No 152/1, Minuwangoda Road Katunayake

Enclosure: Attachment No. IS-04-All-Att.

Page 1 of 1 4th Edition Rev: 00 Date: 28th October 2024

PREAMBLE

Implementing Standard SLCAIS 031: Compliance to Annex 4 – Aeronautical Charts

1. Notice to the Recipient

- 1.1 The requirements in this Implementing Standard (IS) are based on the Standards and Recommended Practices (SARPs) adopted by the International Civil Aviation Organization (ICAO) and incorporated in Amendment No. 62 to Annex 4.
- 1.2 In pursuance of the obligation cast under Article 38 of the Convention which requires the Contracting States to notify the ICAO of any differences between the national regulations of the States and practices and the International Standards contained in the respective Annex and any amendments thereto, the CAASL will be taking steps to notify ICAO of such differences relating to either a Standard or a Recommended Practice, if any. The CAASL will also keep the ICAO currently informed of any differences which may subsequently occur, or of the withdrawal of any differences previously notified. Furthermore, the CAASL will take steps for the publication of differences between the national regulations and practices and the related ICAO Standards and Recommended Practices through the Aeronautical Information Service, which is published in accordance with the provisions in the Annex-15 to the Convention.
- 1.3 Taking into account of the ICAO council resolution dated 13 April 1948 which invited the attention of Contracting States of the desirability of using in the State's national regulations, as far as is practicable, the precise language of those ICAO Standards that are of a regulatory character, to the greatest extent possible the CAASL has attempted to retain the ICAO texts in the Annex in drafting this Implementing Standard.
- 1.4 The requirements contained in this document shall be applicable to Airport & Aviation Services (SL) (Pvt) Ltd (AASL), the statutory service provider who is responsible for the provision of Aeronautical Information Services/Aeronautical Charts for Air Navigation.
- 1.5 AASL shall comply with the requirements published in this document and are hereby instructed to forward to the DGCA a "Declaration of Conformance" which indicates the degree of compliance with each item detailed in the document.
- 1.6 This document supersedes the SLCAIS 031 3rd edition Rev 00 issued on 16th December 2022 and shall be treated as null and void.
- 1.7 This document may be amended from time to time and the amendments will be issued in the form of new pages to replace the relevant pages of this document.
- 1.8 <u>Status of ICAO Annex components in the Implementing Standard</u> Some of the components in an ICAO Annex are as follows and they have the status as indicated:

Page 1 of 133 4th Edition Rev: 00 Date: 28th October 2024

- 1.8.1 **Standard:** Any specification for physical characteristics, configuration, materiel, performance, personnel or procedure, the uniform application of which is recognized as necessary for the safety and regularity of national and international air navigation and to which Contracting States will conform in accordance with the Convention; in the event of impossibility of compliance, notification to the Council is compulsory under Article 38. The ICAO Standards are reflected in the Implementing Standards if they are locally implemented using the normal fonts and recipients are required to conform to such requirements invariably.
- 1.8.2 **Recommended Practice:** Any specification for physical characteristics, configuration, materiel, performance, personnel or procedure, the uniform application of which is recognized as desirable in the interest of safety, regularity, efficiency or environmentally responsiveness of international air navigation, and to which Contracting States will endeavor to conform in accordance with the Convention. The ICAO Recommended Practices are reflected in the Implementing Standards in italic fonts and the Recipients are encouraged to implement them to the greatest extent possible.
- 1.8.3 **Appendices:** Comprising material grouped separately for convenience but forming part of the Standards and Recommended Practices adopted by the Council. Enforcement action on such matters will be as in the case of Standards or Recommended Practices.
- 1.8.4 **Definitions:** A definition does not have independent status but is an essential part of each Standard and Recommended Practice in which the term is used, since a change in the meaning of the term would affect the specification.
- 1.8.5 **Tables and Figures:** add to or illustrate a Standard or Recommended Practice, and which are referred to therein, form part of the associated Standard or Recommended Practice and have the same status.

Page 2 of 133 4th Edition Rev: 00 Date: 28th October 2024

Implementing Standards

SLCAIS - 031; Compliance to Annex 4 – Aeronautical Charts

1. General

- 1.1 Requirements contained in this document are based on the ICAO Annex 4 Aeronautical Charts.
- 1.2 This document supersedes the SLCAIS 031 3^{rd} edition Rev 00 issued on 16^{th} December 2022 and shall be treated as null and void.
- 1.3 This document may be amended from time to time and the amendments (revisions) will be reflected with the vertical line on the right side of the text.

2. Applicable Legal Provisions relating to the issue of the Implementing Standards

- 2.1 Section 120 of the CA Act no. 14 of 2010
- 2.2 Section 30 of the CA Act no. 14 of 2010
- 2.3 Section 31 of the CA Act no. 14 of 2010
- 2.4 ICAO Annex 4
- 2.5 Article 28 of the Chicago Convention
- 2.6 Article 37 of the Chicago Convention

3. Applicability

3.1 This Implementing Standard SLCAIS 031 shall be applicable to Airport & Aviation Services (SL) (Pvt) Ltd, the statutory service provider who is responsible for the provision of Aeronautical Information Services/Aeronautical Charts for Air Navigation.

Page 3 of 133 4th Edition Rev: 00 Date: 28th October 2024

Record of Revision

Rev. Number	Date	Entered by
Edition 01 - Rev 00	08.07.2014	Senior Aeronautical Information Services Officer
Edition 01 - Rev 01	06.03.2017	Aeronautical Information Services Officer
Edition 02 - Rev 00	10.08.2020	Civil Aviation Inspector - AIS
Edition 03 - Rev 00	16.12.2022	Civil Aviation Inspector - AIS
Edition 04 – Rev 00	28.10.2024	Civil Aviation Inspector - AIS

Page 4 of 133 4th Edition Rev: 00 Date: 28th October 2024

List of Effective Pages

Page	Eff. Date						
1	28.11.2024	43	28.11.2024	85	28.11.2024	127	28.11.2024
2	28.11.2024	44	28.11.2024	86	28.11.2024	128	28.11.2024
3	28.11.2024	45	28.11.2024	87	28.11.2024	129	28.11.2024
4	28.11.2024	46	28.11.2024	88	28.11.2024	130	28.11.2024
5	28.11.2024	47	28.11.2024	89	28.11.2024	131	28.11.2024
6	28.11.2024	48	28.11.2024	90	28.11.2024	132	28.11.2024
7	28.11.2024	49	28.11.2024	91	28.11.2024	133	28.11.2024
8	28.11.2024	50	28.11.2024	92	28.11.2024		
9	28.11.2024	51	28.11.2024	93	28.11.2024		
10	28.11.2024	52	28.11.2024	94	28.11.2024		
11	28.11.2024	53	28.11.2024	95	28.11.2024		
12	28.11.2024	54	28.11.2024	96	28.11.2024		
13	28.11.2024	55	28.11.2024	97	28.11.2024		
14	28.11.2024	56	28.11.2024	98	28.11.2024		
15	28.11.2024	57	28.11.2024	99	28.11.2024		
16	28.11.2024	58	28.11.2024	100	28.11.2024		
17	28.11.2024	59	28.11.2024	101	28.11.2024		
18	28.11.2024	60	28.11.2024	102	28.11.2024		
19	28.11.2024	61	28.11.2024	103	28.11.2024		
20	28.11.2024	62	28.11.2024	104	28.11.2024		
21	28.11.2024	63	28.11.2024	105	28.11.2024		
22	28.11.2024	64	28.11.2024	106	28.11.2024		
23	28.11.2024	65	28.11.2024	107	28.11.2024		
24	28.11.2024	66	28.11.2024	108	28.11.2024		
25	28.11.2024	67	28.11.2024	109	28.11.2024		
26	28.11.2024	68	28.11.2024	110	28.11.2024		
27	28.11.2024	69	28.11.2024	111	28.11.2024		
28	28.11.2024	70	28.11.2024	112	28.11.2024		
29	28.11.2024	71	28.11.2024	113	28.11.2024		
30	28.11.2024	72	28.11.2024	114	28.11.2024		
31	28.11.2024	73	28.11.2024	115	28.11.2024		
32	28.11.2024	74	28.11.2024	116	28.11.2024		
33	28.11.2024	75	28.11.2024	117	28.11.2024		
34	28.11.2024	76	28.11.2024	118	28.11.2024		
35	28.11.2024	77	28.11.2024	119	28.11.2024		
36	28.11.2024	78	28.11.2024	120	28.11.2024		
37	28.11.2024	79	28.11.2024	121	28.11.2024		
38	28.11.2024	80	28.11.2024	122	28.11.2024		
39	28.11.2024	81	28.11.2024	123	28.11.2024		
40	28.11.2024	82	28.11.2024	124	28.11.2024		
41	28.11.2024	83	28.11.2024	125	28.11.2024		
42	28.11.2024	84	28.11.2024	126	28.11.2024		

History of Revision

Revision Number	Source	Areas subjected to Change	Effective date
1 (02227.5 02			0.000
SLCAIS	ICAO Annex 4	Replacing ASN 100	08.07.2014
031 Edition	up to amendment		
01 - Rev 00	57		
SLCAIS	ICAO Annex 4	Replacing SLCAIS 031 Edition 01 - Rev 00	06.03.2017
031 Edition	up to amendment		
01 - Rev 01	58-59		
SLCAIS	ICAO Annex 4	Replacing SLCAIS 031 Edition 01- Rev 01	10.08.2020
031 Edition	up to amendment		
02 - Rev 00	60		
SLCAIS	ICAO Annex 4	Replacing SLCAIS 031 Edition 02 - Rev 00	16.12.2022
031 Edition	up to amendment		
03 - Rev 00	61		
SLCAIS	ICAO Annex 4	Replacing SLCAIS 031 Edition 03 - Rev 00	28.11.2024
031 Edition	up to amendment		
04 - Rev 00	62		

Page 6 of 133 4th Edition Rev: 00 Date: 28th October 2024

Table of Contents

PRI	EAMBLE	1
IMP	LEMENTING STANDARDS SLCAIS 031: COMPLIANCE TO ANNEX 4 - AERONAUTICAL CHAR	TS 3
RE	CORD OF REVISION	4
LIS	T OF EFFECTIVE PAGES	5
HIS	TORY OF REVISION	6
TAI	BLE OF CONTENTS	7
1. C	HAPTER 1 – DEFINITIONS, APPLICABILITY AND AVAILABILITY	13
2. C	HAPTER 2 – GENERAL SPECIFICATIONS	24
2.1	OPERATIONAL REQUIREMENTS FOR CHARTS	24
2.2	TITLES	
2.3	MISCELLANEOUS INFORMATION	25
2.4	SYMBOLS	25
2.5	Units of measurement	25
2.6	SCALE AND PROJECTION.	
2.7	DATE OF VALIDITY OF AERONAUTICAL INFORMATION	
2.8	SPELLING OF GEOGRAPHICAL NAMES	
2.9	ABBREVIATIONS	
2.10		
2.11		
2.12		
2.13	,	
2.14		
2.15 2.16		
2.17		
2.17		
	HAPTER 3 – AERODROME OBSTACLE CHART — ICAO TYPE A (OPERATING	20
LIN	IITATIONS)	29
3.1	FUNCTION	29
3.2	AVAILABILITY	29
3.3	UNITS OF MEASUREMENT	29
	COVERAGE AND SCALE	
	FORMAT	
	IDENTIFICATION	
	MAGNETIC VARIATION	
	AERONAUTICAL DATA	
3.9	ACCURACY	33
4. C	HAPTER 4 – AERODROME OBSTACLE CHART — ICAO TYPE B	34
4.1	FUNCTION	34
4.2	AVAILABILITY	34
4.3	UNITS OF MEASUREMENT	34
4.4	COVERAGE AND SCALE	34

4.5	FORMAT	35
4.6	IDENTIFICATION	35
4.7	CULTURE AND TOPOGRAPHY	35
4.8	MAGNETIC VARIATION	35
4.9	AERONAUTICAL DATA	35
4.10	ACCURACY	36
5. C	CHAPTER 5 - AERODROME TERRAIN AND OBSTACLE CHART- ICAO (EL	ECTRONIC)
	`	
5.1	FUNCTION	38
5.2		
5.3	IDENTIFICATION	
5.4	CHART COVERAGE	
5.5	CHART CONTENT	
5.6	ACCURACY AND RESOLUTION	
5.7	ELECTRONIC FUNCTIONALITY	
5.8		
	CHAPTER 6 - PRECISION APPROACH TERRAIN CHART — ICAO	
	FUNCTION	
-	AVAILABILITY	
6.3	SCALE	
6.4		
	PLAN AND PROFILE INFORMATION	
7. C	CHAPTER 7 – ENROUTE CHART — ICAO	46
7.1	FUNCTION	46
7.2	AVAILABILITY	46
7.3	COVERAGE AND SCALE	46
7.4	Projection	46
7.5	IDENTIFICATION	47
7.6	CULTURE AND TOPOGRAPHY	47
7.7	MAGNETIC VARIATION	
7.8	BEARINGS, TRACKS AND RADIALS	47
7.9	AERONAUTICAL DATA	47
8. C	CHAPTER 8 - AREA CHART — ICAO	50
8 1	FUNCTION	50
8.2		
8.3		
8.4		
8.5		
8.6		
8.7		
8.8		
8.9		
	CHAPTER 9 - STANDARD DEPARTURE CHART — INSTRUMENT (SID) — I	
	FUNCTION	
	AVAILABILITY	
	COVERAGE AND SCALE	
	PROJECTION	
	IDENTIFICATION	
	CULTURE AND TOPOGRAPHY	
9.7	MAGNETIC VARIATION	55

Attachment	NΙα	TC	ΩA	A ++
Attachment	INO.	19-	·U4-	Αu

	BEARINGS, TRACKS AND RADIALS	
	AERONAUTICAL DATACHAPTER 10 - STANDARD ARRIVAL CHART — INSTRUMENT (STAR) —	
	FUNCTION	
	AVAILABILITY	
	COVERAGE AND SCALE	
	PROJECTION	
	IDENTIFICATIONCULTURE AND TOPOGRAPHY	
	MAGNETIC VARIATION	
	BEARINGS, TRACKS AND RADIALS	
	AERONAUTICAL DATA	
11. (CHAPTER 11 - INSTRUMENT APPROACH CHART — ICAO	64
11.1	FUNCTION	64
11.2	AVAILABILITY	64
11.3	COVERAGE AND SCALE	64
11.4	FORMAT	65
11.5	Projection	65
11.6	IDENTIFICATION	65
11.7	CULTURE AND TOPOGRAPHY	
11.8		
11.9	,	
	0 AERONAUTICAL DATA	
	CHAPTER 12 - VISUAL APPROACH CHART — ICAO	
	FUNCTION	
12.2		
12.3		
	FORMAT	
	PROJECTION	
	IDENTIFICATION	
	CULTURE AND TOPOGRAPHY	
	MAGNETIC VARIATION	
	BEARINGS, TRACKS AND RADIALS	
	CHAPTER 13 - AERODROME/HELIPORT CHART — ICAO	
	FUNCTION	
	AVAILABILITY	
	COVERAGE AND SCALE	
	IDENTIFICATION	
	MAGNETIC VARIATION	
	AERODROME/HELIPORT DATA	
	CHAPTER 14 - AERODROME GROUND MOVEMENT CHART — ICAO	
	FUNCTION	
14.2		
	COVERAGE AND SCALE	
14.4		
	MAGNETIC VARIATION	
	AERODROME DATA	
	CHAPTER 15 - AIRCRAFT PARKING/DOCKING CHART — ICAO	
15.1	FUNCTION	81

Attachment	No.	IS-04	-Att

	AVAILABILITY	81
15.3	COVERAGE AND SCALE	81
15.4	IDENTIFICATION	81
15.5	MAGNETIC VARIATION	81
15.6	AERODROME DATA	81
16 C	CHAPTER 16 - WORLD AERONAUTICAL CHART — ICAO 1:1 000 000	93
	FUNCTIONFUNCTION	
16.1	AVAILABILITY	
16.2	SCALES	
16.4	FORMAT	
16.5	Projection	
16.5	IDENTIFICATION	
16.7	CULTURE AND TOPOGRAPHY	
16.8	MAGNETIC VARIATION	
	AERONAUTICAL DATA	
	CHAPTER 17 - AERONAUTICAL CHART — ICAO 1:500 000	
	FUNCTION	
17.2	AVAILABILITY	
17.3	SCALES	
17.4	FORMAT	
17.5	PROJECTION	
	IDENTIFICATION	
	CULTURE AND TOPOGRAPHY	
17.8	MAGNETIC VARIATION	
17.9	AERONAUTICAL DATA	94
	CHAPTER 18 - AERONAUTICAL NAVIGATION CHART — ICAO SMALL SCAI	
18.1	Function	97
18.1 18.2	FUNCTIONAVAILABILITY	97 97
18.1 18.2 18.3	FUNCTIONAVAILABILITYCOVERAGE AND SCALE	97 97
18.1 18.2 18.3 18.4	FUNCTION	97 97 97
18.1 18.2 18.3 18.4 18.5	FUNCTION	97 97 98 98
18.1 18.2 18.3 18.4 18.5 18.6	FUNCTION	97 97 97 98 98
18.1 18.2 18.3 18.4 18.5 18.6 18.7	FUNCTION	97 97 98 98 98
18.1 18.2 18.3 18.4 18.5 18.6 18.7	FUNCTION	979798989898
18.1 18.2 18.3 18.4 18.5 18.6 18.7	FUNCTION	9797989898101101
18.1 18.2 18.3 18.4 18.5 18.6 18.7	FUNCTION	9797989898101101
18.1 18.2 18.3 18.4 18.5 18.6 18.7 18.8	FUNCTION	9797989898101101
18.1 18.2 18.3 18.4 18.5 18.6 18.7 18.8 19. C	FUNCTION	97979898101101102102
18.1 18.2 18.3 18.4 18.5 18.6 18.7 18.8 19. C 19.1 19.2 19.3 19.4	FUNCTION	97979898101101102102
18.1 18.2 18.3 18.4 18.5 18.6 18.7 18.8 19. C 19.1 19.2 19.3 19.4 19.5	FUNCTION	9797989898101102102102102
18.1 18.2 18.3 18.4 18.5 18.6 18.7 18.8 19. C 19.1 19.2 19.3 19.4 19.5 19.6	FUNCTION	9797989898101102102102102102
18.1 18.2 18.3 18.4 18.5 18.6 18.7 18.8 19. C 19.1 19.2 19.3 19.4 19.5 19.6 19.7	FUNCTION	97979898101102102102102103103
18.1 18.2 18.3 18.4 18.5 18.6 18.7 18.8 19. C 19.1 19.2 19.3 19.4 19.5 19.6 19.7	FUNCTION AVAILABILITY COVERAGE AND SCALE FORMAT	97979898101102102102102103103
18.1 18.2 18.3 18.4 18.5 18.6 18.7 18.8 19. C 19.1 19.2 19.3 19.4 19.5 19.6 19.7	FUNCTION. AVAILABILITY COVERAGE AND SCALE FORMAT PROJECTION. CULTURE AND TOPOGRAPHY MAGNETIC VARIATION. AERONAUTICAL DATA. CHAPTER 19 - PLOTTING CHART — ICAO FUNCTION. AVAILABILITY COVERAGE AND SCALE FORMAT. PROJECTION. IDENTIFICATION CULTURE AND TOPOGRAPHY MAGNETIC VARIATION AGNORMAT. CULTURE AND TOPOGRAPHY MAGNETIC VARIATION AERONAUTICAL DATA.	97979898101102102102102103103
18.1 18.2 18.3 18.4 18.5 18.6 18.7 18.8 19. C 19.1 19.2 19.3 19.4 19.5 19.6 19.7	FUNCTION AVAILABILITY COVERAGE AND SCALE FORMAT	97979898101102102102102103103
18.1 18.2 18.3 18.4 18.5 18.6 18.7 18.8 19. C 19.1 19.2 19.3 19.4 19.5 19.6 19.7 19.8 19.9	FUNCTION	97979898101102102102102103103103
18.1 18.2 18.3 18.4 18.5 18.6 18.7 18.8 19. C 19.1 19.2 19.3 19.4 19.5 19.6 19.7 19.8 19.9 20. C	FUNCTION	97979898101102102102103103103103104104
18.1 18.2 18.3 18.4 18.5 18.6 18.7 18.8 19. C 19.1 19.2 19.3 19.4 19.5 19.6 19.7 19.8 19.9 20. C 20.1 20.2 20.3	FUNCTION	97979898101102102102102103103103104104
18.1 18.2 18.3 18.4 18.5 18.6 18.7 18.8 19. C 19.1 19.2 19.3 19.4 19.5 19.6 19.7 19.8	FUNCTION	9797989898101102102102102103103103104104104

20.6	BACK-UP ARRANGEMENTS	106
21. C	HAPTER 21 - ATC SURVEILLANCE MINIMUM ALTITUDE CHAR	T — ICAO 107
21.1	FUNCTION	107
21.2	AVAILABILITY	107
21.3	COVERAGE AND SCALE	107
21.4	PROJECTION	107
21.5	IDENTIFICATION	107
21.6	CULTURE AND TOPOGRAPHY	108
21.7	MAGNETIC VARIATION	
21.8	BEARINGS, TRACKS AND RADIALS	108
	AERONAUTICAL DATA	
APPI	ENDIX 1. MARGINAL NOTE LAYOUT	110
APPI	ENDIX 2. ICAO CHART SYMBOLS	111
APPI	ENDIX 3. COLOUR GUIDE	130
APPI	ENDIX 4. HYPSOMETRIC TINT GUIDE	132
	ENDIX 5. SHEET LAYOUT FOR THE WORLD AERONAUTICAL C	

1. CHAPTER 1 – DEFINITIONS, APPLICABILITY AND AVAILABILITY

Definitions

When the following terms are used in this Implementing Standards they have the following meanings;

Aerodrome. A defined area on land or water (including any buildings, installations and equipment) intended to be used either wholly or in part for the arrival, departure and surface movement of aircraft.

Aerodrome elevation. The elevation of the highest point of the landing area.

Aerodrome operating minima. The limits of usability of an aerodrome for:

- a) take-off, expressed in terms of runway visual range and/or visibility and, if necessary, cloud conditions:
- b) landing in precision approach and landing operations, expressed in terms of visibility and/or runway visual range and decision altitude/height (DA/H) as appropriate to the category of the operation;
- c) landing in approach and landing operations with vertical guidance, expressed in terms of visibility and/or runway visual range and decision altitude/height (DA/H); and
- d) landing in non-precision approach and landing operations, expressed in terms of visibility and/or runway visual range, minimum descent altitude/height (MDA/H) and, if necessary, cloud conditions.

Aerodrome reference point. The designated geographical location of an aerodrome.

Aeronautical chart. A representation of a portion of the Earth, its culture and relief, specifically designated to meet the requirements of air navigation.

Aircraft stand. A designated area on an apron intended to be used for parking an aircraft.

Air defence identification zone. Special designated airspace of defined dimensions within which aircraft are required to comply with special identification and/or reporting procedures additional to those related to the provision of air traffic services (ATS).

Air traffic service. A generic term meaning variously, flight information service, alerting service, air traffic advisory service, air traffic control service (area control service, approach control service or aerodrome control service).

Air transit route. A defined route for the air transiting of helicopters.

Airway. A control area or portion thereof established in the form of a corridor.

Altitude. The vertical distance of a level, a point or an object considered as a point, measured from mean sea level (MSL).

Application. Manipulation and processing of data in support of user requirements (ISO 19104*)

Page 12 of 133 4th Edition Rev: 00 Date: 28th October 2024

.

Apron. A defined area, on a land aerodrome, intended to accommodate aircraft for purposes of loading or unloading passengers, mail or cargo, fueling, parking or maintenance.

Area minimum altitude (AMA). The minimum altitude to be used under instrument meteorological conditions (IMC) that provides a minimum obstacle clearance within a specified area, normally formed by parallels and meridians.

Area navigation (RNAV). A method of navigation which permits aircraft operation on any desired flight path within the coverage of ground- or space-based navigation aids or within the limits of the capability of self-contained aids, or a combination of these.

Arrival routes. Routes identified in an instrument approach procedure by which aircraft may proceed from the en-route phase of flight to an initial approach fix.

ATS route. A specified route designed for channeling the flow of traffic as necessary for the provision of air traffic services.

ATS surveillance system. A generic term meaning variously, ADS-B, PSR, SSR or any comparable ground-based system that enables the identification of aircraft.

Bare Earth. Surface of the Earth including bodies of water and permanent ice and snow, and excluding vegetation and man-made objects.

Calendar. Discrete temporal reference system that provides the basis for defining temporal position to a resolution of one day (ISO 19108*).

Canopy. Bare Earth supplemented by vegetation height.

Change-over point. The point at which an aircraft navigating on an ATS route segment defined by reference to very high frequency omnidirectional radio ranges is expected to transfer its primary navigational reference from the facility behind the aircraft to the next facility ahead of the aircraft.

Clearway. A defined rectangular area on the ground or water under the control of the appropriate authority, selected or prepared as a suitable area over which an aeroplane may make a portion of its initial climb to a specified height.

Contour line. A line on a map or chart connecting points of equal elevation.

Culture. All man-made features constructed on the surface of the Earth, such as cities, railways and canals.

Cyclic redundancy check (CRC). A mathematical algorithm applied to the digital expression of data that provides a level of assurance against loss or alteration of data.

Danger area. An airspace of defined dimensions within which activities dangerous to the flight of aircraft may exist at specified times.

Page 13 of 133 4th Edition Rev: 00 Date: 28th October 2024

Data product specification. Detailed description of a data set or data set series together with additional information that will enable it to be created, supplied to and used by another party (ISO 19131*).

Data quality. A degree or level of confidence that the data provided meet the requirements of the data user in terms of accuracy, resolution and integrity (or equivalent assurance level), traceability, timeliness, completeness and format.

Data resolution. A number of units or digits to which a measured or calculated value is expressed and used.

Data set. Identifiable collection of data (ISO 19101*).

Data set series. Collection of data sets sharing the same product specification (ISO 19115*).

Datum. Any quantity or set of quantities that may serve as a reference or basis for the calculation of other quantities (ISO 19104*).

Digital Elevation Model (DEM). The representation of terrain surface by continuous elevation values at all intersections of a defined grid, referenced to common datum.

Displaced threshold. A threshold not located at the extremity of a runway.

Electronic aeronautical chart display. An electronic device by which flight crews are enabled to execute, in a convenient and timely manner, route planning, route monitoring and navigation by displaying the required information.

Elevation. The vertical distance of a point or level on or affixed to the surface of the earth, measured from mean sea level.

Ellipsoid height (Geodetic height). The height related to the reference ellipsoid, measured along the ellipsoidal outer normal through the point in question.

Feature. Abstraction of real world phenomena (ISO 19101*).

Feature attribute. Characteristic of a feature (ISO 19101*).

Final approach. That part of an instrument approach procedure which commences at the specified final approach fix or point, or where such a fix or point is not specified,

- a) at the end of the last procedure turn, base turn or inbound turn of a racetrack procedure, if specified; or
- b) at the point of interception of the last track specified in the approach procedure; and ends at a point in the vicinity of an aerodrome from which:
- 1) a landing can be made; or
- 2) a missed approach procedure is initiated.

Page 14 of 133 4th Edition Rev: 00 Date: 28th October 2024

Final approach and take-off area (FATO). A defined area over which the final phase of the approach manoeuvre to hover or landing is completed and from which the take-off manoeuvre is commenced. Where the FATO is to be used by performance Class 1 helicopters, the defined area includes the rejected take-off area available.

Final approach fix or point. That fix or point of an instrument approach procedure where the final approach segment commences.

Final approach segment. That segment of an instrument approach procedure in which alignment and descent for landing are accomplished.

Flight information region. An airspace of defined dimensions within which flight information service and alerting service are provided.

Flight level. A surface of constant atmospheric pressure which is related to a specific pressure datum, 1 013.2 hectopascals (hPa), and is separated from other such surfaces by specific pressure intervals.

A pressure type altimeter calibrated in accordance with the Standard Atmosphere:

- a) when set to a QNH altimeter setting, will indicate altitude;
- b) when set to a QFE altimeter setting, will indicate height above the QFE reference datum;
- c) when set to a pressure of 1 013.2 hPa, may be used to indicate flight levels.

The terms "height" and "altitude", used in Note 1 above, indicate altimetric rather than geometric heights and altitudes.

Geodesic distance. The shortest distance between any two points on a mathematically defined ellipsoidal surface.

Geodetic datum. A minimum set of parameters required to define location and orientation of the local reference system with respect to the global reference system/frame.

Geoid. The equipotential surface in the gravity field of the Earth which coincides with the undisturbed mean sea level (MSL) extended continuously through the continents.

Geoid undulation. The distance of the geoid above (positive) or below (negative) the mathematical reference ellipsoid.

Glide path. A descent profile determined for vertical guidance during a final approach.

Gregorian calendar. Calendar in general use; first introduced in 1582 to define a year that more closely approximates the tropical year than the Julian calendar (ISO 19108*).

Height. The vertical distance of a level, a point or an object considered as a point, measured from a specified datum.

Page 15 of 133 4th Edition Rev: 00 Date: 28th October 2024

Helicopter stand. An aircraft stand which provides for parking a helicopter and where ground taxi operations are completed or where the helicopter touches down and lifts off for air taxi operations.

Heliport. An aerodrome or a defined area on a structure intended to be used wholly or in part for the arrival, departure and surface movement of helicopters.

Heliport reference point (HRP). The designated location of a heliport or a landing location.

Holding procedure. A predetermined manoeuvre which keeps an aircraft within a specified airspace while awaiting further clearance.

Hot spot. A location on an aerodrome movement area with a history or potential risk of collision or runway incursion, and where heightened attention by pilots/drivers is necessary.

Human Factors principles. Principles which apply to aeronautical design, certification, training, operations and maintenance and which seek safe interface between the human and other system components by proper consideration to human performance.

Hypsometric tints. A succession of shades or colour gradations used to depict ranges of elevation.

Initial approach segment. That segment of an instrument approach procedure between the initial approach fix and the intermediate approach fix or, where applicable, the final approach fix or point.

Instrument approach procedure. A series of predetermined manoeuvres by reference to flight instruments, with specified protection from obstacles from the initial approach fix, or where applicable, from the beginning of a defined arrival route to a point from which a landing can be completed and thereafter, if a landing is not completed, to a position at which holding or enroute obstacle clearance criteria apply.

Integrity classification (aeronautical data). Classification based upon the potential risk resulting from the use of corrupted data. Aeronautical data is classified as:

- a) routine data: there is a very low probability when using corrupted routine data that the continued safe flight and landing of an aircraft would be severely at risk with the potential for catastrophe;
- b) essential data: there is a low probability when using corrupted essential data that the continued safe flight and landing of an aircraft would be severely at risk with the potential for catastrophe; and
- c) critical data: there is a high probability when using corrupted critical data that the continued safe flight and landing of an aircraft would be severely at risk with the potential for catastrophe.

Intermediate approach segment. That segment of an instrument approach procedure between either the intermediate approach fix and the final approach fix or point, or between the end of a reversal, racetrack or dead reckoning track procedure and the final approach fix or point, as appropriate.

Page 16 of 133 4th Edition Rev: 00 Date: 28th October 2024

Intermediate holding position. A designated position intended for traffic control at which taxiing aircraft and vehicles shall stop and hold until further cleared to proceed, when so instructed by the aerodrome control tower.

Isogonal. A line on a map or chart on which all points have the same magnetic variation for a specified epoch.

Isogriv. A line on a map or chart which joins points of equal angular difference between the North of the navigation grid and Magnetic North.

Landing area. That part of a movement area intended for the landing or take-off of aircraft.

Landing direction indicator. A device to indicate visually the direction currently designated for landing and for take-off.

Level. A generic term relating to the vertical position of an aircraft in flight and meaning variously, height, altitude or flight level.

Logon address. A specified code used for data link logon to an ATS unit.

Magnetic variation. The angular difference between True North and Magnetic North.

Manoeuvring area. That part of an aerodrome to be used for the take-off, landing and taxiing of aircraft, excluding aprons.

Marking. A symbol or group of symbols displayed on the surface of the movement area in order to convey aeronautical information.

Metadata. Data about data (ISO 19115*).

Minimum en-route altitude (MEA). The altitude for an en-route segment that provides adequate reception of relevant navigation facilities and ATS communications, complies with the airspace structure and provides the required obstacle clearance.

Minimum obstacle clearance altitude (MOCA). The minimum altitude for a defined segment of flight that provides the required obstacle clearance.

Minimum sector altitude (MSA). The lowest altitude which may be used which will provide a minimum clearance of 300 m (1 000 ft) above all objects located in an area contained within a sector of a circle of 46 km (25 NM) radius centred on a significant point, the aerodrome reference point (ARP) or the heliport reference point (HRP).

Missed approach point (MAPt). That point in an instrument approach procedure at or before which the prescribed missed approach procedure must be initiated in order to ensure that the minimum obstacle clearance is not infringed.

Missed approach procedure. The procedure to be followed if the approach cannot be continued.

Movement area. That part of an aerodrome to be used for the take-off, landing and taxiing of aircraft, consisting of the manoeuvring area and the apron(s).

Page 17 of 133 4th Edition Rev: 00 Date: 28th October 2024

Navigation specification. A set of aircraft and flight crew requirements needed to support performance-based navigation operations within a defined airspace. There are two kinds of navigation specifications:

Required navigation performance (RNP) specification. A navigation specification based on area navigation that includes the requirement for performance monitoring and alerting, designated by the prefix RNP, e.g. RNP 4, RNP APCH.

Area navigation (RNAV) specification. A navigation specification based on area navigation that does not include the requirement for performance monitoring and alerting, designated by the prefix RNAV, e.g. RNAV 5, RNAV 1.

The term RNP in this Implementing Standard is used in the context of navigation specifications that require performance monitoring and alerting, e.g. RNP 4 refers to the aircraft and operating requirements, including a 4 NM lateral performance with on-board performance monitoring and alerting that are detailed in Doc 9613.

Obstacle. All fixed (whether temporary or permanent) and mobile objects, or parts thereof, that:

- a) are located on an area intended for the surface movement of aircraft; or
- b) extend above a defined surface intended to protect aircraft in flight; or
- c) stand outside those defined surfaces and that have been assessed as being a hazard to air navigation.

Obstacle clearance altitude (OCA) or obstacle clearance height (OCH). The lowest altitude or the lowest height above the elevation of the relevant runway threshold or the aerodrome elevation as applicable, used in establishing compliance with appropriate obstacle clearance criteria.

Obstacle clearance altitude is referenced to mean sea level and obstacle clearance height is referenced to the threshold elevation or in the case of non-precision approaches to the aerodrome elevation or the threshold elevation if that is more than 2 m (7 ft) below the aerodrome elevation. An obstacle clearance height for a circling approach is referenced to the aerodrome elevation.

Obstacle free zone (OFZ). The airspace above the inner approach surface, inner transitional surfaces, and balked landing surface and that portion of the strip bounded by these surfaces, which is not penetrated by any fixed obstacle other than a low-mass and frangibly mounted one required for air navigation purposes.

Orthometric height. Height of a point related to the geoid, generally presented as an MSL elevation.

Performance-based navigation (PBN). Area navigation based on performance requirements for aircraft operating along an ATS route, on an instrument approach procedure or in a designated airspace.

Page 18 of 133 4th Edition Rev: 00 Date: 28th October 2024

Point light. A luminous signal appearing without perceptible length.

Portrayal. Presentation of information to humans (ISO 19117*).

Position (geographical). Set of coordinates (latitude and longitude) referenced to the mathematical reference ellipsoid which define the position of a point on the surface of the Earth.

Precision approach procedure. An instrument approach procedure utilizing azimuth and glide path information provided by ILS or PAR.

Procedure altitude/height. A published altitude/height used in defining the vertical profile of a flight procedure, at or above the minimum obstacle clearance altitude/height where established.

Procedure turn. A manoeuvre in which a turn is made away from a designated track followed by a turn in the opposite direction to permit the aircraft to intercept and proceed along the reciprocal of the designated track.

Prohibited area. An airspace of defined dimensions, above the land areas or territorial waters of a State, within which the flight of aircraft is prohibited.

Relief. The inequalities in elevation of the surface of the Earth represented on aeronautical charts by contours, hypsometric tints, shading or spot elevations.

Reporting point. A specified (named) geographical location in relation to which the position of an aircraft can be reported.

There are three categories of reporting points: ground-based navigation aid, intersection and waypoint. In the context of this definition, intersection is a significant point expressed as radials, bearings and/or distances from ground-based navigation aids. A reporting point can be indicated as "on request" or as "compulsory".

Restricted area. An airspace of defined dimensions, above the land areas or territorial waters of a State, within which the flight of aircraft is restricted in accordance with certain specified conditions.

Reversal procedure. A procedure designed to enable aircraft to reverse direction during the initial approach segment of an instrument approach procedure. The sequence may include procedure turns or base turns.

Runway. A defined rectangular area on a land aerodrome prepared for the landing and take-off of aircraft.

Runway-holding position. A designated position intended to protect a runway, an obstacle limitation surface, or an ILS/MLS critical/sensitive area at which taxiing aircraft and vehicles shall stop and hold, unless otherwise authorized by the aerodrome control tower.

Runway strip. A defined area including the runway and stopway, if provided, intended:

a) to reduce the risk of damage to aircraft running off a runway; and

Page 19 of 133 4th Edition Rev: 00 Date: 28th October 2024

b) to protect aircraft flying over it during take-off or landing operations.

Runway visual range (RVR). The range over which the pilot of an aircraft on the centre line of a runway can see the runway surface markings or the lights delineating the runway or identifying its center line.

Shoulder. An area adjacent to the edge of a pavement so prepared as to provide a transition between the pavement and the adjacent surface.

Significant point. A specified geographical location used in defining an ATS route or the flight path of an aircraft and for other navigation and ATS purposes.

There are three categories of significant points: ground-based navigation aid, intersection and waypoint. In the context of this definition, intersection is a significant point expressed as radials, bearings and/or distances from ground-based navigation aids.

Stopway. A defined rectangular area on the ground at the end of the take-off run available prepared as a suitable area in which an aircraft can be stopped in the case of an abandoned take-off.

Taxiing. Movement of an aircraft on the surface of an aerodrome under its own power, excluding take-off and landing.

Taxi-route. A defined path established for the movement of helicopters from one part of a heliport to another. A taxi-route includes a helicopter air or ground taxiway which is centred on the taxi-route.

Taxiway. A defined path on a land aerodrome established for the taxiing of aircraft and intended to provide a link between one part of the aerodrome and another, including:

- a) Aircraft stand taxilane. A portion of an apron designated as a taxiway and intended to provide access to aircraft stands only.
- b) Apron taxiway. A portion of a taxiway system located on an apron and intended to provide a through taxi route across the apron.
- c) Rapid exit taxiway. A taxiway connected to a runway at an acute angle and designed to allow landing aeroplanes to turn off at higher speeds than are achieved on other exit taxiways thereby minimizing runway occupancy times.

Terminal arrival altitude (TAA). The lowest altitude that will provide a minimum clearance of 300 m (1 000 ft) above all objects located in an arc of a circle defined by a 46 km (25 NM) radius centred on the initial approach fix (IAF), or where there is no IAF on the intermediate approach fix (IF), delimited by straight lines joining the extremity of the arc to the IF. The combined TAAs associated with an approach procedure shall account for an area of 360 degrees around the IF.

Terrain. The surface of the Earth containing naturally occurring features such as mountains, hills, ridges, valleys, bodies of water, permanent ice and snow, and excluding obstacles.

Page 20 of 132 3rd Edition Rev: 00 Date: 16th December 2022

In practical terms, depending on the method of data collection, terrain represents the continuous surface that exists at the bare Earth, the top of the canopy or something in-between, also known as "first reflective surface".

Threshold. The beginning of that portion of the runway usable for landing.

Touchdown and lift-off area (**TLOF**). A load bearing area on which a helicopter may touch down or lift off.

Touchdown zone. The portion of a runway, beyond the threshold, where it is intended landing aeroplanes first contact the runway.

Track. The projection on the earth's surface of the path of an aircraft, the direction of which path at any point is usually expressed in degrees from North (true, magnetic or grid).

Transition altitude. The altitude at or below which the vertical position of an aircraft is controlled by reference to altitudes.

Vectoring. Provision of navigational guidance to aircraft in the form of specific headings, based on the use of an ATS surveillance system.

Visual approach procedure. A series of predetermined manoeuvres by visual reference, from the initial approach fix, or where applicable, from the beginning of a defined arrival route to a point from which a landing can be completed and thereafter, if a landing is not completed, a go-around procedure can be carried out.

Waypoint. A specified geographical location used to define an area navigation route or the flight path of an aircraft employing area navigation. Waypoints are identified as either:

Fly-by waypoint. A waypoint which requires turn anticipation to allow tangential interception of the next segment of a route or procedure; or

Flyover waypoint. A waypoint at which a turn is initiated in order to join the next segment of a route or procedure.

Page 21 of 133 4th Edition Rev: 00 Date: 28th October 2024

Applicability

- 1.2.1 AASL shall be responsible for the provision of Aeronautical Maps and Charts Services, in conformity with the requirements in this Implementing Standards.
- 1.2.2 AASL shall ensure that the availability of aeronautical Maps and & Charts which covers the territory of Sri Lanka and those areas over high seas for which Sri Lanka is responsible for the provision of Air Traffic Services.
 - Specifications for aeronautical charts given in this implementing Standard are for production of six types of charts mandatory and for the availability of six non mandatory and other types of charts that are conditional. This Implementing Standard is to be used in conjunction with the current version of Aeronautical Chart Manual ICAO Doc 8697 and Aeronautical Information Management Manual, ICAO Doc 10066.
- 1.2.2.1 All such charts should in addition conform to the Recommended Practices relevant to the particular chart.

Availability

- 1.3.1 Information. AASL with the concurrence of DGCA shall on request by another Contracting State provide all information relating to Sri Lanka territory that is necessary to enable the standards of the ICAO Annex 4.
- 1.3.2 Charts. AASL shall ensure the availability of charts in whichever of the following ways is appropriate for a particular chart or single sheet of a chart series.
 - The availability of charts includes specified electronic charts.
- 1.3.2.1 For any chart or single sheet of a chart series entirely contained within the territory of Sri Lanka, the AASL shall ensure the production of the chart or sheet itself.
- 1.3.2.2 AASL shall make available maps and charts depicting the territory of Sri Lanka including Colombo FIR as specified in ICAO Charts Manual Doc 8697.
- 1.3.3 AASL shall take all reasonable measures to ensure that the information it provides, and the aeronautical charts made available are adequate and accurate and that they are maintained up to date by an adequate revision service.
- 1.3.4 To improve worldwide dissemination of information on new charting techniques and production methods, charts produced by AASL as specified in ICAO Charts Manual Doc 8697, should be made available without charge to other Contracting States on request on a reciprocal basis.

Page 22 of 133 4th Edition Rev: 00 Date: 28th October 2024

2. CHAPTER 2 – GENERAL SPECIFICATIONS

Requirements contained in this implementing Standard are applicable to all ICAO aeronautical charts unless otherwise stated in the specifications of the chart concerned.

2.1 Operational requirements for charts

For the purposes of this Implementing Standard, the total flight is divided into the following phases:

- Phase 1 Taxi from aircraft stand to take-off point
- Phase 2 Take-off and climb to en-route ATS route structure
- *Phase 3 En-route ATS route structure*
- Phase 4 Descent to approach
- Phase 5 Approach to land and missed approach
- *Phase* 6 *landing and taxi to aircraft stand.*
- 2.1.1 AASL shall ensure that each type of chart be provided with information relevant to the function of the chart and its design shall observe Human Factors principles which facilitate its optimum use.
- 2.1.2 AASL shall ensure that each type of chart provided with information appropriate to the phase of flight to ensure the safe and expeditious operation of the aircraft.
- 2.1.3 The presentation of information shall be accurate, free from distortion and clutter, unambiguous, and be readable under all normal operating conditions.
- 2.1.4 Colours or tints and type size used shall be such that the chart can be easily read and interpreted by the pilot in varying conditions of natural and artificial light.
- 2.1.5 The information shall be in a form which enables the pilot to acquire it in a reasonable time consistent with workload and operating conditions.
- 2.1.6 The presentation of information provided on each type of chart shall permit smooth transition from chart to chart as appropriate to the phase of flight.
- 2.1.7 The charts should be True North orientated.
- 2.1.8 The basic sheet size of the charts should be 210 x148mm (8.27x5.82 in) (A5).

2.2 Titles

The title of a chart or chart series prepared in accordance with the specifications contained in this Implementing Standard and intended to satisfy the function of the chart shall be that of the

Page 23 of 133 4th Edition Rev: 00 Date: 28th October 2024

relevant chapter heading as modified by application of any Standard contained therein, except that such title shall not include "ICAO" unless the chart conforms with all Standards specified in this Chapter 2 and any specified for the particular chart.

2.3 Miscellaneous information

- 2.3.1 The marginal note layout shall be as given in Appendix 1, except as otherwise specified for a particular chart.
- 2.3.2 The following information shall be shown on the face of each chart unless otherwise stated in the specification of the chart concerned:
 - a) designation or title of the chart series; (the title may be abbreviated)
 - b) name and reference of the sheet;
 - c) on each margin an indication of the adjoining sheet (when applicable).
- 2.3.3 A legend to the symbols and abbreviations used shall be provided. The legend shall be on the face or reverse of each chart except that, where it is impracticable for reasons of space, a legend may be published separately.
- 2.3.4 The name and adequate address of the producing agency shall be shown in the margin of the chart except that, where the chart is published as part of an aeronautical document, this information may be placed in the front of that document.

2.4 Symbols

- 2.4.1 Symbols used shall conform to those shown in Appendix 2 ICAO Chart Symbols, except that where it is desired to show on an aeronautical chart special features or items of importance to civil aviation for which no ICAO symbol is at present provided, any appropriate symbol may be chosen for this purpose, provided that it does not cause confusion with any existing ICAO chart symbol or impair the legibility of the chart.
- 2.4.2 To represent ground-based navigation aids, intersections and waypoints, the same basic symbol shall be used on all charts on which they appear, regardless of chart purpose.
- 2.4.3 The symbol used for significant points shall be based on a hierarchy of symbols and selected in the following order: ground-based navigation aid, intersection, waypoint symbol. A waypoint symbol shall be used only when a particular significant point does not already exist as either a ground-based navigation aid or intersection.
- 2.4.4 AASL shall ensure that symbols are shown in the manner specified in 2.4.2, 2.4.3 and Appendix 2 ICAO Chart Symbols, symbol number 121.

2.5 Units of measurement

2.5.1 Distances shall be derived as geodesic distances.

Page 24 of 133 4th Edition Rev: 00 Date: 28th October 2024

- 2.5.2 Distances shall be expressed in either kilometres or nautical miles or both, provided the units are clearly differentiated.
- 2.5.3 Altitudes, elevations and heights shall be expressed in either meters or feet or both, provided the units are clearly differentiated.
- 2.5.4 Linear dimensions on aerodromes and short distances shall be expressed in meters.
- 2.5.5 The order of resolution of distances, dimensions, elevations and heights shall be that as specified for a particular chart.
- 2.5.6 The units of measurement used to express distances, altitudes, elevations and heights shall be conspicuously stated on the face of each chart.
- 2.5.7 Conversion scales (kilometers/nautical miles, meters/feet) shall be provided on each chart on which distances, elevations or altitudes are shown. The conversion scales shall be placed on the face of each chart.

2.6 Scale and projection

- 2.6.1 For charts of large areas, the name and basic parameters and scale of the projection shall be indicated.
- 2.6.2 For charts of small areas, a linear scale only shall be indicated.

2.7 Date of validity of aeronautical information

The date of validity of aeronautical information shall be clearly indicated on the face of each chart.

2.8 Spelling of geographical names

- 2.8.1 The symbols of the Roman alphabet shall be used for all writing.
- 2.8.2 The names of places and of geographical features in countries which officially use varieties of the Roman alphabet shall be accepted in their official spelling, including the accents and diacritical marks used in the respective alphabets.
- 2.8.3 Where a geographical term such as "cape", "point", "gulf", "river" is abbreviated on any particular chart that word shall be spelt out in full in English language, in respect of the most important example of each type. Punctuation marks shall not be used in abbreviations within the body of a chart.

Page 25 of 133 4th Edition Rev: 00 Date: 28th October 2024

2.8.4 In areas where romanized names have not been officially produced or adopted, names should be transliterated from the non-Roman alphabet form.

2.9 Abbreviations

- 2.9.1 Abbreviations shall be used on aeronautical charts whenever they are appropriate.
- 2.9.2 Where applicable, abbreviations should be selected from the Procedures for Air Navigation Services ICAO Abbreviations and Codes (Doc 8400).

2.10 Political boundaries

- 2.10.1 International boundaries shall be shown, but may be interrupted if data more important to the use of the chart would be obscured.
- 2.10.2 Where the territory of more than one State appears on a chart, the names identifying the countries shall be indicated.

2.11 Colours

Colours used on charts should conform to Appendix 3 — Colour Guide.

2.12 Relief

- 2.12.1 Relief, where shown, shall be portrayed in a manner that will satisfy the chart users' need for:
 - a) Orientation and identification;
 - b) Safe terrain clearance;
 - c) Clarity of aeronautical information when shown;
 - d) Planning.
- 2.12.2 Where relief is shown by hypsometric tints, the tints used should be based on those shown in the Hypsometric Tint Guide in Appendix 4.
- 2.12.3 Where spot elevations are used, they shall be shown for selected critical points.
- 2.12.3.1 The value of spot elevations of doubtful accuracy shall be followed by the sign ±.

2.13 Prohibited, restricted and danger areas

When prohibited, restricted or dangerous areas are shown, the reference or other identification shall be included, except that the nationality letters may be omitted.

2.14 Air traffic services airspaces

Page 26 of 133 4th Edition Rev: 00 Date: 28th October 2024

- 2.14.1 When ATS airspace is shown on a chart, the class of airspace, the type, name or call sign, the vertical limits and the radio frequency(ies) to be used shall be indicated and the horizontal limits depicted in accordance with Appendix 2 ICAO Chart Symbols.
- 2.14.2 On charts used for visual flight, those parts of the ATS Airspace Classes table (Appendix 4) in Implementing Standard no 28 applicable to the airspace depicted on the chart should be on the face or reverse of each chart.

2.15 Magnetic variation

- 2.15.1 True North and magnetic variation shall be indicated. The order of resolution of magnetic variation shall be that as specified for a particular chart.
- 2.15.2 When magnetic variation is shown on a chart, the values shown should be those for the year nearest to the date of publication that is divisible by 5, i.e. 1980, 1985, etc. In exceptional cases where the current value would be more than one degree different, after applying the calculation for annual change, an interim date and value should be quoted.
 - The date and the annual change may be shown.
- 2.15.3 For instrument procedure charts, the publication of a magnetic variation change should be completed within a maximum of six AIRAC cycles.
- 2.15.4 In large terminal areas with multiple aerodromes, a single rounded value of magnetic variation should be applied so that the procedures that service multiple aerodromes use a single, common variation value.

2.16 Typography

Samples of type suitable for use on aeronautical charts are included in the Aeronautical Chart Manual (Doc 8697).

2.17 Aeronautical data

- 2.17.1 AASL shall take all necessary measures to introduce a properly organized quality system containing procedures, processes and resources necessary to implement quality management at each function stage as outlined in Implementing Standard no 28, Para 3.6. The execution of such quality management shall be made demonstrable for each function stage, when required. In addition, AASL shall ensure that established procedures exist in order that aeronautical data at any moment is traceable to its origin so to allow any data anomalies or errors, detected during the production/maintenance phases or in the operational use, to be corrected.
- 2.17.2 AASL shall ensure that the chart resolution of aeronautical data shall be that as specified for a particular chart.

Specifications concerning the chart resolution for aeronautical data are contained in PANS-AIM (Doc 10066), Appendix 1.

Page 27 of 133 4th Edition Rev: 00 Date: 28th October 2024

- 2.17.3 AASL shall ensure that integrity of aeronautical data is maintained throughout the data process from origination to distribution to the next intended user.
- 2.17.4 Digital data error detection techniques shall be used during the transmission and/or storage of aeronautical data and digital data sets.

2.18 Common reference systems

2.18.1 Horizontal reference system

- 2.18.1.1 World Geodetic System 1984 (WGS-84) shall be used as the horizontal (geodetic) reference system. Published aeronautical geographical coordinates (indicating latitude and longitude) shall be expressed in terms of the WGS-84 geodetic reference datum.
- 2.18.1.2 Geographical coordinates which have been transformed into WGS-84 coordinates but whose accuracy of original field work does not meet the requirements in the Implementing Standard no 25 Chapter 2, and Implementing Standard no 30 Volumes I and II, Chapter 2, shall be identified by an asterisk.
- 2.18.1.3 The chart resolution of geographical coordinates shall be that specified for a particular chart series.

2.18.2 Vertical reference system

2.18.2.1 Mean sea level (MSL) datum, which gives the relationship of gravity-related height (elevation) to a surface known as the geoid, shall be used as the vertical reference system.

The geoid globally most closely approximates MSL. It is defined as the equipotential surface in the gravity field of the Earth that coincides with the undisturbed MSL extended continuously through the continents.

Gravity-related heights (elevations) are also referred to as orthometric heights while distances of points above the ellipsoid are referred to as ellipsoidal heights.

- 2.18.2.2 In addition to elevations referenced to MSL, for the specific surveyed ground positions, geoid undulation (referenced to the WGS-84 ellipsoid) for those positions shall also be published as specified for a particular chart.
- 2.18.2.3 The chart resolution of elevation and geoid undulation shall be that specified for a particular chart series.

2.18.3 Temporal reference system

2.18.3.1 The Gregorian calendar and Coordinated Universal Time (UTC) shall be used as the temporal reference system.

Page 28 of 133 4th Edition Rev: 00 Date: 28th October 2024

3. CHAPTER 3 – AERODROME OBSTACLE CHART — ICAO TYPE A (OPERATING LIMITATIONS)

3.1 Function

Aerodrome Obstacle chart, ICAO type A (operating limitations) shall provide the data necessary to enable an operator to comply with the operating limitations of Annex 6, Part I, Chapter 5, and Part III, Section II, Chapter 3.

3.2 Availability

- 3.2.1 Aerodrome Obstacle Chart ICAO Type A (Operating Limitations) shall be made available in the manner prescribed in 1.3.2 for all aerodromes regularly used by international civil aviation, except for those aerodromes where there are no obstacles in the take-off flight path areas or where the Aerodrome Terrain and Obstacle Chart ICAO (Electronic) is provided in accordance with Chapter 5.
- 3.2.2 Where a chart is not required because no obstacles exist in the take-off flight path area, a notification to this effect shall be published in the AIP.

3.3 Units of measurement

- 3.3.1 Elevations shall be shown to the nearest half-metre or to the nearest foot.
- 3.3.2 Linear dimensions shall be shown to the nearest half-metre.

3.4 Coverage and scale

3.4.1 The extent of each plan shall be sufficient to cover all obstacles.

Isolated distant obstacles that would unnecessarily increase the sheet size may be indicated by the appropriate symbol and an arrow, provided that the distance and bearing from the end of the runway farthest removed and the elevation are given.

- 3.4.2 The horizontal scale shall be within the range of 1:10 000 to 1:15 000.
- 3.4.3 The horizontal scale should be 1:10 000.
- 3.4.4 The vertical scale shall be ten times the horizontal scale.
- 3.4.5 *Linear scales*. Horizontal and vertical linear scales showing both metres and feet shall be included in the charts.

3.5 Format

3.5.1 The charts shall depict a plan and profile of each runway, any associated stop way or clearway, the take-off flight path area and obstacles.

Page 29 of 133 4th Edition Rev: 00 Date: 28th October 2024

- 3.5.2 The profile for each runway, stop way, clearway and the obstacles in the take-off flight path area shall be shown above its corresponding plan. The profile of an alternative take-off flight path area shall comprise a linear projection of the full take-off flight path and shall be disposed above its corresponding plan in the manner most suited to the ready interpretation of the information.
- 3.5.3 A profile grid shall be ruled over the entire profile area exclusive of the runway. The zero for vertical coordinates shall be mean sea level. The zero for horizontal coordinates shall be the end of the runway furthest from the take-off flight path area concerned. Graduation marks indicating the subdivisions of intervals shall be shown along the base of the grid and along the vertical margins.
- 3.5.3.1 The vertical grid should have intervals of 30 m (100 ft) and the horizontal grid should have intervals of 300 m (1 000 ft).
- 3.5.4 The chart shall include:
 - a) a box for recording the operational data specified in 3.8.3;
 - b) a box for recording amendments and dates thereof.

3.6 Identification

The chart shall be identified by the word "Sri Lanka" succeeded by, the name of the city or town or area which the aerodrome serves, the name of the aerodrome and the designator(s) of the runway(s).

3.7 Magnetic variation

The magnetic variation to the nearest degree and date of information shall be indicated.

3.8 Aeronautical data

- 3.8.1 Obstacles
- 3.8.1.1 Objects in the take-off flight path area which project above a plane surface having a 1.2 percent slope and having a common origin with the take-off flight path area shall be regarded as obstacles, except that obstacles lying wholly below the shadow of other obstacles as defined in 3.8.1.2 need not be shown. Mobile objects such as boats, trains and trucks, which may project above the 1.2 per cent plane, shall be considered obstacles but shall not be considered as being capable of creating a shadow.
- 3.8.1.2 The shadow of an obstacle is considered to be a plane surface originating at a horizontal line passing through the top of the obstacle at right angles to the centre line of the take-off flight path area. The plane covers the complete width of the take-off flight path area and extends to the plane defined in 3.8.1.1 or to the next higher obstacle if it occurs first. For the first 300 m (1 000)

Page 30 of 133 4th Edition Rev: 00 Date: 28th October 2024

- ft) of the take-off flight path area, the shadow planes are horizontal and beyond this point such planes have an upward slope of 1.2 per cent.
- 3.8.1.3 If the obstacle creating a shadow is likely to be removed, objects that would become obstacles by its removal shall be shown.
- 3.8.2 Take-off flight path area
- 3.8.2.1 The take-off flight path area consists of a quadrilateral area on the surface of the earth lying directly below, and symmetrically disposed about, the take-off flight path. This area has the following characteristics:
 - a) it commences at the end of the area declared suitable for take-off (i.e. at the end of the runway or clearway as appropriate);
 - b) its width at the point of origin is 180 m (600 ft) and this width increases at the rate of 0.25D to a maximum of 1 800 m (6 000 ft), where D is the distance from the point of origin;
 - c) it extends to the point beyond which no obstacles exist or to a distance of 10.0 km (5.4 NM), whichever is the lesser.
- 3.8.2.2 For runways serving aircraft having operating limitations which do not preclude the use of a take-off flight path gradient of less than 1.2 per cent, the extent of the take-off flight path area specified in 3.8.2.1 c) shall be increased to not less than 12.0 km (6.5 NM) and the slope of the plane surface specified in 3.8.1.1 and 3.8.1.2 shall be reduced to 1.0 per cent or less.
 - When a 1.0 per cent survey plane touches no obstacles, this plane may be lowered until it touches the first obstacle.
- 3.8.3 Declared distances
- 3.8.3.1 The following information for each direction of each runway shall be entered in the space provided:
 - a) take-off run available;
 - b) accelerate-stop distance available;
 - c) take-off distance available;
 - d) landing distance available.
- 3.8.3.2 Where a declared distance is not provided because a runway is usable in one direction only, that runway should be identified as "not usable for take-off, landing or both".
- 3.8.4 Plan and profile views
- 3.8.4.1 The plan view shall show:
 - a) the outline of the runways by a solid line, including the length and width, the magnetic bearing to the nearest degree, and the runway number;

Page 31 of 133 4th Edition Rev: 00 Date: 28th October 2024

- b) the outline of the clearways by a broken line, including the length and identification as such;
- c) take-off flight path areas by a dashed line and the centre line by a fine line consisting of short and long dashes;
- d) alternative take-off flight path areas. When alternative take-off flight path areas not centred on the extension of the runway centre line are shown, notes shall be provided explaining the significance of such areas;
- e) obstacles, including:
- 1) the exact location of each obstacle together with a symbol indicative of its type;
- 2) the elevation and identification of each obstacle;
- 3) the limits of penetration of obstacles of large extent in a distinctive manner identified in the legend.

This does not exclude the necessity for indicating critical spot elevations within the take-off flight path area.

- 3.8.4.1.1 The nature of the runway and stop way surfaces should be indicated.
- 3.8.4.1.2 Stop ways should be identified as such and should be shown by a broken line.
- 3.8.4.1.3 When stop ways are shown, the length of each stop way shall be indicated.
- 3.8.4.2 The profile view shall show:
 - a) the profile of the centre line of the runway by a solid line and the profile of the centre line of any associated stop ways and clearways by a broken line;
 - b) the elevation of the runway centre line at each end of the runway, at the stop way and at the origin of each take- off flight path area, and at each significant change in slope of runway and stop way;
 - c) obstacles, including:
 - 1) each obstacle by a solid vertical line extending from a convenient grid line over at least one other grid line to the elevation of the top of the obstacle;
 - 2) Identification of each obstacle;
 - 3) the limits of penetration of obstacles of large extent in a distinctive manner identified in the legend.

An obstacle profile consisting of a line joining the tops of each obstacle and representing the shadow created by successive obstacles may be shown.

Page 32 of 133 4th Edition Rev: 00 Date: 28th October 2024

3.9 Accuracy

- 3.9.1 The order of accuracy attained shall be shown on the chart.
- 3.9.2 The horizontal dimensions and the elevations of the runway, stop way and clearway to be printed on the chart should be determined to the nearest 0.5 m (1 ft).
- 3.9.3 The order of accuracy of the field work and the precision of chart production should be such that measurements in the take-off flight path areas can be taken from the chart within the following maximum deviations:
 - a) horizontal distances: 5 m (15 ft) at a point of origin is increasing at a rate of 1 per 500;
 - b) vertical distances: 0.5 m (1.5 ft) in the first 300 m (1 000ft) and increasing at a rate of 1 per 1 000.
- 3.9.4 Datum. Where no accurate datum for vertical reference is available, the elevation of the datum used shall be stated and shall be identified as assumed.

Page 33 of 133 4th Edition Rev: 00 Date: 28th October 2024

4. CHAPTER 4 – AERODROME OBSTACLE CHART — ICAO TYPE B

4.1 Function

Aerodrome Obstacle chart - ICAO Type B shall provide information to satisfy the following functions:

- a) the determination of minimum safe altitudes/heights including those for circling procedures;
- b) the determination of procedures for use in the event of an emergency during take-off or landing;
- c) the application of obstacle clearing and marking criteria; and
- d) the provision of source material for aeronautical charts.

4.2 Availability

- 4.2.1 Aerodrome Obstacle Chart ICAO Type B should be made available, in the manner prescribed in 1.3.2, for all aerodromes regularly used by the international civil aviation except for those aerodromes where the Aerodrome Terrain and Obstacle Chart ICAO (Electronic) is provided in accordance with Chapter 5.
- 4.2.2 When a chart combining the specifications of Chapters 3 and 4 is made available, it shall be called the Aerodrome Obstacle Chart ICAO (Comprehensive).

4.3 Units of measurement

- 4.3.1 Elevations shall be shown to the nearest half-metre or to the nearest foot.
- 4.3.2 Linear dimensions shall be shown to the nearest half-metre.

4.4 Coverage and scale

4.4.1 The extent of each plan shall be sufficient to cover all obstacles.

Isolated distant obstacles that would unnecessarily increase the sheet size may be indicated by the appropriate symbol and an arrow, provided that the distance and bearing from the aerodrome reference point and elevation are given.

- 4.4.2 The horizontal scale shall be within the range of 1:10 000 to 1:20 000.
- 4.4.3 A horizontal linear scale showing both metres and feet shall be included in the chart. When necessary, a linear scale for kilometres and a linear scale for nautical miles shall also be shown.

Page 34 of 133 4th Edition Rev: 00 Date: 28th October 2024

4.5 Format

Aerodrome Obstacle chart - ICAO Type B shall include:

- a) any necessary explanation of the projection used;
- b) any necessary identification of the grid used;
- c) a notation indicating that obstacles are those which penetrate the surfaces specified in IS30, Chapter 4;
- d) a box for recording amendments and dates thereof; and
- e) outside the neat line, every minute of latitude and longitude marked in degrees and minutes. Lines of latitude and longitude may be shown across the face of the chart.

4.6 Identification

The chart shall be identified by the word "Sri Lanka" succeeded by, the name of the city or town or area which the aerodrome serves, the name of the aerodrome and the designator(s) of the runway(s).

4.7 Culture and topography

- 4.7.1 Drainage and hydrographic details shall be kept to a minimum.
- 4.7.2 Buildings and other salient features associated with the aerodrome shall be shown. Wherever possible, they shall be shown to scale.
- 4.7.3 All objects, either cultural or natural, that project above the take-off and approach surfaces specified in 4.9 or the clearing and marking surfaces specified in IS30 Chapter 4, shall be shown.
- 4.7.4 Roads and railroads within the take-off and approach area, and less than 600 m (2 000 ft) from the end of the runway or runway extensions, shall be shown.

4.8 Magnetic variation

Aerodrome Obstacle chart - ICAO Type B shall show a compass rose orientated to the True North, or a North point, showing the magnetic variation to the nearest degree with the date of magnetic information and annual change.

4.9 Aeronautical data

- 4.9.1 Aerodrome Obstacle chart ICAO Type B shall show:
 - a) the aerodrome reference point and its geographical coordinates in degrees, minutes and seconds;
 - b) the outline of the runways by a solid line;
 - c) the length and width of the runway;
 - d) the magnetic bearing to the nearest degree of the runway and the runway number;

Page 35 of 133 4th Edition Rev: 00 Date: 28th October 2024

- e) the elevation of the runway centre line at each end of the runway, at the stop way, at the origin of each take-off and approach area, and at each significant change of slope of runway and stop way;
- f) Taxiways, aprons and parking areas identified as such, and the outlines by a solid line;
- g) Stop ways identified as such and depicted by a broken line;
- h) the length of each stop way;
- i) Clearways identified as such and depicted by a broken line;
- i) the length of each clearway;
- k) take-off and approach surfaces identified as such and depicted by a broken line;
- 1) take-off and approach areas;

The take-off area is described in 3.8.2.1. The approach area consists of an area on the surface of the earth lying directly below the approach surface as specified in Implementing Standard no 30 Volume I, Chapter 4.

- m) Obstacles at their exact location, including:
- 1) a symbol indicative of their type;
- 2) Elevation;
- 3) Identification;
- 4) Limits of penetration of large extent in a distinctive manner identified in the legend;

This does not exclude the necessity for indicating critical spot elevations within the take-off and approach areas.

n) any additional obstacles, as determined by 3.8.1.1 including the obstacles in the shadow of an obstacle, which would otherwise be exempted.

The specifications in Implementing Standard no 30 Chapter 4, are minimum requirements issued by DGCA about lower surfaces, they may be used in the determination of obstacles.

- 4.9.1.1 The nature of the runway and stop way surfaces should be given.
- 4.9.1.2 Wherever practicable, the highest object or obstacle between adjacent approach areas within a radius of 5 000 m (15 000 ft) from the aerodrome reference point should be indicated in a prominent manner.
- 4.9.1.3 The extent of tree areas and relief features, part of which constitute obstacles, should be shown.

4.10 Accuracy

- 4.10.1 The order of accuracy attained shall be shown on the chart.
- 4.10.2 The horizontal dimensions and the elevations of the movement area, stop ways and clearways to be printed on the chart should be determined to the nearest 0.5 m (1 ft).
- 4.10.3 The order of accuracy of the field work and the precision of chart production should be such that the resulting data will be within the maximum deviations indicated herein:
 - a) Take-off and approach areas:
 - 1) Horizontal distances: 5 m (15 ft) at point of origin increasing at a rate of 1 per 500;

Page 36 of 133 4th Edition Rev: 00 Date: 28th October 2024

Compliance to Annex 04 – Aeronautical Charts Attachment No. IS-04-Att.

- 2) Vertical distances: 0.5 m (1.5 ft) in the first 300 m (1 000 ft) and increasing at a rate of 1 per 1 000.
- b) Other areas:
- 1) Horizontal distances: 5 m (15 ft) within 5 000 m (15 000 ft) of the aerodrome reference point and 12 m (40 ft) beyond that area;
- 2) Vertical distances: 1 m (3 ft) within 1 500 m (5 000 ft) of the aerodrome reference point increasing at a rate of 1 per 1 000.
- 4.10.4 *Datum*. Where no accurate datum for vertical reference is available, the elevation of the datum used shall be stated and identified as assumed.

Page 37 of 133 4th Edition Rev: 00 Date: 28th October 2024

5. CHAPTER 5 - AERODROME TERRAIN AND OBSTACLE CHART — ICAO (ELECTRONIC)

5.1 Function

Aerodrome Terrain and Obstacle Chart -ICAO (electronic) shall portray the terrain and obstacle data in combination with aeronautical data, necessary to:

- a) enable an operator to comply with the operating limitations of Implementing Standard no 14 and Annex 6, Part I, Chapter 5, and Part III, Section II, Chapter 3, by developing contingency procedures for use in the event of an emergency during a missed approach or take-off, and by performing aircraft operating limitations analysis; and
- b) Support the following air navigation applications:
- 1) Instrument procedure design (including circling procedure);
- 2) Aerodrome obstacle restriction and removal; and
- 3) Provision of source data for the production of other aeronautical charts.

5.2 Availability

5.2.1 Aerodrome Terrain and Obstacle Charts — ICAO (Electronic) shall be made available in the manner prescribed in 1.3.2 for aerodromes regularly used by international civil aviation.

Where the Aerodrome Terrain and Obstacle Chart — ICAO (Electronic) is made available, the Aerodrome Obstacle Chart — ICAO Type A (Operating Limitations) and the Aerodrome Obstacle Chart — ICAO Type B are not required (see 3.2.1 and 4.2.1).

The information required by the Precision Approach Terrain Chart — ICAO may be provided in the Aerodrome Terrain and Obstacle Chart — ICAO (Electronic). Where this occurs, the Precision Approach Terrain Chart — ICAO is not required (see 6.2.1).

- 5.2.2 Aerodrome Terrain and Obstacle Charts ICAO (Electronic) should be made available in the manner prescribed in 1.3.2 for all aerodromes regularly used by international civil aviation.
- 5.2.3 The Aerodrome Terrain and Obstacle Chart ICAO (Electronic) shall also be made available in hard copy format upon request.
- 5.2.4 The ISO 19100 series of standards for geographic information shall be used as a general data modelling framework.

5.3 Identification

The charts shall be identified by the word "Sri Lanka" succeeded by, the name of the city or town or area which the aerodrome serves, and the name of the aerodrome.

Page 38 of 133 4th Edition Rev: 00 Date: 28th October 2024

5.4 Chart coverage

The extent of each chart shall be sufficient to cover Area 2 as specified in Implementing Standard no 28, Chapter 5.

5.5 Chart content

5.5.1 General

5.5.1.1 When developing computer graphics applications that are used to portray features on the chart, the relationships between features, feature attributes, and the underlying spatial geometry and associated topological relationships shall be specified by an application schema. Portrayed information shall be provided on the basis of portrayal specifications applied according to defined portrayal rules. Portrayal specifications and portrayal rules shall not be part of the data set. Portrayal rules shall be stored in a portrayal catalogue which shall make reference to separately stored portrayal specifications.

ISO Standard 19117 contains a definition of the schema describing the portrayal mechanism of feature-based geographic information, while ISO Standard 19109 contains rules for application schema. Spatial geometry and associated topological relationships are defined in ISO Standard 19107.

- 5.5.1.2 Symbols used to portray features shall be in accordance with 2.4 and Appendix 2 ICAO Chart Symbols.
- 5.5.2 Terrain feature
- 5.5.2.1 The terrain feature, and associated attributes, to be portrayed and database-linked to the chart shall be based on the terrain data sets which satisfy the requirements of Implementing Standard 28, Chapter 5.
 - Specifications concerning terrain data sets are contained in PANS-AIM (Doc 10066), Chapter 5 and Appendices 1, 6 and 8.
- 5.5.2.2 The terrain feature shall be portrayed in a manner that provides an effective general impression of a terrain. This shall be a representation of terrain surface by continuous elevation values at all intersections of the defined grid, also known as the Digital Elevation Model (DEM).
 - In accordance with Annex 15, Chapter 5 and PANS-AIM (Doc 10066), Chapter 5 and Appendices 1 and 8, the DEM for Area 2 post spacing (grid) is specified at 1 arc second (approximately 30 m).
- 5.5.2.3 Representation of terrain surface should be provided as a selectable layer of contour lines in addition to the DEM.

Page 39 of 133 4th Edition Rev: 00 Date: 28th October 2024

- 5.5.2.4 An ortho-rectified image which matches the features on the DEM with features on the overlying image should be used to enhance the DEM. The image should be provided as a separate selectable layer.
- 5.5.2.5 The portrayed terrain feature shall be linked to the following associated attributes in the database(s):
 - a) Horizontal positions of grid points in geographic coordinates and elevations of the points;
 - b) Surface type;
 - c) Contour line values, if provided; and
 - d) Names of cities, towns and other prominent topographic features.
- 5.5.2.6 Additional terrain attributes provided in the database(s) should be linked to the portrayed terrain feature.

Specifications concerning terrain attributes are contained in PANS-AIM (Doc 10066), Appendix 6, Table A6-1.

- 5.5.3 Obstacle features
- 5.5.3.1 Obstacle features, and associated attributes, portrayed or database-linked to the chart shall be based on obstacle data sets which satisfy the requirements of Implementing Standard no 28, Chapter 5.
- 5.5.3.2 Each obstacle shall be portrayed by an appropriate symbol and obstacle identifier.
- 5.5.3.3 The portrayed obstacle feature shall be linked to the following associated attributes in the database(s):
 - a) Horizontal position in geographic coordinates and associated elevation;
 - b) Obstacle type; and
 - c) Obstacle extent, if appropriate.
- 5.5.3.4 Additional obstacle attributes provided in the database(s) should be linked to the portrayed obstacle feature.
- 5.5.4 Aerodrome features
- 5.5.4.1 Aerodrome features, and associated attributes, portrayed and database-linked to the chart shall be based on aerodrome data which satisfy the requirements of Implementing Standard no 28, Chapter 5.
- 5.5.4.2 The following aerodrome features shall be portrayed by an appropriate symbol:
 - a) Aerodrome reference point;

Page 40 of 133 4th Edition Rev: 00 Date: 28th October 2024

- b) Runway, with designation numbers, and if available, stop way(s) and clearway(s); and
- c) Taxiways, aprons, large buildings and other prominent aerodrome features.
- 5.5.4.3 The portrayed aerodrome feature shall be linked to the following associated attributes in the database(s):
 - a) Geographical coordinates of the aerodrome reference point;
 - b) Aerodrome magnetic variation, year of information and annual change;

Magnetic variation may be database-linked to the aerodrome reference point.

- c) Length and width of runway(s), stop way(s) and clearway(s);
- d) Type of surface of runway(s) and stop way(s);
- e) Magnetic bearings of the runway(s) to the nearest degree;
- f) Elevations at each end of runway(s), stop way(s) and clearway(s), and at each significant change in slope of runway(s) and stop way(s);
- g) Declared distances for each runway direction, or the abbreviation "NU" where a runway direction cannot be used for take-off or landing or both.
- 5.5.5 Radio navigation aid features

Each radio navigation aid feature located within the chart coverage shall be portrayed by an appropriate symbol.

5.6 Accuracy and resolution

- 5.6.1 The order of accuracy of aeronautical, terrain and obstacle data shall be in accordance with its intended use.
- 5.6.2 The aeronautical, terrain and obstacle data resolution shall be commensurate with the actual data accuracy.

5.7 Electronic functionality

- 5.7.1 It shall be possible to vary the scale at which the chart is viewed. Symbols and text size shall vary with chart scale to enhance readability.
- 5.7.2 Information on the chart shall be geo-referenced, and it shall be possible to determine cursor position to at least the nearest second.
- 5.7.3 The chart shall be compatible with widely available desktop computer hardware, software and media.
- 5.7.4 The chart should include its own "reader" software.

Page 41 of 133 4th Edition Rev: 00 Date: 28th October 2024

- 5.7.5 The information published in the respective chart shall not be removed without authorized update.
- 5.7.6 When, due to congestion of information, the details necessary to support the function of the chart cannot be shown with sufficient clarity on a single comprehensive chart view, selectable information layers shall be provided to allow for the customized combination of information.
- 5.7.7 It shall be possible to print the chart in hard copy format according to the content specifications and scale determined by the user.

5.8 Chart data product specifications

- 5.8.1 A comprehensive statement of the data sets comprising the chart shall be provided in the form of data product specifications on which basis air navigation users will be able to evaluate the chart data product and determine whether it fulfils the requirements for its intended use (application).
- 5.8.2 The chart data product specifications shall include an overview, a specification scope, a data product identification, data content information, the reference systems used, the data quality requirements, and information on data capture, data maintenance, data portrayal, data product delivery, as well as any additional information available, and metadata.
 - ISO Standard 19131 specifies the requirements and outline of data product specifications for geographic information.
- 5.8.3 The overview of the chart data product specifications shall provide an informal description of the product and shall contain general information about the data product. The specification scope of the chart data product specifications shall contain the spatial (horizontal) extent of the chart coverage. The chart data product identification shall include the title of the product, a brief narrative summary of the content and purpose, and a description of the geographic area covered by the chart.
- 5.8.4 The data content of the chart data product specifications shall clearly identify the type of coverage and/or imagery and shall provide a narrative description of each.
 - ISO Standard 19123 contains schema for coverage geometry and functions.
- 5.8.5 The chart data product specifications shall include information that defines the reference systems used. This shall include the spatial reference system (horizontal and vertical) and, if appropriate, temporal reference system. The chart data product specifications shall identify the data quality requirements. This shall include a statement on acceptable conformance quality levels and corresponding data quality measures. This statement shall cover all the data quality elements and data quality sub-elements, even if only to state that a specific data quality element or sub-element is not applicable.
- 5.8.6 The chart data product specifications shall include a data capture statement which shall be a general description of the sources and of processes applied for the capture of chart data. The principles and criteria applied in the maintenance of the chart shall also be provided in the chart

Page 42 of 132 3rd Edition Rev: 00 Date: 16th December 2022

Compliance to Annex 04 – Aeronautical Charts Attachment No. IS-04-Att.

data product specifications, including the frequency with which the chart product is updated. Of particular importance shall be the maintenance information of obstacle data sets included on the chart and an indication of the principles, methods and criteria applied for obstacle data maintenance.

- 5.8.7 The chart data product specifications shall contain information on how data are portrayed on the chart, as detailed in 5.5.1.1. The chart data product specifications shall also contain data product delivery information which shall include delivery formats and delivery medium information.
- 5.8.8 The core chart metadata elements shall be included in the chart data product specifications. Any additional metadata items required to be supplied shall be stated in the product specifications together with the format and encoding of the metadata.

Page 43 of 133 4th Edition Rev: 00 Date: 28th October 2024

6. CHAPTER 6 - PRECISION APPROACH TERRAIN CHART — ICAO

6.1 Function

Precision Approach Terrain Chart – ICAO shall provide detailed terrain profile information within a defined portion of the final approach so as to enable aircraft operating agencies to assess the effect of the terrain on decision height determination by the use of radio altimeters.

6.2 Availability

- 6.2.1 The Precision Approach Terrain Chart ICAO shall be made available for all precision approach runways Categories II and III at aerodromes used by international civil aviation, except where the requisite information is provided in the Aerodrome Terrain and Obstacle Chart ICAO (Electronic) in accordance with Chapter 5.
- 6.2.2 The Precision Approach Terrain Chart ICAO, shall be revised whenever any significant change occurs.

6.3 Scale

- 6.3.1 The horizontal scale should be 1:2500, and the vertical scale 1:500.
- 6.3.2 When the chart includes a profile of the terrain to a distance greater than 900 m (3 000 ft) from the runway threshold, the horizontal scale should be 1:5 000.

6.4 Identification

The chart shall be identified by the word "Sri Lanka" succeeded by, the name of the city or town or area which the aerodrome serves, the name of the aerodrome and the designator of the runway.

6.5 Plan and profile information

- 6.5.1 Precision Approach Terrain Chart ICAO shall include:
 - a) a plan showing contours at 1 m (3 ft) intervals in the area 60 m (200 ft) on either side of the extended centre line of the runway, to the same distance as the profile, the contours to be related to the runway threshold;
 - b) an indication where the terrain or any object thereon, within the plan defined in a), differs by 3 m (10 ft) in height from the centre line profile and is likely to affect a radio altimeter;
 - c) a profile of the terrain to a distance of 900 m (3 000 ft) from the threshold along the extended centre line of the runway.

Compliance to Annex 04 – Aeronautical Charts Attachment No. IS-04-Att.

6.5.2 Where the terrain at a distance greater than 900 m (3 000 ft) from the runway threshold is mountainous or otherwise significant to users of the chart, the profile of the terrain should be shown to a distance not exceeding 2 000 m (6 500 ft) from the runway threshold.

6.5.3 The ILS reference datum height should be shown to the nearest half metre or foot.

Page 45 of 133 4th Edition Rev: 00 Date: 28th October 2024

7. CHAPTER 7 – ENROUTE CHART — ICAO

7.1 Function

Enroute Chart – ICAO shall provide flight crews with information to facilitate navigation along ATS routes in compliance with air traffic services procedures.

Simplified versions of these charts are appropriate for inclusion in Aeronautical Information Publications to complement the tabulation of communication and navigation facilities.

7.2 Availability

- 7.2.1 The Enroute Chart ICAO shall be made available in the manner prescribed in 1.3.2 for all areas where flight information regions have been established.

 Under certain conditions, an Area Chart ICAO may have to be provided. (See Chapter 8.)
- 7.2.2 Where different air traffic services routes, position reporting requirements or lateral limits of flight information regions or control areas exist in different layers of airspace and cannot be shown with sufficient clarity on one chart, separate charts shall be provided.

7.3 Coverage and scale

A uniform scale for charts of this type cannot be specified due to the varying degree of congestion of information in certain areas.

A linear scale based on the mean scale of the chart may be shown.

- 7.3.1 Layout of sheet lines should be determined by the density and pattern of the ATS route structure.
- 7.3.2 Large variations of scale between adjacent charts showing a continuous route structure shall be avoided.
- 7.3.3 An adequate overlap of charts shall be provided to ensure continuity of navigation.

7.4 Projection

- 7.4.1 A conformal projection on which a straight line approximates a great circle should be used.
- 7.4.2 Parallels and meridians shall be shown at suitable intervals.
- 7.4.3 Graduation marks shall be placed at consistent intervals along selected parallels and meridians.

Page 46 of 133 4th Edition Rev: 00 Date: 28th October 2024

7.5 Identification

Each sheet shall be identified by chart series and number.

7.6 Culture and topography

- 7.6.1 Generalized shore lines of all open water areas, large lakes and rivers shall be shown except where they conflict with data more applicable to the function of the chart.
- 7.6.2 Within each quadrilateral formed by the parallels and meridians, the area minimum altitude shall be shown.

Quadrilaterals formed by the parallels and meridians normally correspond to the whole degree of latitude and longitude. Regardless of the chart scale being used, the area minimum altitude relates to the consequent quadrilateral.

Refer to the Procedures for Air Navigation —Aircraft Operations (PANS OPS, Doc 8168), Volume II, Part I, Section 2, Chapter 1, 1.8, for method for determination of area minimum altitude.

7.6.3 Where charts are not True North orientated, this fact and the selected orientation used shall be clearly indicated.

7.7 Magnetic variation

Isogonal should be indicated and the date of the isogonic information given.

7.8 Bearings, tracks and radials

- 7.8.1 Bearings, tracks and radials shall be magnetic. Where bearings and tracks are additionally provided as true values for RNAV segments, they shall be shown in parentheses to the nearest tenth of a degree, e.g.290° (294.9°T).
- 7.8.2 Where bearings, tracks or radials are given with reference to True North or Grid North, this shall be clearly indicated. When Grid North is used, its reference grid meridian shall be identified.

7.9 Aeronautical data

7.9.1 Aerodromes

All aerodromes used by international civil aviation and/or other aerodromes to which an instrument approach can be made shall be shown.

7.9.2 Prohibited, restricted and danger areas

Prohibited, restricted and danger areas relevant to the layer of airspace shall be depicted with their identification and vertical limits.

7.9.3 Air traffic services system

Page 47 of 133 4th Edition Rev: 00 Date: 28th October 2024

- 7.9.3.1 The components of the established air traffic services system shall be shown.
- 7.9.3.1.1 The components shall include the following:
 - a) the radio navigation aids associated with the air traffic services system together with their names, identifications, frequencies and geographical coordinates in degrees, minutes and seconds;
 - b) in respect of DME, additionally the elevation of the transmitting antenna of the DME to the nearest 30 m (100 ft);
 - c) an indication of all designated airspace, including lateral and vertical limits and the appropriate class of airspace;
 - d) All ATS routes for en-route flight including route designators, the track to the nearest degree in both directions along each segment of the routes and, where established, the designation of the navigation specification(s) including any limitations and the direction of traffic flow;

Guidance material on the organization of ATS routes for en-route flight publication which may be used to facilitate charting is contained in the Aeronautical Information Services Manual (Doc 8126).

- e) all significant points which define the ATS routes and are not marked by the position of a radio navigation aid, together with their name-codes and geographical coordinates in degrees, minutes and seconds;
- f) in respect of waypoints defining VOR/DME area navigation routes, additionally,
- 1) the station identification and radio frequency of the reference VOR/DME;
- 2) the bearing to the nearest tenth of a degree and the distance to the nearest two-tenths of a kilometer (tenth of a nautical mile) from the reference VOR/ DME, if the waypoint is not collocated with it:
- g) an indication of all compulsory and "on-request" reporting points and ATS/MET reporting points;
- h) the distances to the nearest kilometer or nautical mile between significant points constituting turning points or reporting points;

Overall distances between radio navigation aids may also be shown.

 i) change-over points on route segments defined by reference to very high frequency omnidirectional radio ranges, indicating the distances to the nearest kilometre or nautical mile to the navigation aids;

Page 48 of 133 4th Edition Rev: 00 Date: 28th October 2024

Compliance to Annex 04 – Aeronautical Charts Attachment No. IS-04-Att.

Change-over points established at the mid-point between two aids, or at the intersection of two radials in the case of a route which changes direction between the aids, need not be shown for each route segment if a general statement regarding their existence is made.

- j) Minimum en-route altitudes and minimum obstacle clearance altitudes, on ATS routes to the nearest higher 50 metres or 100 feet (see Implementing Standard no 25 para, 2.22);
- k) Communication facilities listed with their channels and, if applicable, logon address and satellite voice communications (SATVOICE) number; and
- l) Air defence identification zone (ADIZ) properly identified.

ADIZ procedures may be described in the chart legend.

- 7.9.4 Supplementary information
- 7.9.4.1 Details of departure and arrival routes and associated holding patterns in terminal areas shall be shown unless they are shown on an Area Chart, a Standard Departure Chart Instrument (SID) ICAO or a Standard Arrival Chart Instrument (STAR) ICAO.

Departure routes originate at the end of a runway; arrival routes normally terminate at the point where an instrument approach is initiated.

7.9.4.2 Altimeter setting regions shall be shown and identified.

Page 49 of 133 4th Edition Rev: 00 Date: 28th October 2024

8. CHAPTER 8 - AREA CHART — ICAO

8.1 Function

Area chart – ICAO shall provide the flight crew with information to facilitate the following phases of instrument flight:

- a) the transition between the en-route phase and approach to an aerodrome;
- b) the transition between take-off/missed approach and en-route phase of flight; and
- c) flights through areas of complex ATS routes or airspace structure.

The function described in 8.1 c) may be satisfied by a separate chart or an inset on an Enroute Chart — ICAO.

8.2 Availability

- 8.2.1 The Area Chart ICAO shall be made available in the manner prescribed in 1.3.2 where air traffic services routes or position reporting requirements are complex and cannot be adequately shown on an Enroute Chart ICAO.
- 8.2.2 Where air traffic services routes or position reporting requirements are different for arrivals and departures, and these cannot be shown with sufficient clarity on one chart, separate charts shall be provided.

Under certain conditions, a Standard Departure Chart — Instrument (SID) — ICAO and a Standard Arrival Chart — Instrument (STAR) — ICAO may have to be provided (see Chapters 9 and 10).

8.3 Coverage and scale

- 8.3.1 The coverage of each chart shall extend to points that effectively show departure and arrival routes.
- 8.3.2 The chart shall be drawn to scale and a scale-bar shown.

8.4 Projection

- 8.4.1 A conformal projection on which a straight line approximates a great circle should be used.
- 8.4.2 Parallels and meridians shall be shown at suitable intervals.
- 8.4.3 Graduation marks shall be placed at consistent intervals along the neat lines, as appropriate.

8.5 Identification

The chart shall be identified by a name associated with the airspace portrayed.

Page 50 of 133 4th Edition Rev: 00 Date: 28th October 2024

The name may be that of the air traffic services centre, the name of the largest city or town situated in the area covered by the chart or the name of the city that the aerodrome serves. Where more than one aerodrome serves the city or town, the name of the aerodrome on which the procedures are based should be added.

8.6 Culture and topography

- 8.6.1 Generalized shorelines of all open water areas, large lakes and rivers shall be shown except where they conflict with data more applicable to the function of the chart.
- 8.6.2 To improve situational awareness in areas where significant relief exists, all relief exceeding 300 m (1 000 ft) above the elevation of the primary aerodrome should be shown by smoothed contour lines, contour values and layer tints printed in brown. Appropriate spot elevations, including the highest elevation within each top contour line, should be shown printed in black. Obstacles should also be shown.

The next higher suitable contour line appearing on base topographic maps exceeding 300 m (1 000 ft) above the elevation of the primary aerodrome may be selected to start layer tinting.

An appropriate brown colour, on which half-tone layer tinting is to be based, is specified in Appendix 3 — Colour Guide for contours and topographic features.

Appropriate spot elevations and obstacles are those provided by the procedures specialist.

8.7 Magnetic variation

The average magnetic variation of the area covered by the chart shall be shown to the nearest degree.

8.8 Bearings, tracks and radials

- 8.8.1 Bearings, tracks and radials shall be magnetic. Where bearings and tracks are additionally provided as true values for RNAV segments, they shall be shown in parentheses to the nearest tenth of a degree, e.g. 290° (294.9°T).
- 8.8.2 Where bearings, tracks or radials are given with reference to True North or Grid North, this shall be clearly indicated. When Grid North is used, its reference grid meridian shall be identified.

8.9 Aeronautical data

8.9.1 Aerodromes

All aerodromes which affect the terminal routings shall be shown. Where appropriate, a runway pattern symbol shall be used.

8.9.2 Prohibited, restricted and danger areas

Page 51 of 133 4th Edition Rev: 00 Date: 28th October 2024

Prohibited, restricted and danger areas shall be depicted with their identification and vertical limits.

8.9.3 Area minimum altitudes

Area minimum altitudes shall be shown within quadrilaterals formed by the parallels and meridians.

Quadrilaterals formed by the parallels and meridians normally correspond to the whole degree of latitude and longitude. Regardless of the chart scale being used, the area minimum altitude relates to the consequent quadrilateral.

- 8.9.4 Air traffic services system
- 8.9.4.1 The components of the established relevant air traffic services system shall be shown.
- 8.9.4.1.1 The components shall include the following:
 - a) the radio navigation aids associated with the air traffic services system, together with their names, identifications, frequencies and geographical coordinates in degrees, minutes and seconds;
 - b) in respect of DME, additionally the elevation of the transmitting antenna of the DME to the nearest 30 m (100 ft);
 - c) terminal radio aids which are required for outbound and inbound traffic and for holding patterns;
 - d) the lateral and vertical limits of all designated airspace and the appropriate class of airspace;
 - e) the designation of the navigation specification(s) including any limitations, where established;
 - f) holding patterns and terminal routings, together with the route designators, and the track to the nearest degree along each segment of the prescribed airways and terminal routings;
 - g) all significant points which define the terminal routings and are not marked by the position of a radio navigation aid, together with their name-codes and geographical coordinates in degrees, minutes and seconds;
 - h) in respect of waypoints defining VOR/DME area navigation routes, additionally,
 - 1) the station identification and radio frequency of the reference VOR/DME;
 - 2) the bearing to the nearest tenth of a degree and the distance to the nearest two-tenths of a kilometre (tenth of a nautical mile) from the reference VOR/DME, if the waypoint is not collocated with it;
 - i) an indication of all compulsory and "on-request" reporting points;
 - j) the distances to the nearest kilometre or nautical mile between significant points constituting turning points or reporting points;

Overall distances between radio navigation aids may also be shown.

k) change-over points on route segments defined by reference to very high frequency omnidirectional radio ranges, indicating the distances to the nearest kilometre or nautical mile to the radio navigation aids;

Change-over points established at midpoint between two aids, or at the intersection of two radials in the case of a route which changes direction between the aids, need not be shown for each route segment if a general statement regarding their existence is made.

- 1) minimum en-route altitudes and minimum obstacle clearance altitudes, on ATS routes to the nearest higher 50 metres or 100 feet (see Implementing Standard no 25 Chapter 11, 2.23);
- m) established minimum vectoring altitudes to the nearest higher 50 m or 100 ft, clearly identified;

Where ATS surveillance systems are used to vector aircraft to or from significant points on a published standard departure or arrival route or to issue clearance for descent below the minimum sector altitude during arrival, the relevant procedures may be shown on the Area Chart — ICAO unless excessive chart clutter will result.

- n) area speed and level/altitude restrictions where established;
- o) communication facilities listed with their channels and, if applicable, logon address and SATVOICE number; and
- p) an indication of "flyover" significant points.

Page 53 of 133 4th Edition Rev: 00 Date: 28th October 2024

9. CHAPTER 9 - STANDARD DEPARTURE CHART — INSTRUMENT (SID) — ICAO

9.1 Function

Standard Departure Chart – Instrument (SID) – ICAO shall provide the flight crew with information to enable it to comply with the designated standard departure route — instrument from take-off phase to the en-route phase.

Provisions governing the identification of standard departure routes are in Implementing Standard no 25, Appendix 3; guidance material relating to the establishment of such routes is contained in the Air Traffic Services Planning Manual (Doc 9426).

Provisions governing obstacle clearance criteria and details of the minimum information to be published are contained in the Procedures for Air Navigation Services — Aircraft Operations (PANS-OPS, Doc 8168), Volume II, Part II.

9.2 Availability

The Standard Departure Chart — Instrument (SID) — ICAO shall be made available wherever a standard departure route — instrument has been established and cannot be shown with sufficient clarity on the Area Chart — ICAO.

9.3 Coverage and scale

9.3.1 The coverage of the chart shall be sufficient to indicate the point where the departure route begins and the specified significant point at which the en-route phase of flight along a designated air traffic services route can be commenced.

The departure route normally originates at the end of a runway.

- 9.3.2 The chart should be drawn to scale.
- 9.3.3 If the chart is drawn to scale, a scale-bar shall be shown.
- 9.3.4 When the chart is not drawn to scale, the annotation "NOT TO SCALE" shall be shown and the symbol for scale- break shall be used on tracks and other aspects of the chart which are too large to be drawn to scale.

9.4 Projection

- 9.4.1 A conformal projection on which a straight line approximates a great circle should be used.
- 9.4.2 When the chart is drawn to scale, parallels and meridians should be shown at suitable intervals.
- 9.4.3 Graduation marks shall be placed at consistent intervals along the neat lines.

9.5 Identification

Page 54 of 133 4th Edition Rev: 00 Date: 28th October 2024

The chart shall be identified by the name of the city or town or area which the aerodrome serves, the name of the aerodrome and the identification of the standard departure route(s) — instrument as established in accordance with the Procedures for Air Navigation Services — Aircraft Operations (PANS-OPS, Doc 8168), Volume II, Part I, Section 3, Chapter 5.

The identification of the standard departure route(s) — instrument is provided by the procedures specialist.

9.6 Culture and topography

- 9.6.1 Where the chart is drawn to scale, generalized shore lines of all open water areas, large lakes and rivers shall be shown except where they conflict with data more applicable to the function of the chart.
- 9.6.2 To improve situational awareness in areas where significant relief exists, the chart should be drawn to scale and all relief exceeding 300 m (1 000 ft) above the aerodrome elevation should be shown by smoothed contour lines, contour values and layer tints printed in brown. Appropriate spot elevations, including the highest elevation within each top contour line, should be shown printed in black. Obstacles should also be shown.

The next higher suitable contour line appearing on base topographic maps exceeding 300 m (1 000 ft) above the aerodrome elevation may be selected to start layer tinting.

Appropriate spot elevations and obstacles are those provided by the procedures specialist.

9.7 Magnetic variation

Magnetic variation used in determining the magnetic bearings, tracks and radials shall be shown to the nearest degree.

9.8 Bearings, tracks and radials

9.8.1 Bearings, tracks and radials shall be magnetic. Where bearings and tracks are additionally provided as true values for RNAV segments, they shall be shown in parentheses to the nearest tenth of a degree, e.g. 290° (294.9°T).

A note to this effect may be included on the chart.

9.8.2 Where bearings, tracks or radials are given with reference to True North or Grid North, this shall be clearly indicated. When Grid North is used, its reference grid meridian shall be identified.

9.9 Aeronautical data

- 9.9.1 Aerodromes
- 9.9.1.1 The aerodrome of departure shall be shown by the runway pattern.

- 9.9.1.2 All aerodromes which affect the designated standard departure route instrument shall be shown and identified. Where appropriate, the aerodrome runway patterns shall be shown.
- 9.9.2 Prohibited, restricted and danger areas

Prohibited, restricted and danger areas which may affect the execution of the procedures shall be shown with their identification and vertical limits.

- 9.9.3 Minimum sector altitude
- 9.9.3.1 The established minimum sector altitude shall be shown with a clear indication of the sector to which it applies.
- 9.9.3.2 Where the minimum sector altitude has not been established, the chart shall be drawn to scale and area minimum altitudes shall be shown within quadrilaterals formed by the parallels and meridians. Area minimum altitudes shall also be shown in those parts of the chart not covered by the minimum sector altitude.

Quadrilaterals formed by the parallels and meridians normally correspond to the half degree of latitude and longitude. Regardless of the chart scale being used, the area minimum altitude relates to the consequent quadrilateral.

- 9.9.4 Air traffic services system
- 9.9.4.1 The components of the established relevant air traffic services system shall be shown.
- 9.9.4.1.1 The components shall comprise the following:
 - a) a graphic portrayal of each standard departure route instrument, including:
 - 1) for departure procedures designed specifically for helicopters, the term "CAT H" shall be depicted in the departure chart plan view;
 - 2) route designator;
 - 3) significant points defining the route;
 - 4) track or radial to the nearest degree along each segment of the route;
 - 5) distances to the nearest kilometre or nautical mile between significant points
 - 6) minimum obstacle clearance altitudes, along the route or route segments and altitudes required by the procedure to the nearest higher 50 m or 100 ft and flight level restrictions where established;
 - 7) where the chart is drawn to scale and vectoring on departure is provided, established minimum vectoring altitudes to the nearest higher 50 m or 100 ft, clearly identified;

Page 56 of 133 4th Edition Rev: 00 Date: 28th October 2024

Where ATS surveillance systems are used to vector aircraft to or from significant points on a published standard departure route, the relevant procedures may be shown on the Standard Departure Chart — Instrument (SID) — ICAO unless excessive chart clutter will result.

Where excessive chart clutter will result, an ATC Surveillance Minimum Altitude Chart — ICAO may be provided (see Chapter 21), in which case the elements indicated by 9.9.4.1.1, a) 6), need not be duplicated on the Standard Departure Chart — Instrument (SID) — ICAO.

- b) the radio navigation aid(s) associated with the route(s) including:
 - 1) when the radio navigation aid is used for conventional navigation:
- i) plain language name;
- ii) identification;
- iii) Morse Code;
- iv) frequency;
- v) geographical coordinates in degrees, minutes and seconds;
- vi) for DME, the channel and the elevation of the transmitting antenna of the DME to the nearest 30 m (100 ft);
 - 2) when the radio navigation aid is used as a significant point for area navigation:
- i) plain language name;
- ii) identification;
- c) significant points not marked by the position of a radio navigation aid including;
 - 1) when the significant point is used for conventional navigation:
- i) name-code;
- ii) geographical coordinates in degrees, minutes and seconds;
- iii) bearing to the nearest tenth of a degree from the reference radio navigation aid;
- iv) distance to the nearest two-tenths of a kilometre (tenth of a nautical mile) from the reference radio navigation aid;
- v) identification of the reference radio navigation aid;
 - 2) when the significant point is used for area navigation:
- i) name-code;

- d) applicable holding patterns;
- e) transition altitude/height to the nearest higher 300 m or 1 000 ft;
- f) the position and height of close-in obstacles which penetrate the obstacle identification surface (OIS). A note shall be included whenever close-in obstacles penetrating the OIS exist but which were not considered for the published procedure design gradient;

In accordance with PANS-OPS, Volume II, information on close-in obstacles is provided by the procedures specialist.

- g) area speed restrictions, where established;
- h) for PBN procedures, a PBN requirements box;

Refer to the Procedures for Air Navigation Services — Aircraft Operations (PANS-OPS, Doc 8168), Volume II, Part III, Section 5 for information on a PBN requirements box.

- i) all compulsory and "on-request" reporting points;
- j) radio communication procedures, including:
- 1) call sign(s) of ATS unit(s);
- 2) frequency and, if applicable, SATVOICE number;
- 3) transponder setting, where appropriate;
- k) an indication of "flyover" significant points.
- 9.9.4.2 A textual description of standard departure route(s) instrument (SID) and relevant communication failure procedures should be provided and should, whenever feasible, be shown on the chart or on the same page which contains the chart.
- 9.9.4.3 Aeronautical database requirements

Appropriate data to support navigation database coding shall be published in accordance with the Procedures for Air Navigation Services — Aircraft Operations (PANS-OPS, Doc 8168), Volume II, Part III, Section 5, Chapter 2, 2.1, on the verso of the chart or as a separate, properly referenced sheet.

Appropriate data are those provided by the procedures specialist.

Page 58 of 133 4th Edition Rev: 00 Date: 28th October 2024

10. CHAPTER 10 - STANDARD ARRIVAL CHART — INSTRUMENT (STAR) — ICAO

10.1 Function

Standard Arrival Chart-Instrument (STAR)-ICAO shall provide the flight crew with information to enable it to comply with the designated standard arrival route—instrument from the en-route phase to the approach phase.

Standard arrival routes — instrument are to be interpreted as including "standard descent profiles", "continuous descent approach", and other non-standard descriptions. In the case of a standard descent profile, the depiction of a cross-section is not required.

Provisions governing the identification of standard arrival routes are in IS25, Appendix 3; guidance material relating to the establishment of such routes is contained in the Air Traffic Services Planning Manual (Doc 9426).

10.2 Availability

The Standard Arrival Chart — Instrument (STAR) — ICAO shall be made available wherever a standard arrival route — instrument has been established and cannot be shown with sufficient clarity on the Area Chart.

10.3 Coverage and scale

- 10.3.1 The coverage of the chart shall be sufficient to indicate the points where the en-route phase ends and the approach phase begins.
- 10.3.2 The chart should be drawn to scale.
- 10.3.3 If the chart is drawn to scale, a scale-bar shall be shown.
- 10.3.4 When the chart is not drawn to scale, the annotation "NOT TO SCALE" shall be shown and the symbol for scale break shall be used on tracks and other aspects of the chart which are too large to be drawn to scale.

10.4 Projection

- 10.4.1 A conformal projection on which a straight line approximates a great circle should be used.
- 10.4.2 When the chart is drawn to scale, parallels and meridians should be shown at suitable intervals.
- 10.4.3 Graduation marks shall be placed at consistent intervals along the neat lines.

Page 59 of 133 4th Edition Rev: 00 Date: 28th October 2024

10.5 Identification

The chart shall be identified by the name of the city or town or area which the aerodrome serves, the name of the aerodrome, and the identification of the standard arrival route(s) — instrument as established in accordance with the Procedures for Air Navigation Services — Aircraft Operations (PANS-OPS, Doc 8168), Volume II, Part I, Section 4, Chapter 2.

The identification of the standard arrival route(s) — instrument is provided by the procedures specialist.

10.6 Culture and topography

- 10.6.1 Where the chart is drawn to scale, generalized shore lines of all open water areas, large lakes and rivers shall be shown except where they conflict with data more applicable to the function of the chart.
- 10.6.2 To improve situational awareness in areas where significant relief exists, the chart should be drawn to scale and all relief exceeding 300 m (1 000 ft) above the aerodrome elevation should be shown by smoothed contour lines, contour values and layer tints printed in brown. Appropriate spot elevations, including the highest elevation within each top contour line, should be shown printed in black. Obstacles should also be shown.

The next higher suitable contour line appearing on base topographic maps exceeding 300 m (1 000 ft) above the aerodrome elevation may be selected to start layer tinting.

An appropriate brown colour, on which half-tone layer tinting is to be based, is specified in Appendix 3 — Colour Guide for contours and topographic features.

Appropriate spot elevations and obstacles are those provided by the procedures specialist.

10.7 Magnetic variation

Magnetic variation used in determining the magnetic bearings, tracks and radials shall be shown to the nearest degree.

10.8 Bearings, tracks and radials

10.8.1 Bearings, tracks and radials shall be magnetic. Where bearings and tracks are additionally provided as true values for RNAV segments, they shall be shown in parentheses to the nearest tenth of a degree, e.g. 290° (294.9°T).

A note to this effect may be included on the chart.

Page 60 of 133 4th Edition Rev: 00 Date: 28th October 2024

10.8.2 Where bearings, tracks or radials are given with reference to True North or Grid North, this shall be clearly indicated. When Grid North is used, its reference grid meridian shall be identified.

10.9 Aeronautical data

- 10.9.1 Aerodromes
- 10.9.1.1 The aerodrome of landing shall be shown by the runway pattern.
- 10.9.1.2 All aerodromes which affect the designated standard arrival route instrument shall be shown and identified. Where appropriate, the aerodrome runway patterns shall be shown.
- 10.9.2 Prohibited, restricted and danger areas

Prohibited, restricted and danger areas which may affect the execution of the procedures shall be shown with their identification and vertical limits.

- 10.9.3 Minimum sector altitude
- 10.9.3.1 The established minimum sector altitude shall be shown with a clear indication of the sector to which it applies.
- 10.9.3.2 Where the minimum sector altitude has not been established, the chart shall be drawn to scale and area minimum altitudes shall be shown within quadrilaterals formed by the parallels and meridians. Area minimum altitudes shall also be shown in those parts of the chart not covered by the minimum sector altitude.

Quadrilaterals formed by the parallels and meridians normally correspond to the half degree of latitude and longitude. Regardless of the chart scale being used, the area minimum altitude relates to the consequent quadrilateral.

Refer to the Procedures for Air Navigation — Aircraft Operations (PANS OPS, Doc 8168), Volume II, Part I, Section 2, Chapter 1, 1.8, for method for determination of area minimum altitude.

10.9.4 Air traffic services system

- 10.9.4.1 The components of the established relevant air traffic services system shall be shown.
- 10.9.4.1.1 The components shall comprise the following:
 - a) a graphic portrayal of each standard arrival route instrument, including:
 - 1) route designator;
 - 2) significant points defining the route;
 - 3) track or radial to the nearest degree along each segment of the route;

Page 61 of 133 4th Edition Rev: 00 Date: 28th October 2024

- 4) distances to the nearest kilometre or nautical mile between significant points;
- 5) minimum obstacle clearance altitudes, along the route or route segments and altitudes required by the procedure to the nearest higher 50 m or 100 ft and flight level restrictions where established:
- 6) where the chart is drawn to scale and vectoring on arrival is provided, established minimum vectoring altitudes to the nearest higher 50 m or 100 ft, clearly identified;

Where ATS surveillance systems are used to vector aircraft to or from significant points on a published standard arrival route or to issue clearance for descent below the minimum sector altitude during arrival, the relevant procedures may be shown on the Standard Arrival Chart— *Instrument (STAR)* — *ICAO unless excessive chart clutter will result.*

Where excessive chart clutter will result, an ATC Surveillance Minimum Altitude Chart — ICAO may be provided (see Chapter 21), in which case the elements indicated by 10.9.4.1.1, a) 6), need not be duplicated on the Standard Arrival Chart — Instrument (STAR) — ICAO.
b) the radio navigation aid(s) associated with the route(s) including:
when the radio navigation aid is used for conventional navigation: i) plain language name;
ii) identification;
iii) Morse code;
iv) frequency;
v) geographical coordinates in degrees, minutes and seconds;
vi) for DME, the channel and the elevation of the transmitting antenna of the DME to the nearest 30 m (100 ft);
2) when the radio navigation aid is used as a significant point for area navigation: i) plain language name;
ii) identification
c) significant points not marked by the position of a radio navigation aid including:1) when the significant point is used for conventional navigation:

4th Edition Date: 28th October 2024 Rev: 00 Page 62 of 133

i) name-code;

- ii) geographical coordinates in degrees, minutes and seconds;
- iii) bearing to the nearest tenth of a degree from the reference radio navigation aid;
- iv) distance to the nearest two-tenths of a kilometre (tenth of a nautical mile) from the reference radio navigation aid;
- v) identification of the reference radio navigation aid;
 - 2) when the significant point is used for area navigation:
- i) name-code;
- d) applicable holding patterns;
- e) transition altitude/height to the nearest higher 300 m or 1 000 ft;
- f) area speed restrictions, where established;
- g) for PBN procedures, a PBN requirements box;

Refer to the Procedures for Air Navigation Services — Aircraft Operations (PANS-OPS, Doc 8168), Volume II, Part III, Section 5 for information on a PBN requirements box.

- h) all compulsory and "on-request" reporting points;
- i) radio communication procedures, including:
 - 1) call sign(s) of ATS unit(s);
 - 2) frequency and, if applicable, SATVOICE number;
 - 3) transponder setting, where appropriate;
- i) an indication of "flyover" significant waypoints; and
- k) for arrival procedures to an instrument approach designed specifically for helicopters, the term "CAT H" shall be depicted in the arrival chart plan view.
- 10.9.4.2 A textual description of standard arrival route(s) instrument (STAR) and relevant communication failure procedures should be provided and should, whenever feasible, be shown on the chart or on the same page which contains the chart.

10.9.4.3 Aeronautical database requirements

Appropriate data to support navigation database coding shall be published in accordance with the Procedures for Air Navigation Services — Aircraft Operations (PANS-OPS, Doc 8168), Volume II, Part III, Section 5, Chapter 2, 2.2, on the verso of the chart or as a separate, properly referenced sheet.

Appropriate data are those provided by the procedures specialist.

Page 63 of 133 4th Edition Rev: 00 Date: 28th October 2024

11. CHAPTER 11 - INSTRUMENT APPROACH CHART — ICAO

11.1 Function

Instrument Approach Chart – ICAO shall provide flight crews with information which will enable them to perform an approved instrument approach procedure to the runway of intended landing including the missed approach procedure and, where applicable, associated holding patterns.

Detailed criteria for the establishment of instrument approach procedures and the resolutions of associated altitudes/heights are contained in the Procedures for Air Navigation Services — Aircraft Operations (PANS-OPS, Doc 8168).

11.2 Availability

- 11.2.1 Instrument Approach Charts ICAO shall be made available for all aerodromes used by the international civil aviation where instrument approach procedures have been established in Sri Lanka.
- 11.2.2 A separate Instrument Approach Chart ICAO shall be provided for each precision approach procedure established by Sri Lanka.
- 11.2.3 A separate Instrument Approach Chart ICAO shall be provided for each non-precision approach procedure established by Sri Lanka.
 - A single precision or non-precision approach procedure chart may be provided to portray more than one approach procedure when the procedures for the intermediate approach, final approach and missed approach segments are identical.
- 11.2.4 When the values for track, time or altitude differ between categories of aircraft on other than the final approach segment of the instrument approach procedures and the listing of these differences on a single chart could cause clutter or confusion, more than one chart shall be provided.
 - For categories of aircraft, see Procedures for Air Navigation Services Aircraft Operations (PANS-OPS, Doc 8168), Volume II, Part I, Section 4, Chapter 9.
- 11.2.5 Instrument Approach Charts ICAO shall be revised whenever information essential to safe operation becomes out of date.

11.3 Coverage and scale

11.3.1 The coverage of the chart shall be sufficient to include all segments of the instrument approach procedure and such additional areas as may be necessary for the type of approach intended.

Page 64 of 133 4th Edition Rev: 00 Date: 28th October 2024

- 11.3.2 The scale selected shall ensure optimum legibility consistent with:
 - a) the procedure shown on the chart;
 - b) sheet size.
- 11.3.3 A scale indication shall be given.
- 11.3.3.1 Except where this is not practicable, a distance circle with a radius of 20 km (10 NM) centred on a DME located on or close to the aerodrome, or on the aerodrome reference point where no suitable DME is available, shall be shown; its radius shall be indicated on the circumference.
- 11.3.3.2 A distance scale should be shown directly below the profile.

11.4 Format

The sheet size should be $210 \times 148 \text{ mm}$ (8.27 $\times 5.82 \text{ in}$).

11.5 Projection

- 11.5.1 A conformal projection on which a straight line approximates a great circle shall be used.
- 11.5.2 Graduation marks should be placed at consistent intervals along the neat lines.

11.6 Identification

The chart shall be identified by the name of the city or town or area which the aerodrome serves, the name of the aerodrome and the identification of the instrument approach procedure as established in accordance with the Procedures for Air Navigation Services — Aircraft Operations (PANS-OPS, Doc 8168), Volume II, Part I, Section 4, Chapter 9.

The identification of the instrument approach procedure is provided by the procedures specialist.

11.7 Culture and topography

- 11.7.1 Culture and topographic information pertinent to the safe execution of the instrument approach procedure, including the missed approach procedure, associated holding procedures and visual manoeuvring (circling) procedure when established, shall be shown. Topographic information shall be named, only when necessary, to facilitate the understanding of such information, and the minimum shall be a delineation of land masses and significant lakes and rivers.
- 11.7.2 Relief shall be shown in a manner best suited to the particular elevation characteristics of the area. In areas where relief exceeds 1 200 m (4 000 ft) above the aerodrome elevation within the coverage of the chart or 600 m (2 000 ft) within 11 km (6 NM) of the aerodrome reference point

Page 65 of 132 3rd Edition Rev: 00 Date: 16th December 2022

or when final approach or missed approach procedure gradient is steeper than optimal due to terrain, all relief exceeding 150 m (500 ft) above the aerodrome elevation shall be shown by smoothed contour lines, contour values and layer tints printed in brown. Appropriate spot elevations, including the highest elevation within each top contour line, shall also be shown printed in black.

The next higher suitable contour line appearing on base topographic maps exceeding 150 m (500 ft) above the aerodrome elevation may be selected to start layer tinting.

An appropriate brown colour, on which half-tone layer tinting is to be based, is specified in Appendix 3 — Colour Guide for contours and topographic features.

Appropriate spot elevations are those provided by the procedures specialist.

11.7.3 In areas where relief is lower than specified in 11.7.2, all relief exceeding 150 m (500 ft) above the aerodrome elevation should be shown by smoothed contour lines, contour values and layer tints printed in brown. Appropriate spot elevations, including the highest elevation within each top contour line, should also be shown printed in black.

The next higher suitable contour line appearing on base topographic maps exceeding 150 m (500 ft) above the aerodrome elevation may be selected to start layer tinting.

An appropriate brown colour, on which half-tone layer tinting is to be based, is specified in Appendix 3 — Colour Guide for contours and topographic features.

Appropriate spot elevations are those provided by the procedures specialist.

11.8 Magnetic variation

- 11.8.1 The magnetic variation should be shown.
- 11.8.2 When shown, the value of the variation, indicated to the nearest degree, shall agree with that used in determining magnetic bearings, tracks and radials.

11.9 Bearings, tracks and radials

11.9.1 Bearings, tracks and radials shall be magnetic. Where bearings and tracks are additionally provided as true values for RNAV segments, they shall be shown in parentheses to the nearest tenth of a degree, e.g. 290° (294.9°T).

A note to this effect may be included on the chart.

11.9.2 Where bearings, tracks or radials are given with reference to True North or Grid North, this shall be clearly indicated. When Grid North is used, its reference grid meridian shall be identified.

Page 66 of 133 4th Edition Rev: 00 Date: 28th October 2024

11.10 Aeronautical data

- 11.10.1 Aerodromes
- 11.10.1.1All aerodromes which show a distinctive pattern from the air shall be shown by the appropriate symbol. Abandoned aerodromes shall be identified as abandoned.
- 11.10.1.2The runway pattern, at a scale sufficiently large to show it clearly, shall be shown for:
 - a) the aerodrome on which the procedure is based;
 - b) aerodromes affecting the traffic pattern or so situated as to be likely, under adverse weather conditions, to be mistaken for the aerodrome of intended landing.
- 11.10.1.3 The aerodrome elevation shall be shown to the nearest metre or foot in a prominent position on the chart.
- 11.10.1.4 The threshold elevation or, where applicable, the highest elevation of the touchdown zone shall be shown to the nearest metre or foot.
- 11.10.2 Obstacles
- 11.10.2.1 Obstacles shall be shown on the plan view of the chart.

Appropriate obstacles are those provided by the procedures specialist.

- 11.10.2.2 If one or more obstacles are the determining factor of an obstacle clearance altitude/height, those obstacles should be identified.
- 11.10.2.3 The elevation of the top of obstacles shall be shown to the nearest (next higher) metre or foot.
- 11.10.2.4 The heights of obstacles above a datum other than mean sea level (see 11.10.2.3) should be shown. When shown, they should be given in parentheses on the chart.
- 11.10.2.5 When the heights of obstacles above a datum other than mean sea level are shown, the datum shall be the aerodrome elevation except that, at aerodromes having an instrument runway (or runways) with a threshold elevation more than 2 m (7 ft) below the aerodrome elevation, the chart datum shall be the threshold elevation of the runway to which the instrument approach is related.
- 11.10.2.6 Where a datum other than mean sea level is used, it shall be stated in a prominent position on the chart.
- 11.10.2.7 Where an obstacle free zone has not been established for a precision approach runway Category I, this shall be indicated.
- 11.10.3 Prohibited, restricted and danger areas

Page 67 of 133 4th Edition Rev: 00 Date: 28th October 2024

Prohibited areas, restricted areas, and danger areas which may affect the execution of the procedures shall be shown with their identification and vertical limits.

- 11.10.4 Radio communication facilities and navigation aids
- 11.10.4.1 Radio navigation aids required for the procedures together with their frequencies, identifications and track-defining characteristics, if any, shall be shown. In the case of a procedure in which more than one station is located on the final approach track, the facility to be used for track guidance for final approach shall be clearly identified. In addition, consideration shall be given to the elimination from the approach chart of those facilities that are not used by the procedure.
- 11.10.4.1.1 When a radio navigation aid is used as a significant point for area navigation, only its plain language name and identification shall be shown.
- 11.10.4.2 The initial approach fix (IAF), the intermediate approach fix (IF), the final approach fix (FAF) (or final approach point (FAP) for an ILS approach procedure), the missed approach point (MAPt), where established, and other essential fixes or points comprising the procedure shall be shown and identified.
- 11.10.4.3 When the final approach fix is used for conventional navigation (or final approach point for an ILS approach procedure), it should be identified with its geographical coordinates in degrees, minutes and seconds.
- 11.10.4.4 Radio navigation aids that might be used in diversionary procedures together with their track-defining characteristics, if any, shall be shown or indicated on the chart.
- 11.10.4.5 Radio communication frequencies, including call signs that are required for the execution of the procedures shall be shown.
- 11.10.4.6 When required by the procedures, the distance to the aerodrome from each radio navigation aid concerned with the final approach shall be shown to the nearest kilometre or nautical mile. When no track-defining aid indicates the bearing of the aerodrome, the bearing shall also be shown to the nearest degree.
- 11.10.5 Minimum sector altitude or terminal arrival altitude

The minimum sector altitude or terminal arrival altitude established by the competent authority shall be shown, with a clear indication of the sector to which it applies.

- 11.10.6 Portrayal of procedure tracks
- 11.10.6.1 The plan view shall show the following information in the manner indicated:
 - a) the approach procedure track by an arrowed continuous line indicating the direction of flight;
 - b) the missed approach procedure track by an arrowed broken line;

Page 68 of 133 4th Edition Rev: 00 Date: 28th October 2024

- c) any additional procedure track, other than those specified in a) and b), by an arrowed dotted line:
- d) bearings, tracks, radials to the nearest degree and distances to the nearest two-tenths of a kilometre or tenth of a nautical mile or times required for the procedure;
- e) where no track-defining aid is available, the magnetic bearing to the nearest degree to the aerodrome from the radio navigation aids concerned with the final approach;
- f) the boundaries of any sector in which visual manoeuvring (circling) is prohibited;
- g) where specified, the holding pattern and minimum holding altitude/height associated with the approach and missed approach;
- h) caution notes where required, prominently displayed on the face of the chart;
- i) an indication of "flyover" significant points.
- 11.10.6.2 The plan view should show the distance to the aerodrome from each radio navigation aid concerned with the final approach.
- 11.10.6.3 A profile shall be provided normally below the plan view showing the following data:
 - a) the aerodrome by a solid block at aerodrome elevation;
 - b) the profile of the approach procedure segments by an arrowed continuous line indicating the direction of flight;
 - c) the profile of the missed approach procedure segment by an arrowed broken line and a description of the procedure;
 - d) the profile of any additional procedure segment, other than those specified in b) and c), by an arrowed dotted line;
 - e) bearings, tracks, radials to the nearest degree and distances to the nearest two-tenths of a kilometre or tenth of a nautical mile or times required for the procedure;
 - f) altitudes/heights required by the procedures, including transition altitude, procedure altitudes/heights and heliport crossing height (HCH), where established;
 - g) limiting distance to the nearest kilometre or nautical mile on procedure turn, when specified;
 - h) the intermediate approach fix or point, on procedures where no course reversal is authorized;
 - i) a line representing the aerodrome elevation or threshold elevation, as appropriate, extended across the width of the chart including a distance scale with its origin at the runway threshold.
- 11.10.6.4 Heights required by procedures should be shown in parentheses, using the height datum selected in accordance with 11.10.2.5.
- 11.10.6.5 The profile view should include a ground profile or a minimum altitude/height portrayal as follows:
 - a) a ground profile shown by a solid line depicting the highest elevations of the relief occurring within the primary area of the final approach segment. The highest elevations of the relief occurring in the secondary areas of the final approach segment shown by a dashed line; or
 - b) minimum altitudes/heights in the intermediate and final approach segments indicated within bounded shaded blocks.

For the ground profile portrayal, actual templates of the primary and secondary areas of the final approach segment are provided to the cartographer by the procedures specialist.

The minimum altitude/height portrayal is intended for use on charts depicting non-precision approaches with a final approach fix.

- 11.10.7 Aerodrome operating minima
- 11.10.7.1 Aerodrome operating minima when established shall be shown.
- 11.10.7.2 The obstacle clearance altitudes/heights for the aircraft categories for which the procedure is designed shall be shown; for precision approach procedures, additional OCA/H for Cat D aircraft (wing span between 65 m and 80 m and/or vertical distance between the flight path of the wheels and the glide path antenna between 7 m and 8 m) shall be published, when necessary.
- 11.10.8 Supplementary information
- 11.10.8.1 When the missed approach point is defined by:
 - a distance from the final approach fix, or
 - a facility or a fix and the corresponding distance from the final approach fix,

the distance to the nearest two-tenths of a kilometre or tenth of a nautical mile and a table showing ground speeds and times from the final approach fix to the missed approach point shall be shown.

- 11.10.8.2 When DME is required for use in the final approach segment, a table showing altitudes/heights for each 2 km or 1 NM, as appropriate, shall be shown. The table shall not include distances which would correspond to altitudes/heights below the OCA/H.
- 11.10.8.3 For procedures in which DME is not required for use in the final approach segment but where a suitably located DME is available to provide advisory descent profile information, a table showing the altitudes/heights should be included.
- 11.10.8.4 A rate of descent table should be shown.
- 11.10.8.5 For non-precision approach procedures with a final approach fix, the final approach descent gradient to the nearest one-tenth of a per cent and, in parentheses, descent angle to the nearest one-tenth of a degree shall be shown.
- 11.10.8.6 For precision approach procedures and approach procedures with vertical guidance, the reference datum height to the nearest half metre or foot and the glide path/elevation/vertical path angle to the nearest one-tenth of a degree shall be shown.

- 11.10.8.7 When a final approach fix is specified at the final approach point for ILS, a clear indication shall be given whether it applies to the ILS, the associated ILS localizer only procedure, or both. In the case of MLS, a clear indication shall be given when an FAF has been specified at the final approach point.
- 11.10.8.8 If the final approach descent gradient/angle for any type of instrument approach procedure exceeds the maximum value specified in the Procedures for Air Navigation Services Aircraft Operations (PANS-OPS, Doc 8168), Volume II, a cautionary note shall be included.
- 11.10.8.9 A note shall be included on the chart indicating the approach procedures that are authorized for simultaneous independent or dependent operations. The note shall include the runway (s) involved and if they are closely spaced.
- 11.10.8.10 For approach procedures having PBN segments, a PBN requirements box shall be included.

Refer to the Procedures for Air Navigation Services — Aircraft Operations (PANS-OPS, Doc 8168), Volume II, Part III, Section 5 for information on a PBN requirements box.

11.10.9 Aeronautical database requirements

Appropriate data to support navigation database coding shall be published in accordance with the Procedures for Air Navigation Services — Aircraft Operations (PANS-OPS, Doc 8168), Volume II, Part III, Section 5, Chapter 2, 2.3, for RNAV procedures and Volume II, Part I, Section 4, Chapter 9, 9.4.1.3, for non-RNAV procedures, on the verso of the chart or as a separate, properly referenced sheet.

Appropriate data are those provided by the procedures specialist.

12. CHAPTER 12 - VISUAL APPROACH CHART — ICAO

12.1 Function

Visual Approach Chart — ICAO shall provide flight crews with information which will enable them to transit from the en-route/descent to approach phases of flight to the runway of intended landing by means of visual reference.

12.2 Availability

The Visual Approach Chart — ICAO shall be made available in the manner prescribed in 1.3.2 for all aerodromes used by the international civil aviation where:

- a) only limited navigation facilities are available; or
- b) radio communication facilities are not available; or
- c) no adequate aeronautical charts of the aerodrome and its surroundings at 1:500 000 or greater scale are available; or
- d) visual approach procedures have been established.

12.3 Scale

- 12.3.1 The scale shall be sufficiently large to permit depiction of significant features and indication of the aerodrome layout.
- 12.3.2 The scale should not be smaller than 1:500 000.

A scale of 1:250 000 or 1:200 000 is preferred.

12.3.3 When an Instrument Approach Chart is available for a given aerodrome, the Visual Approach Chart should be drawn to the same scale.

12.4 Format

The sheet size should be $210 \times 148 \text{ mm}$ (8.27 × 5.82 in).

12.5 Projection

- 12.5.1 A conformal projection on which a straight line approximates a great circle shall be used.
- 12.5.2 Graduation marks should be placed at consistent intervals along the neat lines.

12.6 Identification

The chart shall be identified by the name of the city or town which the aerodrome serves and the name of the aerodrome.

12.7 Culture and topography

- 12.7.1 Natural and cultural landmarks shall be shown (e.g. bluffs, cliffs, sand dunes, cities, towns, roads, railroads, isolated lighthouses).
- 12.7.1.1 Geographical place names should be included only when they are required to avoid confusion or ambiguity.
- 12.7.2 Shore lines, lakes, rivers and streams shall be shown.
- 12.7.3 Relief shall be shown in a manner best suited to the particular elevation and obstacle characteristics of the area covered by the chart.
- 12.7.4 When shown, spot elevations should be carefully selected.

The value of certain spot elevations/heights in relation to both mean sea level and aerodrome elevation may be given.

12.7.5 The figures relating to different reference levels shall be clearly differentiated in their presentation.

12.8 Magnetic variation

The magnetic variation shall be shown.

12.9 Bearings, tracks and radials

- 12.9.1 Bearings, tracks and radials shall be magnetic.
- 12.9.2 Where bearings, tracks or radials are given with reference to True North or Grid North, this shall be clearly indicated. When Grid North is used, its reference grid meridian shall be identified.

12.10 Aeronautical data

- 12.10.1 Aerodromes
- 12.10.1.1 All aerodromes shall be shown by the runway pattern. Restrictions on the use of any landing direction shall be indicated. Where there is any risk of confusion between two neighbouring aerodromes, this shall be indicated. Abandoned aerodromes shall be identified as abandoned.
- 12.10.1.2 The aerodrome elevation shall be shown in a prominent position on the chart.

12.10.2 Obstacles

Page 73 of 133 4th Edition Rev: 00 Date: 28th October 2024

- 12.10.2.1 Obstacles shall be shown and identified.
- 12.10.2.2 The elevation of the top of obstacles shall be shown to the nearest (next higher) metre or foot.
- 12.10.2.3 The heights of obstacles above the aerodrome elevation should be shown.
- 12.10.2.3.1 When the heights of obstacles are shown, the height datum shall be stated in a prominent position on the chart and the heights shall be given in parentheses on the chart.
- 12.10.3 Prohibited, restricted and danger areas

Prohibited areas, restricted areas, and danger areas shall be depicted with their identification and vertical limits.

12.10.4 Designated airspace

Where applicable, control zones and aerodrome traffic zones shall be depicted with their vertical limits and the appropriate class of airspace.

- 12.10.5 Visual approach information
- 12.10.5.1 Visual approach procedures shall be shown where applicable.
- 12.10.5.2 Visual aids for navigation shall be shown as appropriate.
- 12.10.5.3 Location and type of the visual approach slope indicator systems with their nominal approach slope angle(s), minimum eye height(s) over the threshold of the on-slope signal(s), and where the axis of the system is not parallel to the runway centre line, the angle and direction of displacement, i.e. left or right, shall be shown.
- 12.10.6 Supplementary information
- 12.10.6.1 Radio navigation aids together with their frequencies and identifications shall be shown as appropriate.
- 12.10.6.2 Radio communication facilities with their frequencies shall be shown as appropriate.

Page 74 of 133 4th Edition Rev: 00 Date: 28th October 2024

13. CHAPTER 13 - AERODROME/HELIPORT CHART — ICAO

13.1 Function

Aerodrome/Heliport chart – ICAO shall provide flight crews with information which will facilitate the ground movement of aircraft:

- a) from the aircraft stand to the runway; and
- b) from the runway to the aircraft stand;

and helicopter movement:

- a) from the helicopter stand to the touchdown and lift-off area and to the final approach and take-off area;
- b) from the final approach and take-off area to the touchdown and lift-off area and to the helicopter stand;
- c) along helicopter ground and air taxiways; and
- d) along air transit routes;

it shall also provide essential operational information at the aerodrome/heliport.

13.2 Availability

- 13.2.1 The Aerodrome/Heliport Chart ICAO shall be made available in the manner prescribed in 1.3.2 for all aerodromes/heliports regularly used by international civil aviation.
- 13.2.2 The Aerodrome/Heliport Chart ICAO should be made available also, in the manner prescribed in 1.3.2, for all other aerodromes/heliports available for use by international civil aviation.

Under certain conditions, an Aerodrome Ground Movement Chart — ICAO and an Aircraft Parking/Docking Chart — ICAO may have to be provided (see Chapters 14 and 15); in which case, the elements portrayed on these supplementary charts need not be duplicated on the Aerodrome/Heliport Chart — ICAO.

13.3 Coverage and scale

- 13.3.1 The coverage and scale shall be sufficiently large to show clearly all the elements listed in 13.6.1.
- 13.3.2 A linear scale shall be shown.

Page 75 of 133 4th Edition Rev: 00 Date: 28th October 2024

13.4 Identification

The chart shall be identified by the name of the city or town or area which the aerodrome/heliport serves and the name of the aerodrome/heliport.

13.5 Magnetic variation

True and Magnetic North arrows and magnetic variation to the nearest degree and annual change of the magnetic variation shall be shown.

13.6 Aerodrome/heliport data

- 13.6.1 Aerodrome/Heliport chart ICAO shall show:
 - a) geographical coordinates in degrees, minutes and seconds for the aerodrome/heliport reference point;
 - b) elevations, to the nearest metre or foot, of the aerodrome/heliport and apron (altimeter checkpoint locations) where applicable; and for non-precision approaches, elevations and geoid undulations of runway thresholds and the geometric centre of the touchdown and lift-off area;
 - c) elevations and geoid undulations, to the nearest half-metre or foot, of the precision approach runway threshold, the geometric centre of the touchdown and lift-off area, and at the highest elevation of the touchdown zone of a precision approach runway;
 - d) all runways including those under construction with designation number, length and width to the nearest metre, bearing strength, displaced thresholds, stop ways, clearways, runway directions to the nearest degree magnetic, type of surface and runway markings;

Bearing strengths may be shown in tabular form on the face or verso of the chart.

e) all aprons, with aircraft/helicopter stands, lighting, markings and other visual guidance and control aids, where applicable, including location and type of visual docking guidance systems, type of surface for heliports, and bearing strengths or aircraft type restrictions where the bearing strength is less than that of the associated runways;

Bearing strengths or aircraft type restrictions may be shown in tabular form on the face or verso of the chart.

- f) geographical coordinates in degrees, minutes and seconds for thresholds, geometric centre of touchdown and lift-off area and/or thresholds of the final approach and take-off area (where appropriate);
- g) all taxiways, helicopter air and ground taxiways with type of surface, helicopter air transit routes, with designations, width, lighting, markings (including runway-holding positions and,

Page 76 of 133 4th Edition Rev: 00 Date: 28th October 2024

where established, intermediate holding positions), stop bars, other visual guidance and control aids, and bearing strength or aircraft type restrictions where the bearing strength is less than that of the associated runways;

Bearing strengths or aircraft type restrictions may be shown in tabular form on the face or verso of the chart.

- h) where established, hot spot locations with additional information properly annotated; Additional information regarding hot spots may be shown in tabular form on the face or verso of the chart.
- i) geographical coordinates in degrees, minutes, seconds and hundredths of seconds for appropriate taxiway centre line points and aircraft stands;
- j) where established, standard routes for taxiing aircraft with their designators;
- k) the boundaries of the air traffic control service;
- 1) position of runway visual range (RVR) observation sites;
- m) approach and runway lighting;
- n) location and type of the visual approach slope indicator systems with their nominal approach slope angle(s), minimum eye height(s) over the threshold of the on-slope signal(s), and where the axis of the system is not parallel to the runway centre line, the angle and direction of the displacement, i.e. left or right;
- o) relevant communication facilities listed with their channels and, if applicable, logon address and SATVOICE number;
- p) obstacles to taxiing;
- q) aircraft servicing areas and buildings of operational significance;
- r) VOR checkpoint and radio frequency of the aid concerned;
- s) any part of the depicted movement area permanently unsuitable for aircraft, clearly identified as such.
- 13.6.2 For aerodromes accommodating aeroplanes with folding wing tips, areas where it is safe for aeroplanes with folding wing tips to operate with wing tips extended, should be shown on the chart.
- 13.6.3 In addition to the items in 13.6.1 relating to heliports, the chart shall show:

Page 77 of 133 4th Edition Rev: 00 Date: 28th October 2024

a) heliport type;

Heliport types are identified in Annex 14, Volume II, as surface-level, elevated or helideck.

- b) touchdown and lift-off area including dimensions to the nearest metre, slope, type of surface and bearing strength in tonnes;
- c) final approach and take-off area including type, true bearing to the nearest degree, designation number (where appropriate), length and width to the nearest metre, slope and type of surface;
- d) safety area including length, width and type of surface;
- e) helicopter clearway including length and ground profile;
- f) obstacles including type and elevation of the top of the obstacles to the nearest (next higher) metre or foot;
- g) visual aids for approach procedures, marking and lighting of final approach and take-off area, and of touchdown and lift-off area;
- h) declared distances to the nearest metre for heliports, where relevant, including:
- 1) take-off distance available;
- 2) rejected take-off distance available;
- 3) landing distance available.

Page 78 of 133 4th Edition Rev: 00 Date: 28th October 2024

14. CHAPTER 14 - AERODROME GROUND MOVEMENT CHART — ICAO

14.1 Function

Aerodrome Ground Movement Chart — ICAO is a supplementary chart which shall provide flight crews with detailed information to facilitate the ground movement of aircraft to and from the aircraft stands and the parking/docking of aircraft.

14.2 Availability

The Aerodrome Ground Movement Chart — ICAO should be made available in the manner prescribed in 1.3.2 where, due to congestion of information, details necessary for the ground movement of aircraft along the taxiways to and from the aircraft stands cannot be shown with sufficient clarity on the Aerodrome/Heliport Chart — ICAO.

14.3 Coverage and scale

- 14.3.1 The coverage and scale shall be sufficiently large to show clearly all the elements listed in 14.6.
- 14.3.2 A linear scale should be shown.

14.4 Identification

The chart shall be identified by the name of the city or town or area which the aerodrome serves and the name of the aerodrome.

14.5 Magnetic variation

- 14.5.1 A True North arrow shall be shown.
- 14.5.2 Magnetic variation to the nearest degree and its annual change should be shown.

Aerodrome Ground Movement Chart — ICAO need not be True North orientated.

14.6 Aerodrome data

Aerodrome Ground Movement Chart — ICAO shall show in a similar manner all the information on the Aerodrome/Heliport Chart — ICAO relevant to the area depicted, including:

- a) apron elevation to the nearest metre or foot;
- b) aprons with aircraft stands, bearing strengths or aircraft type restrictions, lighting, marking and other visual guidance and control aids, where applicable, including location and type of visual docking guidance systems;

Compliance to Annex 04 – Aeronautical Charts
Attachment No. IS-04-Att.

- c) geographical coordinates in degrees, minutes, seconds and hundredths of seconds for aircraft stands;
- d) taxiways with designations, width to the nearest metre, bearing strength or aircraft type restrictions where applicable, lighting, markings (including runway-holding positions and, where established, intermediate holding positions), stop bars, and other visual guidance and control aids;
- e) where established, hot spot locations with additional information properly annotated;

Additional information regarding hot spots may be shown in tabular form on the face or verso of the chart.

- f) where established, standard routes for taxiing aircraft, with their designators;
- g) geographical coordinates in degrees, minutes, seconds and hundredths of seconds for appropriate taxiway centre line points;
- h) the boundaries of the air traffic control service;
- i) relevant communication facilities listed with their channels and, if applicable, logon address;
- j) obstacles to taxiing;
- k) aircraft servicing areas and buildings of operational significance;
- 1) VOR checkpoint and radio frequency of the aid concerned;
- m) any part of the depicted movement area permanently unsuitable for aircraft, clearly identified as such.
- 14.6.2 For aerodromes accommodating aeroplanes with folding wing tips, areas where it is safe for aeroplanes with folding wing tips to operate with wing tips extended, should be shown on the chart.

Page 80 of 133 4th Edition Rev: 00 Date: 28th October 2024

15. CHAPTER 15 - AIRCRAFT PARKING/DOCKING CHART — ICAO

15.1 Function

Aircraft Parking/Docking Chart — ICAO is a supplementary chart which shall provide flight crews with detailed information to facilitate the ground movement of aircraft between the taxiways and the aircraft stands and the parking/docking of aircraft.

15.2 Availability

The Aircraft Parking/Docking Chart — ICAO should be made available in the manner prescribed in 1.3.2 where, due to the complexity of the terminal facilities, the information cannot be shown with sufficient clarity on the Aerodrome/Heliport Chart — ICAO or on the Aerodrome Ground Movement Chart — ICAO.

15.3 Coverage and scale

- 15.3.1 The coverage and scale shall be sufficiently large to show clearly all the elements listed in 15.6.
- 15.3.2 A linear scale should be shown.

15.4 Identification

The chart shall be identified by the name of the city or town or area which the aerodrome serves and the name of the aerodrome.

15.5 Magnetic variation

- 15.5.1 A True North arrow shall be shown.
- 15.5.2 Magnetic variation to the nearest degree and its annual change should be shown.

Aircraft Parking/Docking Chart — ICAO need not be True North orientated.

15.6 Aerodrome data

Aircraft Parking/Docking Chart — ICAO shall show in a similar manner all the information on the Aerodrome/Heliport Chart — ICAO and the Aerodrome Ground Movement Chart — ICAO relevant to the area depicted, including:

a) apron elevation to the nearest metre or foot;

Compliance to Annex 04 – Aeronautical Charts Attachment No. IS-04-Att.

- b) aprons with aircraft stands, bearing strengths or aircraft type restrictions, lighting, marking and other visual guidance and control aids, where applicable, including location and type of visual docking guidance systems;
- c) geographical coordinates in degrees, minutes, seconds and hundredths of seconds for aircraft stands;
- d) taxiway entries with designations, including runway-holding positions and, where established, intermediate holding positions, and stop bars;
- e) where established, hot spot locations with additional information properly annotated;

Additional information regarding hot spots may be shown in tabular form on the face or verso of the chart.

- f) geographical coordinates in degrees, minutes, seconds and hundredths of seconds for appropriate taxiway centre line points;
- g) the boundaries of the air traffic control service;
- h) relevant communication facilities listed with their channels and, if applicable, logon address;
- i) obstacles to taxiing;
- j) aircraft servicing areas and buildings of operational significance;
- k) VOR checkpoint and radio frequency of the aid concerned;
- l) any part of the depicted movement area permanently unsuitable for aircraft, clearly identified as such.

Page 82 of 133 4th Edition Rev: 00 Date: 28th October 2024

16. CHAPTER 16 - WORLD AERONAUTICAL CHART — ICAO 1:1 000 000

16.1 Function

World Aeronautical Chart — ICAO 1:1 000 000 shall provide information to satisfy the requirements of visual air navigation.

World Aeronautical Chart — ICAO 1:1 000 000 may also serve:

- a) as a basic aeronautical chart:
- 1) when highly specialized charts lacking visual information do not provide essential data;
- 2) to provide complete world coverage at a constant scale with a uniform presentation of plan metric data:
- 3) in the production of other charts required by international civil aviation;
- b) as a pre-flight planning chart.

16.2 Availability

16.2.1 The World Aeronautical Chart — ICAO 1:1 000 000 shall be made available in the manner prescribed in 1.3.2 for all areas delineated in Appendix 5.

When operational or chart production considerations indicate that operational requirements can be effectively satisfied by Aeronautical Charts — ICAO 1:500 000 or Aeronautical Navigation Charts — ICAO Small Scale, either of these charts may be made available instead of the basic 1:1 000 000 chart.

16.2.2 To ensure complete coverage of all land areas and adequate continuity in any one coordinated series, the selection of a scale of other than 1:1 000 000 should be determined by regional agreement.

16.3 Scales

- 16.3.1 Linear scales for kilometres and nautical miles arranged in the following order:
 - kilometres,
 - nautical miles,

with their zero points in the same vertical line shall be shown in the margin.

- 16.3.1.1 The length of the linear scales should represent at least 200 km (110 NM).
- 16.3.2 A conversion scale (metres/feet) shall be shown in the margin.

16.4 Format

Page 83 of 133 4th Edition Rev: 00 Date: 28th October 2024

- 16.4.1 The title and marginal notes shall be in English Language.
- 16.4.2 The information regarding the number of the adjoining sheets and the unit of measurement to express elevations shall be so located as to be clearly visible when the sheet is folded.
- 16.4.3 The method of folding should be as follows:

Fold the chart on the long axis near the mid-parallel of latitude, face out, with the bottom part of the chart face upward. Fold inward near the meridian, and fold both halves backward in accordion folds.

16.4.4 Whenever practicable, the sheet lines should conform with those shown in the index in Appendix 5.

The area covered by a sheet may vary from the lines shown to satisfy particular requirements.

The value of adopting identical sheet lines for ICAO 1:1 000 000 Charts and the corresponding sheet of the International Map of the World (IMW), provided aeronautical requirements are not compromised, is recognized.

16.4.5 Overlaps should be provided by extending the chart area on the top and right side beyond the area given on the index. This overlap area should contain all aeronautical, topographical, hydrographical and cultural information. The overlap should extend up to 28 km (15 NM), if possible, but in any case from the limiting parallels and meridians of each chart to the neat line.

16.5 Projection

- 16.5.1 The projections shall be as follows:
 - a) between the Equator and 80° latitude: the Lambert conformal conic projection, in separate bands for each tier of charts. The standard parallels for each 4° band shall be 40' south of the northern parallel and 40' north of the southern parallel;
 - b) between 80° and 90° latitude: the Polar stereographic projection with scale matching that of the Lambert conformal conic projection at latitude 80°, except that in the northern hemisphere the Lambert conformal conic projection may be used between 80° and 84° latitude and the Polar stereographic projection between 84° and 90° with the scales matching at 84° North.
- 16.5.2 Graticules and graduations shall be shown as follows:

Page 84 of 133 4th Edition Rev: 00 Date: 28th October 2024

a) Parallels:

Latitude	Distance between parallels	Graduations on parallels
0° to 72°	30'	1'
72° to 84°	30'	5'
84° to 89°	30'	1°
89° to 90°	30'	5°
		(Only on degree parallels from 72° to 89°)

b) Meridians:

Latitude	Interval between meridians	Graduations on meridians
0° to 52°	30'	1'
52° to 72°	30'	1'
		(Only on even
		numbered meridians)
72° to 84°	1°	1'
84° to 89°	5°	1'
89° to 90°	15°	1'
		(Only on every
		fourth meridian)

- 16.5.3 The graduation marks at 1 and 5 intervals shall extend away from the Greenwich Meridian and from the Equator. Each 10 interval shall be shown by a mark on both sides of the graticule line.
- 16.5.3.1 The length of the graduation marks should be approximately 1.3 mm (0.05 in) for the 1 intervals, and 2 mm (0.08 in) for the 5 intervals and 2 mm (0.08 in) extending on both sides of the graticule line for the 10 intervals.
- 16.5.4 All meridians and parallels shown shall be numbered in the borders of the chart. In addition, each parallel shall be numbered within the body of the chart in such a manner that the parallel can be readily identified when the chart is folded.

Meridians may be numbered within the body of the chart.

16.5.5 The name and basic parameters of the projection shall be indicated in the margin.

16.6 Identification

Sheet numbering shall be in conformity with the index in Appendix 5.

The corresponding International Map of the World (IMW) sheet number may also be shown.

16.7 Culture and topography

16.7.1 Built-up areas

Page 85 of 133 4th Edition Rev: 00 Date: 28th October 2024

- 16.7.1.1 Cities, towns and villages shall be selected and shown according to their relative importance to visual air navigation.
- 16.7.1.2 Cities and towns of sufficient size should be indicated by the outline of their built-up areas and not of their established city limits.

16.7.2 Railroads

16.7.2.1 All railroads having landmark value shall be shown.

In congested areas, some railroads may be omitted in the interest of legibility.

Railroads may be named where space permits.

16.7.2.2 Important tunnels should be shown.

A descriptive note may be added.

- 16.7.3 Highways and roads
- 16.7.3.1 Road systems shall be shown in sufficient detail to indicate significant patterns from the air.
- 16.7.3.2 Roads should not be shown in built-up areas unless they can be distinguished from the air as definite landmarks.

The numbers or names of important highways may be shown.

16.7.4 Landmarks

Natural and cultural landmarks, such as bridges, prominent transmission lines, permanent cable car installations, wind turbines, mine structures, forts, ruins, levees, pipelines, rocks, bluffs, cliffs, sand dunes, isolated lighthouses and lightships, when considered to be of importance for visual air navigation, should be shown.

Descriptive notes may be added.

16.7.5 Political boundaries

International boundaries shall be shown. Undemarcated and undefined boundaries shall be distinguished by descriptive notes.

16.7.6 Hydrography

- 16.7.6.1 All water features compatible with the scale of the chart comprising shore lines, lakes, rivers and streams (including those non-perennial in nature), salt lakes, glaciers and ice caps shall be shown.
- 16.7.6.2 The tint covering large open water areas should be kept very light.

 A narrow band of darker tone may be used along the shore line to emphasize this feature.
- 16.7.6.3 Reefs and shoals, including rocky ledges, tidal flats, isolated rocks, sand, gravel, stone and all similar areas, should be shown by symbols when of significant landmark value.

Groups of rocks may be shown by a few representative rock symbols within the area.

- 16.7.7 Contours
- 16.7.7.1 Contours shall be shown. The selection of intervals shall be governed by the requirement to depict clearly the relief features required in air navigation.
- 16.7.7.2 The values of the contours used shall be shown.
- 16.7.8 Hypsometric tints
- 16.7.8.1 When hypsometric tints are used, the range of elevations for the tints shall be shown.
- 16.7.8.2 The scale of the hypsometric tints used on the chart shall be shown in the margin.
- 16.7.9 Spot elevations
- 16.7.9.1 Spot elevations shall be shown at selected critical points. The elevations selected shall always be the highest in the immediate vicinity and shall generally indicate the top of a peak, ridge, etc. Elevations in valleys and at lake surface levels which are of special value to the aviator shall be shown. The position of each selected elevation shall be indicated by a dot.
- 16.7.9.2 The elevation (in metres or feet) of the highest point on the chart and its geographical position to the nearest five minutes shall be indicated in the margin.
- 16.7.9.3 The spot elevation of the highest point in any sheet should be cleared of hypsometric tinting.
- 16.7.10 Incomplete or unreliable relief
- 16.7.10.1 Areas that have not been surveyed for contour information shall be labelled "Relief data incomplete".
- 16.7.10.2 Charts on which spot elevations are generally unreliable shall bear a warning note prominently displayed on the face of the chart in the colour used for aeronautical information, as follows:

Page 87 of 133 4th Edition Rev: 00 Date: 28th October 2024

"Warning — The reliability of relief information on this chart is doubtful and elevations should be used with caution."

16.7.11 Escarpments

Escarpments should be shown when they are prominent landmarks or when cultural detail is very sparse.

16.7.12 Wooded areas

- 16.7.12.1 Wooded areas should be shown.
- 16.7.12.2 Where shown, the approximate extreme northern or southern limits of tree growth shall be indicated by a dashed black line and shall be appropriately labelled.

16.7.13 Date of topographic information

The date of the latest information shown on the topographic base shall be indicated in the margin.

16.8 Magnetic variation

- 16.8.1 Isogonic lines shall be shown.
- 16.8.2 The date of the isogonic information shall be indicated in the margin.

16.9 Aeronautical data

16.9.1 General

Aeronautical data shown shall be kept to a minimum consistent with the use of the chart for visual navigation and the revision cycle (see 16.9.6).

16.9.2 Aerodromes

- 16.9.2.1 Land and water aerodromes and heliports shall be shown with their names, to the extent that they do not produce undesirable congestion on the chart, priority being given to those of greatest aeronautical significance.
- 16.9.2.2 The aerodrome elevation, the lighting available, the type of runway surface and the length of the longest runway or channel, shown in abbreviated form for each aerodrome in conformity with the example given in Appendix 2, provided they do not cause undesirable clutter on the chart, shall be indicated.

Page 88 of 133 4th Edition Rev: 00 Date: 28th October 2024

16.9.2.3 Abandoned aerodromes which are still recognizable as aerodromes from the air shall be shown and identified as abandoned.

16.9.3 Obstacles

16.9.3.1 Obstacles shall be shown.

Objects of a height of 100 m (300 ft) or more above ground are normally regarded as obstacles.

- 16.9.3.2 When considered of importance to visual flight, prominent transmission lines, permanent cable car installations and wind turbines, which are obstacles, shall be shown.
- 16.9.4 Prohibited, restricted and danger areas

Prohibited, restricted and danger areas shall be shown.

- 16.9.5 Air traffic services system
- 16.9.5.1 Significant elements of the air traffic services system including, where practicable, control zones, aerodrome traffic zones, control areas, flight information regions and other airspaces in which VFR flights operate shall be shown together with the appropriate class of airspace.
- 16.9.5.2 Where appropriate, the air defence identification zone (ADIZ) shall be shown and properly identified.

ADIZ procedures may be described in the chart legend.

16.9.6 Radio navigation aids

Radio navigation aids shall be shown by the appropriate symbol and named, but excluding their frequencies, coded designators, times of operation and other characteristics unless any or all of this information which is shown is kept up to date by means of new editions of the chart.

- 16.9.7 Supplementary information
- 16.9.7.1 Aeronautical ground lights together with their characteristics or their identifications or both shall be shown.
- 16.9.7.2 Marine lights on outer prominent coastal or isolated features of not less than 28 km (15 NM) visibility range shall be shown:
 - a) where they are not less distinguishable than more powerful marine lights in the vicinity;
 - b) where they are readily distinguishable from other marine or other types of lights in the vicinity of built-up coastal areas;
 - c) where they are the only lights of significance available.

Page 89 of 133 4th Edition Rev: 00 Date: 28th October 2024

17. CHAPTER 17 - AERONAUTICAL CHART — ICAO 1:500 000

17.1 Function

Aeronautical Chart — ICAO 1:500 000 shall provide information to satisfy the requirements of visual air navigation for low speed, short- or medium-range operations at low and intermediate altitudes.

Aeronautical Chart — ICAO 1:500 000 may be used:

- a) to serve as a basic aeronautical chart;
- b) to provide a suitable medium for basic pilot and navigation training;
- c) to supplement highly specialized charts which do not provide essential visual information;
- d) in pre-flight planning.

It is intended that these charts be provided for land areas where charts of this scale are required for civil air operations employing visual air navigation independently or in support of other forms of air navigation.

17.2 Availability

The Aeronautical Chart — ICAO 1:500 000 should be made available in the manner prescribed in 1.3.2 for all areas delineated in Appendix 5.

The selection of this scale as an alternative to the World Aeronautical Chart — ICAO 1:1 000 000 is covered by 16.2.1 and 16.2.2.

17.3 Scales

- 17.3.1 Linear scales for kilometres and nautical miles arranged in the following order:
 - kilometres,
 - nautical miles, with their zero points in the same vertical line shall be shown in the margin.
- 17.3.1.1 The length of the linear scale should be not less than 200 mm (8 in).
- 17.3.2 A conversion scale (metres/feet) shall be shown in the margin.

17.4 Format

- 17.4.1 The title and marginal notes shall be in English Language.
- 17.4.2 The information regarding the number of the adjoining sheets and the unit of measurement used to express elevation shall be so located as to be clearly visible when the sheet is folded.

Page 90 of 133 4th Edition Rev: 00 Date: 28th October 2024

- 17.4.3 The method of folding should be as follows:

 Fold the chart on the long axis near the mid-parallel of latitude, face out, with the bottom part of the chart face upward. Fold inward near the meridian, and fold both halves backward in accordion folds.
- 17.4.4 Whenever practicable, sheets should be quarter sheets of the World Aeronautical Chart ICAO 1:1 000 000. An appropriate index to adjacent sheets, showing the relationship between the two chart series, should be included on the face of the chart or on the reverse side.
 - Sheet lines may be varied to satisfy particular requirements.
- 17.4.5 Overlaps should be provided by extending the chart area on the top and right side beyond the area given on the index. This overlap area should contain all aeronautical, topographical, hydrographical and cultural information. The overlap should extend up to 15 km (8 NM), if possible, but in any case from the limiting parallels and meridians of each chart to the neat line.

17.5 Projection

- 17.5.1 A conformal (orthomorphic) projection shall be used.
- 17.5.2 The projection of the World Aeronautical Chart ICAO 1:1 000 000 should be used.
- 17.5.3 Parallels shall be shown at intervals of 30.
- 17.5.3.1 Meridians shall normally be shown at intervals of 30.
- 17.5.4 Graduation marks shall be shown at 1 intervals along each whole degree meridian and parallel, extending away from the Greenwich Meridian and from the Equator. Each 10 interval shall be shown by a mark on both sides of the graticule line.
- 17.5.4.1 The length of the graduation marks should be approximately 1.3 mm (0.05 in) for the 1 intervals, and 2 mm (0.08 in) for the 5 intervals and 2 mm (0.08 in) extending on both sides of the graticule line for the 10 intervals.
- 17.5.5 All meridians and parallels shown shall be numbered in the borders of the chart.
- 17.5.5.1 Each meridian and parallel should be numbered within the body of the chart whenever this data is required operationally.
- 17.5.6 The name and basic parameters of the projection shall be indicated in the margin.

17.6 Identification

17.6.1 Each sheet shall be identified by a name which should be that of the principal town or of a main geographical feature appearing on the sheet.

Page 91 of 133 4th Edition Rev: 00 Date: 28th October 2024

17.6.1.1 Where applicable, sheets should also be identified by the reference number of the corresponding World Aeronautical Chart — ICAO 1:1 000 000, with the addition of one or more of the following letter suffixes indicating the quadrant or quadrants:

Letter	Chart quadrant
A	North-West
В	North-East
C	South-East
D	South-West

17.7 Culture and topography

- 17.7.1 Built-up areas
- 17.7.1.1 Cities, towns and villages shall be selected and shown according to their relative importance to visual air navigation.
- 17.7.1.2 Cities and towns of sufficient size should be indicated by the outline of their built-up areas and not of their established city limits.
- 17.7.2 Railroads
- 17.7.2.1 All railroads having landmark value shall be shown.

In congested areas, some railroads may be omitted in the interest of legibility.

Railroads may be named.

Rail stations may be shown.

17.7.2.2 Tunnels shall be shown when they serve as prominent landmarks.

A descriptive note may be added, if necessary, to accentuate this feature.

- 17.7.3 Highways and roads
- 17.7.3.1 Road systems shall be shown in sufficient detail to indicate significant patterns from he air. *Roads under construction may be shown*.
- 17.7.3.2 Roads should not be shown in built-up areas unless they can be distinguished from the air as definite landmarks.

The numbers or names of important highways may be shown.

17.7.4 Landmarks

Natural and cultural landmarks, such as bridges, prominent transmission lines, permanent cable car installations, wind turbines, mine structures, lookout towers, forts, ruins, levees, pipelines, rocks, bluffs, cliffs, sand dunes, isolated lighthouses and lightships, when considered to be of importance for visual air navigation, should be shown.

Descriptive notes may be added.

17.7.5 Political boundaries

International boundaries shall be shown. Undemarcated and undefined boundaries shall be distinguished by descriptive notes.

Other boundaries may be shown.

17.7.6 Hydrography

- 17.7.6.1 All water features compatible with the scale of the chart comprising shore lines, lakes, rivers and streams (including those non-perennial in nature), salt lakes, glaciers and ice caps shall be shown.
- 17.7.6.2 The tint covering large open water areas should be kept very light.

 A narrow band of darker tone may be used along the shore line to emphasize this feature.
- 17.7.6.3 Reefs and shoals, including rocky ledges, tidal flats, isolated rocks, sand, gravel, stone and all similar areas, should be shown by symbols when of significant landmark value.

Groups of rocks may be shown by a few representative rock symbols within the area.

17.7.7 Contours

- 17.7.7.1 Contours shall be shown. The selection of intervals shall be governed by the requirement to depict clearly the relief features required in air navigation.
- 17.7.7.2 The values of the contours used shall be shown.
- 17.7.8 Hypsometric tints
- 17.7.8.1 When hypsometric tints are used, the range of elevations for the tints shall be shown.
- 17.7.8.2 The scale of the hypsometric tints used on the chart shall be shown in the margin.
- 17.7.9 Spot elevations
- 17.7.9.1 Spot elevations shall be shown at selected critical points. The elevations selected shall always be the highest in the immediate vicinity and shall generally indicate the top of a peak, ridge, etc. Elevations in valleys and at lake surface levels which are of navigational value shall be shown. The position of each selected elevation shall be indicated by a dot.
- 17.7.9.2 The elevation (in metres or feet) of the highest point on the chart and its geographical position to the nearest five minutes shall be indicated in the margin.
- 17.7.9.3 The spot elevation of the highest point on any sheet should be cleared of hypsometric tinting.

Page 93 of 133 4th Edition Rev: 00 Date: 28th October 2024

- 17.7.10 Incomplete or unreliable relief
- 17.7.10.1 Areas that have not been surveyed for contour information shall be labelled "Relief data incomplete".
- 17.7.10.2 Charts on which spot elevations are generally unreliable shall bear a warning note prominently displayed on the face of the chart in the colour used for aeronautical information, as follows:

"Warning — The reliability of relief information on this chart is doubtful and elevations should be used with caution."

17.7.11 Escarpments

Escarpments should be shown when they are prominent landmarks or when cultural detail is very sparse.

- 17.7.12 Wooded areas
- 17.7.12.1 Wooded areas should be shown.
- 17.7.12.2 Where shown, the approximate northern or southern limits of tree growth shall be indicated by a dashed black line and shall be appropriately labelled.
- 17.7.13 Date of topographic information

The date of latest information shown on the topographic base shall be indicated in the margin.

17.8 Magnetic variation

- 17.8.1 Isogonic lines shall be shown.
- 17.8.2 The date of the isogonic information shall be indicated in the margin.

17.9 Aeronautical data

17.9.1 General

Aeronautical information shall be shown consistent with the use of the chart and the revision cycle.

17.9.2 Aerodromes

- 17.9.2.1 Land and water aerodromes and heliports shall be shown with their names, to the extent that they do not produce undesirable congestion on the chart, priority being given to those of greatest aeronautical significance.
- 17.9.2.2 The aerodrome elevation, the lighting available, the type of runway surface and the length of the longest runway or channel, shown in abbreviated form for each aerodrome in conformity with the example given in Appendix 2, provided they do not cause undesirable clutter on the chart, shall be indicated.
- 17.9.2.3 Abandoned aerodromes which are still recognizable as aerodromes from the air shall be shown and identified as abandoned.
- 17.9.3 Obstacles
- 17.9.3.1 Obstacles shall be shown.

Objects of a height of 100 m (300 ft) or more above ground are normally regarded as obstacles.

- 17.9.3.2 When considered of importance to visual flight, prominent transmission lines, permanent cable car installations and wind turbines, which are obstacles, shall be shown.
- 17.9.4 Prohibited, restricted and danger areas

Prohibited, restricted and danger areas shall be shown.

- 17.9.5 Air traffic services system
- 17.9.5.1 Significant elements of the air traffic services system including, where practicable, control zones, aerodrome traffic zones, control areas, flight information regions and other airspaces in which VFR flights operate shall be shown together with the appropriate class of airspace.
- 17.9.5.2 Where appropriate, the air defence identification zone (ADIZ) shall be shown and properly identified.

ADIZ procedures may be described in the chart legend.

17.9.6 Radio navigation aids

Radio navigation aids shall be shown by the appropriate symbol and named, but excluding their frequencies, coded designators, times of operation and other characteristics unless any or all of this information which is shown is kept up to date by means of new editions of the chart.

- 17.9.7 Supplementary information
- 17.9.7.1 Aeronautical ground lights together with their characteristics or their identifications or both shall be shown.

Page 95 of 133 4th Edition Rev: 00 Date: 28th October 2024

Compliance to Annex 04 – Aeronautical Charts Attachment No. IS-04-Att.

- 17.9.7.2 Marine lights on outer prominent coastal or isolated features of not less than 28 km (15 NM) visibility range shall be shown:
 - a) where they are not less distinguishable than more powerful marine lights in the vicinity;
 - b) where they are readily distinguishable from other marine or other types of lights in the vicinity of built-up coastal areas;
 - c) where they are the only lights of significance available.

Page 96 of 133 4th Edition Rev: 00 Date: 28th October 2024

18. CHAPTER 18 - AERONAUTICAL NAVIGATION CHART — ICAO SMALL SCALE

18.1 Function

Aeronautical Navigation Chart — ICAO Small Scale shall:

- a) serve as an air navigation aid for flight crews of long-range aircraft at high altitudes;
- b) provide selective checkpoints over extensive ranges for identification at high altitudes and speeds, which are required for visual confirmation of position;
- c) provide for continuous visual reference to the ground during long-range flights over areas lacking radio or other electronic navigation aids, or over areas where visual navigation is preferred or becomes necessary;
- d) provide a general purpose chart series for long-range flight planning and plotting.

18.2 Availability

The Aeronautical Navigation Chart — ICAO Small Scale should be made available in the manner prescribed in 1.3.2 for all areas delineated in Appendix 5.

The selection of this scale as an alternative to the World Aeronautical Chart — ICAO 1:1 000 000 is covered by 16.2.1 and 16.2.2.

18.3 Coverage and scale

18.3.1 The Aeronautical Navigation Chart — ICAO Small Scale should provide, as a minimum, complete coverage of the major land masses of the world.

A sheet layout for this series is contained in the Aeronautical Chart Manual (Doc 8697).

The sheet size may represent the maximum press size available to the producing agency.

- 18.3.2 The scale shall be in the range of 1:2 000 000 to 1:5 000 000.
- 18.3.3 The scale of the chart shall be substituted in the title for the words "Small Scale".
- 18.3.4 Linear scales for kilometres and nautical miles arranged in the following order:
 - kilometres,
 - nautical miles,

with their zero points in the same vertical line shall be shown in the margin.

18.3.5 The length of the linear scale should be not less than 200 mm (8 in).

Page 97 of 133 4th Edition Rev: 00 Date: 28th October 2024

18.3.6 A conversion scale (metres/feet) shall be shown in the margin.

18.4 Format

- 18.4.1 The title and marginal notes shall be in English Language.
- 18.4.2 The information regarding the number of the adjoining sheets and the unit of measurement to express elevations shall be so located as to be clearly visible when the sheet is folded.

There is no internationally agreed sheet numbering.

18.5 Projection

- 18.5.1 A conformal (orthomorphic) projection shall be used.
- 18.5.1.1 The name and basic parameters of the projection shall be shown in the margin.
- 18.5.2 Parallels shall be shown at intervals of 1°.
- 18.5.2.1 Graduations on the parallels shall be shown at sufficiently close intervals compatible with the latitude and the scale of the chart.
- 18.5.3 Meridians shall be shown at intervals compatible with the latitude and the scale of the chart.
- 18.5.3.1 Graduations on the meridians shall be shown at intervals not exceeding 5.
- 18.5.4 The graduation marks shall extend away from the Greenwich Meridian and from the Equator.
- 18.5.5 All meridians and parallels shown shall be numbered in the borders of the chart. In addition, when required, meridians and parallels shall be numbered within the body of the chart in such a manner that they can be readily identified when the chart is folded.

18.6 Culture and topography

- 18.6.1 Built-up areas
- 18.6.1.1 Cities, towns and villages shall be selected and shown according to their relative importance to visual air navigation.
- 18.6.1.2 Cities and towns of sufficient size should be indicated by the outline of their built-up areas and not of their established city limits.
- 18.6.2 Railroads
- 18.6.2.1 All railroads having landmark value shall be shown.

Page 98 of 133 4th Edition Rev: 00 Date: 28th October 2024

In congested areas, some railroads may be omitted in the interest of legibility.

18.6.2.2 Important tunnels should be shown.

A descriptive note may be added.

- 18.6.3 Highways and roads
- 18.6.3.1 Road systems shall be shown in sufficient detail to indicate significant patterns from the air.
- 18.6.3.2 Roads should not be shown in built-up areas unless they can be distinguished from the air as definite landmarks.

18.6.4 Landmarks

Natural and cultural landmarks, such as bridges, prominent transmission lines, permanent cable car installations, mine structures, forts, ruins, levees, pipelines, rocks, bluffs, cliffs, sand dunes, isolated lighthouses and lightships, when considered to be of importance for visual air navigation, should be shown.

Descriptive notes may be added.

18.6.5 Political boundaries

International boundaries shall be shown. Undemarcated and undefined boundaries shall be distinguished by descriptive notes.

- 18.6.6 Hydrography
- 18.6.6.1 All water features compatible with the scale of the chart comprising shore lines, lakes, rivers and streams (including those non-perennial in nature), salt lakes, glaciers and ice caps shall be shown.
- 18.6.6.2 The tint covering large open water areas should be kept very light.

A narrow band of darker tone may be used along the shore line to emphasize this feature.

- 18.6.6.3 Reefs and shoals, including rocky ledges, tidal flats, isolated rocks, sand, gravel, stone and all similar areas, should be shown by symbols when of significant landmark value.
- 18.6.7 Contours
- 18.6.7.1 Contours shall be shown. The selection of intervals shall be governed by the requirement to depict clearly the relief features required in air navigation.

Page 99 of 133 4th Edition Rev: 00 Date: 28th October 2024

- 18.6.7.2 The values of the contours used shall be shown.
- 18.6.8 Hypsometric tints
- 18.6.8.1 When hypsometric tints are used, the range of elevations for the tints shall be shown.
- 18.6.8.2 The scale of the hypsometric tints used on the chart shall be shown in the margin.
- 18.6.9 Spot elevations
- 18.6.9.1 Spot elevations shall be shown at selected critical points. The elevations selected shall always be the highest in the immediate vicinity and shall generally indicate the top of a peak, ridge, etc. Elevations in valleys and at lake surface levels which are of value to visual air navigation shall be shown. The position of each selected elevation shall be indicated by a dot.
- 18.6.9.2 The elevation (in metres or feet) of the highest point on the chart and its geographical position to the nearest five minutes shall be indicated in the margin.
- 18.6.9.3 The spot elevation of the highest point in any sheet should be cleared of hypsometric tinting.
- 18.6.10 Incomplete or unreliable relief
- 18.6.10.1 Areas that have not been surveyed for contour information shall be labelled "Relief data incomplete".
- 18.6.10.2 Charts on which spot elevations are generally unreliable shall bear a warning note prominently displayed on the face of the chart in the colour used for aeronautical information, as follows:
 - "Warning The reliability of relief information on this chart is doubtful and elevations should be used with caution."

18.6.11 Escarpments

Escarpments should be shown when they are prominent landmarks or when cultural detail is very sparse.

18.6.12 Wooded areas

Wooded areas of large extent should be shown.

18.6.13 Date of topographic information

The date of latest information shown on the topographic base shall be indicated in the margin.

18.6.14 Colours

18.6.14.1 Subdued colours should be used for the chart background to facilitate plotting.

Page 100 of 133 4th Edition Rev: 00 Date: 28th October 2024

18.6.14.2 Good colour contrast should be ensured to emphasize features important to visual air navigation.

18.7 Magnetic variation

- 18.7.1 Isogonic lines shall be shown.
- 18.7.2 The date of isogonic information shall be indicated in the margin.

18.8 Aeronautical data

18.8.1 Aerodromes

Land and water aerodromes and heliports shall be shown with their names, to the extent that they do not produce undesirable congestion on the chart, priority being given to those of greatest aeronautical significance.

18.8.2 Obstacles

Obstacles shall be shown.

18.8.3 Prohibited, restricted and danger areas

Prohibited, restricted and danger areas should be shown when considered to be of importance to air navigation.

- 18.8.4 Air traffic services system
- 18.8.4.1 Significant elements of the air traffic services system should be shown when considered to be of importance to air navigation.
- 18.8.4.2 Where appropriate, the air defence identification zone (ADIZ) should be shown and properly identified.

ADIZ procedures may be described in the chart legend.

18.8.5 Radio navigation aids

Radio aids to navigation may be shown by the appropriate symbol and named.

Page 101 of 133 4th Edition Rev: 00 Date: 28th October 2024

19. CHAPTER 19 - PLOTTING CHART — ICAO

19.1 Function

Plotting Chart — ICAO shall provide a means of maintaining a continuous flight record of the aircraft position by various fixing methods and dead reckoning in order to maintain an intended flight path.

19.2 Availability

Plotting Chart — ICAO should be made available, in the manner prescribed in 1.3.2, to cover major air routes over oceanic areas and sparsely settled areas used by international civil aviation.

In areas where the Enroute Chart — ICAO is provided, there may be no requirement for a plotting chart.

19.3 Coverage and scale

- 19.3.1 Where practicable, the chart for a particular region should cover major air routes and their terminals on a single sheet.
- 19.3.2 The scale should be governed by the area to be covered.

The scale will range from 1:3 000 000 to 1:7 500 000.

19.4 Format

The sheet should be of a size that can be adapted for use on a navigator's plotting table.

19.5 Projection

- 19.5.1 A conformal projection on which a straight line approximates a great circle should be used.
- 19.5.2 Parallels and meridians shall be shown.
- 19.5.2.1 The intervals should be arranged to permit accurate plotting to be carried out with a minimum of time and effort.
- 19.5.2.2 Graduation marks shall be shown at consistent intervals along an appropriate number of parallels and meridians. The interval selected shall, regardless of scale, minimize the amount of interpolation required for accurate plotting.
- 19.5.2.3 Parallels and meridians should be numbered so that a number appears at least once every 15 cm (6 in) on the face of the chart.
- 19.5.2.4 If a navigational grid is shown on charts covering the higher latitudes, it shall comprise lines parallel to the Meridian or anti-Meridian of Greenwich.

Page 102 of 133 4th Edition Rev: 00 Date: 28th October 2024

19.6 Identification

Each sheet shall be identified by chart series and number.

19.7 Culture and topography

- 19.7.1 Generalized shore lines of all open water areas, large lakes and rivers shall be shown.
- 19.7.2 Spot elevations for selected features constituting a hazard to air navigation shall be shown.
- 19.7.3 Particularly hazardous or prominent relief features should be emphasized.

Large cities and towns may be shown.

19.8 Magnetic variation

- 19.8.1 Isogonals or, in higher latitudes, isogrivs, or both, shall be shown at consistent intervals throughout the chart. The interval selected shall, regardless of scale, minimize the amount of interpolation required.
- 19.8.2 The date of the isogonic information shall be shown.

19.9 Aeronautical data

- 19.9.1 The following aeronautical data shall be shown:
 - a) aerodromes regularly used by international commercial air transport together with their names;
 - b) selected radio aids to navigation that will contribute to position-finding together with their names and identifications;
 - c) lattices of long-range electronic aids to navigation, as required;
 - d) boundaries of flight information regions, control areas and control zones necessary to the function of the chart:
 - e) designated reporting points necessary to the function of the chart;
 - f) ocean station vessels.

Other aeronautical data may be shown provided that they do not detract from the legibility of essential information.

19.9.2 Aeronautical ground lights and marine lights useful for air navigation should be shown where other means of navigation are non-existent.

Page 103 of 133 4th Edition Rev: 00 Date: 28th October 2024

20. CHAPTER 20 - ELECTRONIC AERONAUTICAL CHART DISPLAY — ICAO

20.1 Function

The Electronic Aeronautical Chart Display — ICAO, with adequate back-up arrangements and in compliance with the requirements of Annex 6 for charts, shall enable flight crews to execute, in a convenient and timely manner, route planning, route monitoring and navigation by displaying the required information.

20.2 Information available for display

- 20.2.1 The Electronic Aeronautical Chart Display ICAO shall be capable of displaying all aeronautical, cultural and topographic information required by Chapter 5 and Chapters 7 through 19.
- 20.2.2 The Electronic Aeronautical Chart Display ICAO should be capable of displaying all aeronautical, cultural and topographic information as per the Chapter 5 and Chapters 7 through 19.

The Electronic Aeronautical Chart Display — ICAO may display supplementary information, in addition to that required for the equivalent paper chart, which may be considered useful for safe navigation.

20.3 Display requirements

- 20.3.1 Display categories
- 20.3.1.1 Information available for display shall be subdivided into the following categories:
 - a) basic display information, permanently retained on the display and consisting of the minimum information essential for the safe conduct of flight; and
 - b) other display information, which may be removed from the display or displayed individually on demand, and consisting of information not considered essential for the safe conduct of flight.
- 20.3.1.2 It shall be a simple function to add or remove other display information but shall not be possible to remove information contained in the basic display.
- 20.3.2 Display mode and generation of neighbouring area
- 20.3.2.1 The Electronic Aeronautical Chart Display ICAO shall be capable of continuously plotting the aircraft's position in a true motion mode where reset and generation of the surrounding area shall take place automatically.

Other modes, such as static chart displays, may be available.

Page 104 of 133 4th Edition Rev: 00 Date: 28th October 2024

20.3.2.2 It shall be possible manually to change the chart area and the position of the aircraft relative to the edge of the display.

20.3.3 Scale

It shall be possible to vary the scale at which a chart is displayed.

20.3.4 Symbols

Symbols used shall conform to those specified for electronic charts in Appendix 2 — ICAO Chart Symbols except where it is desired to show items for which no ICAO chart symbol is provided. In these cases, electronic chart symbols shall be chosen which:

- a) employ a minimum use of lines, arcs and area fills;
- b) do not cause confusion with any existing aeronautical chart symbol;
- c) do not impair the legibility of the display.

Additional details for each symbol may be added according to the resolution of the output media, but any enhancements may not change the basic recognizability of the symbol.

20.3.5 Display hardware

- 20.3.5.1 The effective size of the chart presentation shall be sufficient to display the information required by 20.2 without excessive scrolling.
- 20.3.5.2 The display shall have the capabilities required to accurately portray required elements of Appendix 2 ICAO Chart Symbols.
- 20.3.5.3 The method of presentation shall ensure that the displayed information is clearly visible to the observer in the conditions of natural and artificial light experienced in the cockpit.
- 20.3.5.4 The display luminance shall be adjustable by the flight crew.

20.4 Provision and updating of data

20.4.1 The provision and updating of data for use by the display shall be in conformance with the aeronautical data quality system requirements.

For aeronautical data quality system requirements, see Chapter 2, 2.17, and Implementing Standard no 28, Chapter 3, 3.2.

20.4.2 The display shall be capable of automatically accepting authorized updates to existing data. A means of ensuring that authorized data and all relevant updates to that data have been correctly loaded into the display shall be provided.

Page 105 of 133 4th Edition Rev: 00 Date: 28th October 2024

- 20.4.3 The display shall be capable of accepting updates to authorized data entered manually with simple means for verification prior to final acceptance of the data. Updates entered manually shall be distinguishable on the display from authorized data and its authorized updates and shall not affect display legibility.
- 20.4.4 A record shall be kept of all updates, including date and time of application.
- 20.4.5 The display shall allow the flight crew to display updates so that the flight crew may review the contents of the updates and determine that they have been included in the system.

20.5 Performance tests, malfunction alarms and indications

- 20.5.1 A means shall be provided for carrying out on-board tests of major functions. In case of a failure, the test shall display information to indicate which part of the system is at fault.
- 20.5.2 A suitable alarm or indication of system malfunction shall be provided.

20.6 Back-up arrangements

To ensure safe navigation in case of a failure of the Electronic Aeronautical Chart Display — ICAO, the provision of adequate back-up arrangements shall include:

- a) facilities enabling a safe takeover of display functions in order to ensure that a failure does not result in a critical situation; and
- b) a back-up arrangement facilitating the means for safe navigation of the remaining part of the flight.

A suitable back-up system may include the carriage of paper charts.

Page 106 of 133 4th Edition Rev: 00 Date: 28th October 2024

21. CHAPTER 21 - ATC SURVEILLANCE MINIMUM ALTITUDE CHART — ICAO

21.1 Function

21.1.1 ATC Surveillance Minimum Altitude Chart — ICAO is a supplementary chart which shall provide information that will enable flight crews to monitor and cross-check altitudes assigned by a controller using an ATS surveillance system.

The objectives of the air traffic control service as prescribed in Implementing Standard no 28 do not include prevention of collision with terrain. The procedures prescribed in the Procedures for Air Navigation Services — Air Traffic Management (PANS-ATM, Doc 4444) do not relieve pilots of their responsibility to ensure that any clearances issued by air traffic control units are safe in this respect. When an IFR flight is vectored or is given a direct routing which takes the aircraft off an ATS route, the PANS-ATM, Chapter 8, 8.6.5.2, applies.

21.1.2 A note indicating that the chart may only be used for cross-checking of altitudes assigned while the aircraft is identified shall be prominently displayed on the face of the chart.

21.2 Availability

The ATC Surveillance Minimum Altitude Chart — ICAO should be made available, in the manner prescribed in 1.3.2, where vectoring procedures are established and minimum vectoring altitudes cannot be shown adequately on the Area Chart — ICAO, Standard Departure Chart — Instrument (SID) — ICAO or Standard Arrival Chart — Instrument (STAR) — ICAO.

21.3 Coverage and scale

- 21.3.1 The coverage of the chart shall be sufficient to effectively show the information associated with vectoring procedures.
- 21.3.2 The chart shall be drawn to scale.
- 21.3.3 The chart should be drawn to the same scale as the associated Area Chart ICAO.

21.4 Projection

- 21.4.1 A conformal projection on which a straight line approximates a geodesic line should be used.
- 21.4.2 Graduation marks should be placed at consistent intervals along the neat lines, as appropriate.

21.5 Identification

The chart shall be identified by the name of the aerodrome for which the vectoring procedures are established or, when procedures apply to more than one aerodrome, the name associated with the airspace portrayed.

The name may be that of the city which the aerodrome serves or, when the procedures apply to more than one aerodrome that of the air traffic services centre or the largest city or town situated in the area covered by the chart.

21.6 Culture and topography

- 21.6.1 Generalized shorelines of all open water areas, large lakes and rivers shall be shown except where they conflict with data more applicable to the function of the chart.
- 21.6.2 Appropriate spot elevations and obstacles shall be shown.

Appropriate spot elevations and obstacles are those provided by the procedures specialist.

21.7 Magnetic variation

The average magnetic variation of the area covered by the chart shall be shown to the nearest degree.

21.8 Bearings, tracks and radials

- 21.8.1 Bearings, tracks and radials shall be magnetic, except as provided for in 21.8.2.
- 21.8.2 Where bearings, tracks or radials are given with reference to True North or Grid North, this shall be clearly indicated. When Grid North is used, its reference grid meridian shall be identified.

21.9 Aeronautical data

- 21.9.1 Aerodromes
- 21.9.1.1 All aerodromes that affect the terminal routings shall be shown. Where appropriate, a runway pattern symbol shall be used.
- 21.9.1.2 The elevation of the primary aerodrome to the nearest metre or foot shall be shown.
- 21.9.2 Prohibited, restricted and danger areas

Prohibited, restricted and danger areas shall be depicted with their identification.

- 21.9.3 Air traffic services system
- 21.9.3.1 The chart shall show components of the established air traffic services system including:
 - a) relevant radio navigation aids together with their identifications;
 - b) lateral limits of relevant designated airspace;
 - c) relevant significant points associated with standard instrument departure and arrival procedures;

Routes used in the vectoring of aircraft to and from the significant points may be shown.

d) transition altitude, where established;


- e) information associated with vectoring including:
- 1) minimum vectoring altitudes to the nearest higher 50 m or 100 ft, clearly identified;
- 2) lateral limits of minimum vectoring altitude sectors normally defined by bearings and radials to/from radio navigation aids to the nearest degree or, if not practicable, geographical coordinates in degrees, minutes and seconds and shown by heavy lines so as to clearly differentiate between established sectors;

In congested areas, geographical coordinates may be omitted in the interest of legibility.

- 3) distance circles at 20-km or 10-NM intervals or, when practicable, 10-km or 5-NM intervals shown as fine dashed lines with the radius indicated on the circumference and centred on the identified aerodrome main VOR radio navigation aid or, if not available, on the aerodrome/heliport reference point;
- 4) notes concerning correction for low temperature effect, as applicable;
- f) communications procedures including call sign(s) and channel(s) of the ATC unit(s) concerned.
- 21.9.3.2 A textual description of relevant communication failure procedures should be provided and should, whenever feasible, be shown on the chart or on the same page that contains the chart.

Page 109 of 133 4th Edition Rev: 00 Date: 28th October 2024

APPENDIX 1. MARGINAL NOTE LAYOUT



APPENDIX 2. ICAO CHART SYMBOLS

1. CATEGORY INDEX

OPOGRAPHY (1–18)	
Approximate contours	
Areas not surveyed for contour information or relief data incomplete	
Bluff, cliff or escarpment	
Coniferous trees	
Contours	
Gravel	••••••
Highest elevation on chart	
Lava flow	
Levee or esker	
Mountain pass	
Other trees	
Palms	
Relief shown by hachures	
Sand area	
Sand dunes	
Spot elevation (of doubtful accuracy)	••••••
Spot elevation	
Unusual land features appropriately labelled	
IYDROGRAPHY (19–46)	
Abandoned canal	
Canal	
Charted isolated rock	
Coral reefs and ledges	
Danger line (2 m or one fathom line)	
Dry lake bed	
Falls	
Glaciers and ice caps	
Lakes (non-perennial)	
Lakes (perennial)	
Large river (perennial)	
Rapids	
Reservoir	
Rice field	
Rivers and streams (non-perennial)	
Rivers and streams (unsurveyed)	
Rock awash	
Salt lake	
Salt pans (evaporator)	
Shoals	
Shore line (reliable)	
Shore line (unreliable)	
Small river (perennial)	
Spring, well or water hole	
Swamp	
Tidal flats	

Invested water feetures appropriately labelled	Symbo
nusual water features appropriately labelled	
Vash	
PUDE (47, 92)	
TURE (47–83)	
Built-up Areas (47–50)	
Buildings	
City or large town	
Town	
Village	
Railroads (51–56)	
Railroad (single track)	
Railroad (two or more tracks)	
Railroad (under construction)	
Railroad bridge	
Railroad station	
Railroad tunnel	
Wi-lovens and Dec. J. (57, 60)	
Highways and Roads (57–62)	
Dual highway	
Primary road	
Road bridge	
Road tunnel	
Secondary road	
Boundaries (international)	
Coast guard station	
Dam	
Fence	
Ferry	
Forest ranger station	
Fort	
Lookout tower	
Mine	
Mosque	
Nuclear power station	
Oil or gas field	
Outer boundaries	
Pagoda	
Pipeline	
Race track or stadium	
Ruins	
Tank farms	
Telegraph or telephone line (when a landmark)	
Temple	
ODROMES (84–95)	
· · · · · · · · · · · · · · · · · · ·	
Abandoned or closed aerodromeAerodrome for use on charts on which aerodrome classification is not	
ici cai cinc i ci abe chi charto chi minchi aci calcine ciabbilicaticii ib ilut	1 ~ M M 11 ~ C

Civil — Land	
Civil — Water	
Emergency aerodrome or aerodrome with no facilities	
Heliport	
Joint civil and military — Land	
Joint civil and military — Water	
Military — Land	
Military — Water	
Runway pattern in lieu of the aerodrome symbol	
Aerodrome data in abbreviated form which may be in association with aerodrome	ome symbols
Aerodrome symbols for Approach Charts (97 and 98)	
Aerodromes affecting the traffic pattern on the aerodrome on which the proced	lure is based
The aerodrome on which the procedure is based	
1	
DIO NAVIGATION AIDS (99–110)	
Basic radio navigation aid symbol	
Collocated VOR and DME radio navigation aids — VOR/DME	
Collocated VOR and TACAN radio navigation aids — VORTAC	
Compass rose	
Distance measuring equipment — DME	
DME distance	
Instrument landing system — ILS	
Non-directional radio beacon — NDB	
Radio marker beacon	
UHF tactical air navigation aid — TACAN	
VHF omnidirectional radio range — VOR	
VOR radial	
R TRAFFIC SERVICES (111–144) Advisory airspace — ADA	
Advisory route — ADR	
Aerodrome traffic zone — ATZ	
Air defence identification zone — ADIZ	
Altitudes/flight levels	
ATS/MET reporting point — MRP	
Change-over point — COP	
Control area, Airway, Controlled route	
Control zone — CTR	
Final approach fix — FAF	
Flight information region — FIR	
Reporting and Fly-by/Flyover functionality	
Scale-break (on ATS route)	
Uncontrolled route	
Visual flight path	

Airspace Classifications (126 and 127) Aeronautical data in abbreviated form to be used in association with air	space classification symbols
Airspace classifications	
Airspace Restrictions (128 and 129)	
International boundary closed to passage of aircraft except through air c	orridor
Restricted airspace (prohibited, restricted or danger area)	
Obstacles (130–136)	
Elevation of top/Height above specified datum	
Exceptionally high obstacle — lighted (optional symbol)	
Exceptionally high obstacle (optional symbol)	
Group obstacles	
Lighted group obstacles	
Lighted obstacle	
Obstacle	
Miscellaneous ((137–141)	
Isogonic line or isogonal	
Ocean station vessel (normal position)	
Prominent transmission line	
Wind turbine — unlighted and lighted	
Wind turbines — minor group and group in major area, lighted	
Visual Aids (142–144)	
Aeronautical ground light	
Lightship	
Marine light	
Marine light	61)
Marine light Ma	61)
Marine light	61)
Marine light	61)
Marine light Ma	61)
Marine light Ma	61)
Marine light Ma	51)
Marine light Ma	61)
Marine light Ma	51)
Marine light Ma	61)
Marine light Ma	51)
Marine light Ma	61)
Marine light Helicopter aleghting area on an aerodrome Hot spot Intermediate holding position Landing direction indicator (lighted) Landing direction indicator (unlighted) Obstacle light Pierced steel plank or steel mesh runway Point light Runway-holding position	51)
Marine light Hard Surface CHARTS (145–16 Alexandre Hard Surface (145–16 Marine light Hard Surface runway Marine light Hard Surface CHARTS (145–16 Marine light Hard Surface CHARTS (145–16 Marine light Marine light Hard Surface CHARTS (145–16 Marine light Hard Surface CHARTS (145–16 Marine light Marine light Marine light Hard Surface CHARTS (145–16 Marine light Marine light Hard Surface CHARTS (145–16 Marine light Marine light	51)
Marine light Helicopter alighting area on an aerodrome Hot spot Intermediate holding position Landing direction indicator (lighted) Landing direction indicator (unlighted) Obstacle light Pierced steel plank or steel mesh runway Point light Runway-holding position Runway visual range (RVR) observation site Stop bar. Stopway Taxiways and parking areas	61)
Marine light Hard Surface CHARTS (145–16 Alexandre Hard Surface (145–16 Marine light Hard Surface runway Marine light Hard Surface CHARTS (145–16 Marine light Hard Surface CHARTS (145–16 Marine light Marine light Hard Surface CHARTS (145–16 Marine light Hard Surface CHARTS (145–16 Marine light Marine light Marine light Hard Surface CHARTS (145–16 Marine light Marine light Hard Surface CHARTS (145–16 Marine light Marine light	61)

uilding or large structurelearway	
carpment	
Pole, tower, spire, antenna, etc.	
Railroad	
Stopway	
Ferrain penetrating obstacle plane	
Fransmission line or overhead cable	
Free or shrub	
Tee of siliub	
ITIONAL SYMBOLS FOR USE ON PAPER AND ELEC	TRONIC CHARTS (171-
Collocated DME fix and marker beacon	•
Collocated radio navigation aid and marker beacon	
OME fix	
Holding pattern	
Vinimum sector altitude	
Missed approach track	
Radio marker beacon	
Radio navigation aid	
Runway	
Ferminal arrival altitude	
LPHABETICAL INDEX	
LPHABETICAL INDEX	
LPHABETICAL INDEX	
sbandoned canal	
sbandoned canaldvisory airspace — ADA	
Abandoned canal	undary of two areas
Abandoned canal	undary of two areas
Abandoned canal	undary of two areas
Abandoned canal	undary of two areas
Abandoned canal	undary of two areas
bandoned canal	undary of two areas

Anchorage, sheltered	92
Antenna	163
Areas	
Built-up	
Not surveyed for contour information or relief data incomplete	
Prohibited	128
Restricted	
ATS/MET reporting point — MRP (compulsory, on request)	123
Bluff	4
Boundaries	
International	63
Outer	64
Building (on Aerodrome Obstacle Charts)	
Buildings	
Cable, overhead	166
Canal	29
Canal, abandoned	
Change-over point — COP	122
Charted isolated rock	
Chart, highest elevation on	
Chart symbols, electronic	
	171-1
Church	80
City or large town	47
Clearway — CWY	
Cliff	
Coast guard station	
Collocated DME fix and marker beacon	
Collocated radio navigation aid and marker beacon	
Collocated VOR and DME radio navigation aids — VOR/DME	
Collocated VOR and TACAN radio navigation aids — VORTAC	
Compass rose	
Coniferous trees	
Contours	-
Contours, approximate	
Control area — CTA	
Controlled route	
Control zone — CTR	
Control Zone — CTR	110
Coral reefs and ledges	
Culture	
Culture, miscellaneous	63-83

Compliance to Annex 04 – Aeronautical Charts Attachment No. IS-04-Att.

D	
Dam	67
Danger area	128
Danger line	43
Distance measuring equipment — DME	
DME distance	176
DME distance	
Collocated DME fix and marker beacon	
Dry lake bed	
Dual highway.	
Dunes, sand	
E	
Electronic chart symbols	108,
Liceronic chart symbols	171–
Elevation (of doubtful accuracy), spot	
Elevation, spot	
Escarpment	
Escarpment (on Aerodrome Obstacle Charts)	
Esker	
Falls Fence Ferry Final approach fix — FAF Flight information region — FIR	
Flight levels	
Forest ranger station	
Fort	79
G	
Gas field	70
Glaciers	
Gravel	8
Н	
Hard surface runway	
Helicopter alighting area on an aerodrome	
Heliport	

Compliance to Annex 04 – Aeronautical Charts Attachment No. IS-04-Att.

Hiş	ghest elevation on chart	12
Hiş	ghway, dual	57
Hiş	ghways and roads	57-62
Но	lding pattern	173
Но	t spot	161
	drography	19-46
[
		40
	caps	42
	trument landing system — ILS	108
	ermediate holding position	160
	ernational boundary closed to passage of aircraft except through air corridor	129
	ersection INT	121
ISO	gonic line or isogonal	138
<u>,</u>		
		20
	e bed, dry	39
Lake		22
	Non-perennial	32
	Perennial	31
Land		
	Civil	84
	Military	86
	Joint civil and military	88
Land	d features appropriately labelled, unusual	10
Lan	ding direction indicator	
	Lighted	156
		156
	Unlighted	157
_	ge river (perennial)	23
_	ge structure	164
	a flow	5
	ges	22
	ee	9
	ıtship	144
Loo	kout tower	74
Mar	rine light	142
Mir	ne	75
Mir	nimum sector altitude — MSA	171
	cellaneous symbols	
	Air Traffic Services	137-1
	Culture	63-83
Mis	sed approach track	174
Mo	sque	81
Mo	untain pass	11

Compliance to Annex 04 – Aeronautical Charts Attachment No. IS-04-Att.

	al radio beacon — NDB
Nuclear power	er station
Obstacle ligh	
Obstacles	
Ocean station	vessel
Overhead cab	le
Pagoda	
-	
	5
	plank or steel mesh runway
_	
	ı, nuclear
•	ea
	ansmission line
Race track	
	r beacon
	tion aid
	ed radio navigation aid and marker beacon
	· · · · · · · · · · · · · · · · · · ·
	ed VOR and DMEed VOR and TACAN
Naulo Haviga	tion aids
`	Aerodrome Obstacle Charts)
	ılture)
-	gamplata
	by healthy ac
	by hachures
	d fly-by/flyover functionality
	rspace (prohibited, restricted or danger area) and common boundary of two areas
	29

Compliance to Annex 04 – Aeronautical Charts Attachment No. IS-04-Att.

35

River (Perennial), small	36 24 23
River (Perennial), small	
(Perennial), large	
Non-perennial	
Unsurveyed2	25
D 11.11	26
Road bridge	61
Road, primary	58
	59
Roads (Highways and Roads)	57-62
Road tunnel	62
Rock awash	45
Rock, charted isolated	44
Route	
Advisory — ADR	
	118 113
	114
	78
	175
	145
	147
	159
	153
C C	
S	
Salt lake	33
	34
Sand area	7
	6
	120
•	59
Sheltered anchorage	92
Shoals	41
Reliable	19
Unreliable	20
Shrub	162
Small river (perennial)	24
Spire	163
Spot elevation	13
Spot elevation (of doubtful accuracy)	14
Spring (perennial or intermittent)	37
Stadium	77
·	146
Stool plank, piorood	146
Steel plank, pierced	158
Stop bar	
Stop bar	148
Stop bar	
Stop bar	148

Swamp.....

T


	121
	106, 1
Tank farms	71
Taxiways	149
Telegraph or telephone line (when a landmark)	66
Temple	83
Terminal arrival altitude — TAA	172
Terrain penetrating obstacle plane	167
Tidal flats	21
Topography	1-18
Tower	1 10
Lookout	74
On Aerodrome Obstacle Charts	163
Town	48
Town, large	
•	
Trail	00
Transmission line	1.00
On Aerodrome Obstacle Charts	
Prominent	137
Tree	
Coniferous	
On Aerodrome Obstacle Charts	162
Other	16
JHF tactical air navigation aid — TACAN	106,
Uncontrolled route	114
Jnpaved runway	147
Jnusual land features appropriately labelled	10
Jnusual water features appropriately labelled	46
V	
	121
	101,
-8	49
	142-
Visual flight path	119
/OR	121
OR check-point	152
/OR/DME	121
VOR/DME (collocated VOR and DME radio navigation aids)	103
VOR radial	105
VORTAC	121
VORTAC (collocated VOR and TACAN radio navigation aids)	107
VOR (VHF omnidirectional radio range)	101
OK (111 Onini Ground radio range)	101

Compliance to Annex 04 – Aeronautical Charts Attachment No. IS-04-Att.

Symbol No.

\mathbf{W}

Wash	40
Water	
Civil	85
Military	87
Joint civil and military	89
Water features appropriately labelled, unusual	46
Water hole (perennial or intermittent)	37
Waypoint — WPT	121
Well (perennial or intermittent)	37
Wind turbine, unlighted and lighted	140
Wind turbines, minor group and group in major area, lighted	141



CULTURE

BUILT-UP AREAS

47	City or large town	
48	Town	o
49	Village	0
50	Buildings	= I

HIGHWAYS AND ROADS

57	Dual highway	=====
58	Primary road	
59	Secondary road	
60	Trail	
61	Road bridge	
62	Road tunnel	→

MISCELLANEOUS (Cont.)

69	Pipeline	Pipeline
70	Oil or gas field	A
71	Tank farms	•.••
72	Nuclear power station	*
73	Coast guard station	•
74	Lookout tower	(A)
75	Mine	父
76	Forest ranger station	±
77	Race track or stadium	
78	Ruins	٨
79	Fort	Ħ
80	Church	4
81	Mosque	γ
82	Pagoda	₽
83	Temple	血

RAILROADS

51	Railroad (single track)	
52	Railroad (two or more tracks)	##
53	Railroad (under construction)	
54	Railroad bridge	₩
55	Railroad tunnel	-0 e-
56	Railroad station	+ = + +

MISCELLANEOUS

63	Boundaries (international)	
64	Outer boundaries	
65	Fence	xxx
66	Telegraph or telephone line (when a landmark)	-TT-
67	Dam	-(
68	Ferry	J0/

AERODROMES

84	Civil	Land	\rightarrow
85	Civil	Water	(
86	Military	Land	0
87	Military	Water	(3)


88	Joint civil and military Land	\ODES
89	Joint civil and military Water	@
90	Emergency aerodrome or aerodrome with no facilities	0
91	Abandoned or closed aerodrome	\otimes

92	Sheltered anchorage	Ţ
93	Aerodrome for use on charts on which aerodrome classification is not required e.g. Enroute Charts	Ф
94	Heliport Note.— Aerodrome for the exclusive use of helicopters	H

Note.— Where required by the function of the chart, the runway pattern of the aerodrome may be shown in lieu of the aerodrome symbol, for example:



AERODROMES (Cont.) AERODROME DATA IN ABBREVIATED FORM WHICH MAY BE IN ASSOCIATION WITH AERODROME SYMBOLS (Reference: 16.9.2.2 and 17.9.2.2)



AERODROME SYMBOLS FOR APPROACH CHARTS

Aerodromes affecting the traffic pattern on the aerodrome on which the procedure is based

Aerodromes affecting the traffic pattern on the aerodrome on which the procedure is based

The aerodrome on which the procedure is based

RADIO NAVIGATION AIDS*


			RADIO NA	/IGATI	ON AIDS			
99	Basic radio navigation ai Note.— This symbol ma without a box to		0	107	Collocated VOR and TACAN radio navigation aids	VORTAC	•	
100	Non-directional radio bea	acon NDB				PLAN VIEW	PLAN VIEW B	
101	VHF omnidirectional radi	io range VOR	0			FRONT COURSE		
02	Distance measuring equi	ipment DME	⊡	108	Instrument landing system ILS	BACK COURSE PROFILE		
03	Collocated VOR and DM radio navigation aids	E VOR/DME	\Box			Electronic		
1		Distance in kilomet (nautical miles) to DI				GLIDE PATH		
04	DME distance	Identification radio navigation	of — KAV		Radio marker beacon	Elliptical	\bigcirc	
05	VOR radial	Radial bearing fro and identification of, V		109	Nauv market beacen	Bone Shape	\approx	
06	UHF tactical air navigation	on aid TACAN	∇		Note.— Marker beacon may be shown by outline, or stipple, or both.		pple, or both.	


110	ELL BUTTON	VOR	0
	Compass rose To be orientated on the chart in Compass rose to be used as appropriate in combination with the following	VOR/DME	$\overline{\mathbf{C}}$
	accordance with the alignment of the station (normally Magnetic North)	TACAN	∇
	Note.— Additional points of compass may be added as required.	VORTAC	♥


^{*}Note.— Guidance material on the presentation of radio navigation aid data is given in the Aeronautical Chart Manual (Doc 8697).

Compliance to Annex 04 – Aeronautical Charts Attachment No. IS-04-Att.

AIR TRAFFIC SERVICES








Compulsory Change-over point COP Δ 26 To be superimposed on the appropriate route symbol at right angles to the route ATS/MET Final approach fix * 122 MRP 124 FAF 123 reporting point 36 On request Δ


AIR TRAFFIC SERVICES (cont.)

	Procedure altitudes/flight levels	Altitude/flight level "window"	17 000 10 000	FL 220 10 000
		"At or above" altitude/flight level	7 000	FL 070
125		"At or below" altitude/flight level	5 000	FL 050
120		"At" altitude/flight level	3 000	FL 030
		"Recommended" altitude/flight level	5 000	FL 050
		"Expected" altitude/flight level	Expect 5 000	Expect FL 050
	,			

AIRSPACE CLASSIFICATIONS



Aeronautical data in abbreviated form to be used in association with airspace classification symbols:



AIRSPACE RESTRICTIONS

12	Restricted airspace (prohibited, restricted or danger area)		Common boundary of two areas	!!!!!!!!!!!	
	Note.— The angle and density of rulings may be varied according to scale and the size, shape and orientation of the area.				
12	International boundary closed to passage of aircraft except through air corridor		% ///) (/////		

OBSTACLES

130	Obstacle	٨
131	Lighted obstacle	汰
132	Group obstacles	\ <u>\</u> \.\
133	Lighted group obstacles	<u>``</u>

134	Exceptionally high obstacle (optional symbol)	<u> </u>
135	Exceptionally high obstacle – lighted (optional symbol) Note.— For obstacles having a height of the order of 300 m (1 000 ft) above terrain.	<u> </u>
136		specified datum n parentheses)

$\begin{array}{c} Compliance \ to \ Annex \ 04-Aeronautical \ Charts \\ Attachment \ No. \ IS-04-Att. \end{array}$

MISCELLANEOUS

137	Prominent transmission line	~~~T~~~~T~~~
138	Isogonic line or isogonal	3° E
139	Ocean station vessel (normal position)	

140	Wind turbine — unlighted and lighted	十	*
141	Wind turbines — minor group and group in major area, lighted	推	* *

VISUAL AIDS

142		Marine light		Aarine light		Note 1.— Marine alternating lights are red and white unless otherwise indicated. Marine lights are white unless colours are stated.			e f.		
14	42	Note 2.— Characteristics are to be indicated as follows:	В	Alternating Blue Fixed		Fl G Gr		Occ R SEC	Occulting Red Sector	sec (U) W	Second Unwatched White
1	43	Aeronautical ground light	*	Electronic		144	Lightship				*

SYMBOLS FOR AERODROME/HELIPORT CHARTS

145	Hard surface runway		
146	Pierced steel plank or steel mesh runway		
147	Unpaved runway		
148	Stopway	SWY	
149	Taxiways and parking areas		
150	Helicopter alighting area on an aerodrome		Э
151	Aerodrome reference point	ARP	+
152	VOR check-point		◆0
153	Runway visual range (RVR) observation s	ite	\triangleright

154	Point light		•
155	Obstacle light	柒	
156	Landing direction indicator (lighted)	Ť	
157	Landing direction indicator (unlighted)	Т	
158	Stop bar		•••
159	Runway-holding position Note. — For application, see Annex 14, Volume	Pattern A Pattern B	=== ===
160	Intermediate holding position Note.— For application, see Annex 14, Volume		
161	Hot spot Note.— Hot spot location to be circled.		

SYMBOLS FOR AERODROME OBSTACLE CHARTS - TYPE A, B AND C

		Plan	Profile
162	Tree or shrub	*	Identification
163	Pole, tower, spire, antenna, etc.	0	number
164	Building or large structure	-	1
165	Railroad	+	.
166	Transmission line or overhead cable	—т—т—	

			Plan	Profile
167	Terrain penetrating obst	acle plane	\bigcirc	
168	Escarpment		111111	,,,,,,,
169	Stopway	SWY]]
170	Clearway	CWY]	

Page 128 of 133 4th Edition Rev: 00 Date: 28th October 2024

ADDITIONAL SYMBOLS FOR USE ON PAPER AND ELECTRONIC CHARTS

	PLAN VIEW		Electronic
171	Minimum sector altitude Note.—This symbol may be modified to reflect particular sector shapes.	MSA	8500' 10,500'
172	Terminal arrival alfitude Note.—This symbol may be modified to reflect particular TAA shapes.	TAA	7000 2650
173	Holding pattern		
174	Missed approach track		>
	PROFILE		
175	Runway		
176	Radio navigation aid (type of aid and its use in the procedure to be annotated on top of the symbol)		
177	Radio marker beacon (type of beacon to be annotated on top of the symbol)		
178	Collocated radio navigation aid and marker beacon (type of aid to be annotated on top of the symbol)		
179	DME fix (distance from DME and the fix use in the procedure to be annotated on top of the symbol)		
180	Collocated DME fix and marker beacon (distance from DME and the type of beacon to be annotated on top of the symbol)		

APPENDIX 3. COLOUR GUIDE

(Ref. 2.11.1)

CHART SYMBOLS Culture, except highways and roads; outlines of large cities, grids and graticules; spot elevations; danger lines and off-shore rocks; names and lettering except for aeronautical and hydrographic features BLACK BLACK Built-up areas of cities Stipple BLACK Half-tone Optional Highways and roads colours RED Built-up areas for cities (alternative to black stipple) YELLOW Contours and topographic features: Items 1 through 10 of Appendix 2 Hydrographic features: Items 39 through 41 of Appendix 2 BROWN Shore lines, drainage, rivers, lakes, bathymetric contours and other hydrographic features BLUE including their names or description BLUE Open water areas Half-tone BLUE Salt lakes and salt pans Stipple BLUE Large non-perennial rivers and non-perennial lakes Stipple MAGENTA Aeronautical data, except for Enroute and Area Charts - ICAO, where different Optional colours may be required. Both contours may be used on the same sheet but, where only one colour is used, dark blue is preferred colours DARK BLUE

Page 130 of 133 4th Edition Rev: 00 Date: 28th October 2024

CHART SYMBOLS (Cont.) GREEN Woods GOLDEN BUFF Areas which have not been surveyed for contour information Optional WHITE HYPSOMETRIC TINTS WHITE SEPIA Tint for extreme elevations VIOLET ORANGE BROWN Tint for higher range elevations or BUFF YELLOW Tint for middle range elevations BUFF

GREEN

WHITE

BLUE-GREEN

LIGHT

Optional colours

Optional colours

Tint for lower range elevations

Tint for areas below sea level


GREEN

BLUE-GREEN

Note.— Basic tints are identical to those specified for the International Map of the World.

APPENDIX 4. HYPSOMETRIC TINT GUIDE

(Alternative systems, reference 2.12.2)



Note 1.— These tints are identical to those specified for the International Map of the World.

Note 2.— Elevations have not been associated with tints of either system in order to allow for flexibility in their selection.

APPENDIX 5. SHEET LAYOUT FOR THE WORLD AERONAUTICAL CHART – ICAO 1:1 000 000

